

INFORMATIONAL PROPOSAL

(For information only, not to be used for bidding)

NEBRASKA DEPARTMENT OF ROADS
LETTING DATE: March 10, 2016

CALL ORDER: 300
CONTROL NO. SEQ. NO.: 00922 000
TENTATIVE START DATE: 07/05/2016
LOCATION: DISTRICTS 2 & 3 DISTRICTWIDE CURB RAMPS
IN COUNTIES: COLFAX, CUMING, DODGE, PLATTE

CONTRACT ID: 0922
PROJECT NO.: MISC-STWD(1076)
CONTRACT TIME: 509 Calendar Days

BIDDER

GROUP 3 CONCRETE PAVEMENT

NOTES

THE TOTAL AMOUNT OR WORK WHICH WILL BE ACCEPTED IN
THIS LETTING IS LIMITED TO \$ _____

THE NUMBER OF GROUP _____ CONTRACTS WHICH WILL BE
ACCEPTED IN THIS LETTING IS LIMITED TO _____.

NOTICE TO ALL BIDDERS

To report bid rigging activities, call: 1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free “hotline” Monday through Friday, 8:00 a.m. to 5:00 p.m. eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the “hotline” to report such activities.

The “hotline” is part of the DOT’s continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

LETTING QUESTIONS

Prior to the letting, any questions pertaining to the Special Provisions or the Plans for this project should be submitted to NDOR in a written format through the Bid Express (BidX) website at <https://www.bidx.com/ne/lettings>. Likewise, NDOR will post answers exclusively to the BidX website. All official answers will be identified as “Authorized by NDOR.” **Questions will not be answered verbally.**

STATE OF NEBRASKA
DEPARTMENT OF ROADS

Required Provisions Supplemental to the

Standard Specifications for Highway Construction

I. Application

These contract provisions shall apply to all work performed on the contract by the contractor with his own organization and with the assistance of workmen under his immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

The contractor shall insert in each of his subcontracts all of the stipulations contained in the Special Provisions and these Required Provisions.

A breach of any of the stipulations contained in these Required Provisions may be grounds for termination of the contract.

II. Equal Opportunity

1. **Selection of Labor**

During the performance of this contract, the contractor shall not discriminate against labor from any other state.

2. **Nebraska Fair Employment Practices Act**

The contractor shall not discriminate against any employee or applicant for employment, to be employed in the performance of this contract with respect to his hire, tenure, terms, conditions, or privileges of employment, because of his race, color, religion, sex or national origin. The contractor agrees to post in a conspicuous place or places a notice to be provided by the State Highway Department which sets forth excerpts of the Act.

3. **Nebraska Equal Pay Act**

The contractor shall not discriminate on the basis of sex by paying wages to employees of one sex at a lesser rate than the rate paid to employees of the opposite sex for comparable work on jobs which have comparable requirements. An abstract of the Act is included on the notice which is provided by the State Highway Department.

April 4, 1995

III. Employment of Labor

1. General

No person under the age of sixteen (16) years, and no one whose age or physical condition is such as to make his employment dangerous to his health or safety, or to the health and safety of others shall be employed on any project. This paragraph shall not be construed to deny the employment of older people or physically handicapped persons, otherwise employable, where such persons may be safely assigned to work which they can ably perform.

No person currently serving sentence to a penal or correction institution shall be employed on any project.

Except as specifically provided under this section, workers who are qualified by training or experience to be assigned to projects of this character shall not be discriminated against on any grounds whatsoever.

2. Payrolls

Payrolls and basic records relating thereto will be maintained during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working on the site of the work.

The contractor's and subcontractor's payroll records shall be available for inspection by authorized representatives of the State Highway Department and authorized representatives of Federal Agencies.

The wages of labor shall be paid in legal tender of the United States, except that this condition will be considered satisfied if payment is made by a negotiable check, on a solvent bank, which may be cashed readily by the employee in the local community for the full amount, without discount or collection charges of any kind. Where checks are used for payment the contractor shall make all necessary arrangements for them to be cashed and shall give information regarding such arrangements.

No fee of any kind shall be asked or accepted by the contractor or any of his agents from any person as a condition of employment on the project.

No laborers shall be charged for any tools used in performing their respective duties except for reasonably avoidable loss or damage thereto.

Every employee on the work covered by this contract shall be permitted to lodge, board and trade where and with whom he elects and neither the contractor nor his agents, nor his employees shall directly or indirectly require as a condition of employment that an employee shall lodge, board or trade at a particular place or with a particular person.

No charge shall be made for any transportation furnished by the contractor or his agents to any person employed on the work.

April 4, 1995

No individual shall be employed as a laborer on this contract except on a wage basis, but this shall not be construed to prohibit the rental of teams, trucks or other equipment from individuals. No such rental agreement, or any charges for feed, gasoline, supplies, or repairs on account of such agreement, shall cause any deduction from the wages accruing to any employee except as authorized by the regulations hereinbefore cited.

IV. Safety and Accident Prevention

In the performance of this contract, the contractor shall comply with all applicable Federal, State and local laws governing safety, health and sanitation. The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions, on his own responsibility or as the contracting officer may determine, reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.

V. Subletting or Assigning the Contract

The contractor shall perform with his own organization contract work amounting to not less than 30 percent of the total contract amount except that any items designated in the contract as "Specialty Items" may be performed by subcontract and the amount of any such "Specialty Items" so performed may be deducted from the total contract amount before computing the amount of work required to be performed by the contractor with his own organization.

Any items that have been selected as "Specialty Items" for the contract are listed as such in the Special Provisions found elsewhere in the contract.

No portion of the contract shall be sublet, assigned, or otherwise disposed of except with the written consent of the contracting officer or his authorized representative. Requests for permission to sublet assign or otherwise dispose of any portion of the contract shall be in writing and accompanied by a showing that the organization which will perform the work is particularly experienced and equipped for such work. The contractor shall give assurance that the minimum wage for labor as stated in his proposal shall apply to labor performed on all work sublet, assigned or otherwise disposed of in any way. Consent to sublet, assign or otherwise dispose of any portion of the contract shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract.

April 4, 1995

**SPECIAL PROVISIONS
FOR
STATE
PROJECT NO. MISC-STWD(1076)**

GENERAL CONDITIONS

Bids for the work contemplated in this proposal form will be received at the office of the Nebraska Department of Roads in Room 104 of the Central Office Building at 1500 Highway 2 at Lincoln, Nebraska, on March 10, 2016, until 1:30 P.M.

- a. Bids submitted by mail should be addressed to the Nebraska Department of Roads, c/o Contract Lettings Section, P.O. Box 94759, Lincoln, NE 68509-4759.
- b. Bids submitted electronically over the internet, shall be submitted using www.bidx.com.

The 2007 Edition of the Standard Specifications for Highway Construction, including all amendments and additions thereto effective at the date of the contract, are made a part of these Special Provisions, through reference.

The Required Provisions dated April 4, 1995, are attached to and are a part of this proposal form.

The attention of bidders is directed to the Required Provisions covering subletting or assigning the contract.

The proposal contains a statement that the contractor is complying with, and will continue to comply with, fair labor standards in the pursuit of his business and in the execution of the work contemplated in this proposal.

Fair labor standards shall be construed to mean such a scale of wages and conditions of employment as are paid and maintained by at least fifty per cent of the contractors in the same business or field of endeavor as the contractor filing this proposal.

BIDDING PROPOSAL FORMS FOR THIS WORK WILL BE ISSUED AND A
CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR CONCRETE
PAVEMENT OR SPECIALTY.

STATUS OF UTILITIES

The following information is current as of February 3, 2016.

Aerial and/or underground utilities may exist within the limits of this project. The Contractor shall determine to his satisfaction the extent of occupancy of any utility facilities located within the project construction areas and the extent of conflict with the proposed work under this contract.

At this time, no utilities have been required to relocate their facilities.

Any utility adjustments or interruption of service for the convenience of the Contractor shall be the sole responsibility of the Contractor.

To arrange for utilities to locate and flag their underground facilities, contact Diggers Hotline of Nebraska at 1-800-331-5666, or dial 811.

Any work necessary will be concurrent with construction.

STATUS OF RIGHT OF WAY

The right of way for this project has been acquired and physical possession is held by the State of Nebraska and ready for the Contractor's use, except tracts listed below:

Unacquired Right-of-Way Tracts as follows:

Tract Number	Status of Tract	Hearing Date
None	None	None

Right-of-Way Tracts with Pay Items:

Tract Number	Pay Items
None	None

- No encroachments on the old right of way.
- Acquisition of right of way is not required for this project.

**SPECIAL PROSECUTION AND PROGRESS
(General Requirements)**

I. Project Prosecution

The Contractor shall limit all operations to the following area defined as:

- Public Right of Way.
- Within one (1) foot of the grading limits, and
- Within five (5) feet of the limits of construction when on or inside the pavement.

The Contractor shall notify the NDOR prior to commencing removal or grading operations if the lines and/or grades of the proposed curb ramps, maneuvering/landing pad, or transition walk interfere with or pose risk of damage to adjacent retaining walls, trees, structures, or other similar objects, or will require grading slopes steeper than 4H: 1 V to tie-in with the existing ground within the right of way or grading beyond three (3) feet of the limits of the proposed construction.

Pedestrian access to adjacent businesses and residences shall be maintained during work on this project. As the Contractor develops their detailed work plan they will need to consider the access needs to each of these properties. All work described under this Access to Adjacent Properties during Construction item shall be considered subsidiary to other bid items of work. The contractor shall be responsible for notifying businesses and residents a minimum of 2 days before commencing removal operations.

No equipment, materials, debris, etc., shall be stored outside of this defined area at any time without prior written permission from the NDOR. The Contractor is responsible for completing the work within the Contract specified timeframe. **No work will be allowed adjacent to or within one (1) block of a school when school is in session without prior written permission from the NDOR.** Additional time will not be granted due to delays or production loss because of scheduling conflicts or other unforeseen events associated with other projects, including other NDOR projects, local projects, unless approved in writing by the NDOR.

The Contractor will be required to maintain traffic on all public streets during work on this project. If a temporary lane closure will be required to complete the work, it shall be approved by NDOR prior to the closure. Appropriate traffic control shall be provided as directed by NDOR.

In high pedestrian traffic areas, the NDOR reserves the right to limit the work to one corner of the intersection at one time to maintain pedestrian access around the intersection. The NDOR reserves the right, but is not obligated, to increase the number of intersections under construction if additional crews are utilized. The amount, if any, of additional intersections allowed shall be at the sole discretion of the NDOR and may be modified throughout the project.

II. Project Scheduling

The Time Allowance for this project is 509 Calendar Days. The Start Date is July 5, 2016, and the completion date is November 25, 2017. In this two construction season project, the periods when work may occur are July 5, 2016, to November 26, 2016 (a 145 calendar day period), and from April 3, 2017, to November 25, 2017 (a 237 calendar period). There are a total of 302 calendar days of work for the **8 Work Areas** on this project.

The project is divided into **8 work areas** and each work area has its specific **time allowance**, shown in **bold type**. Each individual intersection grouping within a work area has its own estimated individual time allowance shown in (xx). The 8 areas of work and their individual time allowances are as follows:

Work Area	Time Allowance (Calendar Days)	Corner Location
#1 – Fremont (US-77)	41	
W. Washington } (21 CD)		NE
W. Jackson } (21 CD)		NW
W. 16 th }		SW
W. Jackson } (20 CD)		SE, NE
W. Linden } (20 CD)		SE
W. 16 th }		NE
	* * * * *	
#2 – North Bend	24	
N-79/9 th } (10 CD)		NE
US-30/N-79 } (14 CD)		SW
US-30/N-79 }		SE, NE
	* * * * *	

Work Area	Time Allowance (Calendar Days)	Corner Location
#3 – Beemer L20A/2 nd	10 (10 CD)	SW, SE
* * * * *		
#4 – Columbus	50	
US-81/45 th Ave } US-81/39 th Ave } US-81-36 th Ave }	(25CD)	NE NE NW
US-81/36 th Ave } US-30/10 th Ave } US-81/36 th Ave }	(15 CD) (10 CD)	SW SE SE
* * * * *		
5 – Monroe N-22/Ziegler	10 (10 CD)	SE, NE
* * * * *		
6 – Schuyler (N-15)	63	
4 th } 8 th } 10 th }	(14 CD)	NW NW SW
4 th } 5 th } 9 th }	(21 CD)	SW NW SW
11 th } 4 th } 5 th }	(14 CD)	SW SE SE
4 th } 11 th }	(14 CD)	NE SE
* * * * *		
7 – West Point (N-32)	59	
Monroe } Ash } Oak } River }	(21 CD)	NW NW NE NE
Maple } Oak } River }	(14 CD)	NW NW NW
Monroe } Oak } River }	(14 CD)	SW SW SE
Maple } River }	(10 CD)	SW SW
* * * * *		

Work Area	Time Allowance (Calendar Days)	Corner Location
8 – Wisner (US-275)	45	
16 th	} (10 CD)	SE
14 th		SE
13 th		SE
15 th	} (10 CD)	SW
11 th		SW
7 th		SW
16 th	} (10 CD)	NW
15 th		NW
14 th		NW
16 th	} (15 CD)	NE
14 th		NW
13 th		NE
7 th		NW

It is the intent of this project to complete the curb ramps in each individual **Work Area** in a timely manner in order to minimize disruption to a community’s vehicular and pedestrian traffic.

The Contractor will be allowed to perform concurrent work in **Work Areas 1-8**. However, when working in an individual **Work Area**, the Contractor will only be allowed to work in one intersection grouping at a time, unless otherwise directed by the Engineer.

For each of the 8 individual **Work Areas**, all work, except seeding/sodding, shall be completed in that intersection grouping before beginning work in another intersection grouping.

For all curb ramp areas with pavement removal and concrete pavement replacement, regardless of size, the Contractor shall be required to complete these two operations in 3 calendar days at each curb ramp location within an intersection grouping.

All areas disturbed in 2016 will be seeded/sodded by the end of the 2016 construction season. The remainder of the seeding/sodding shall be completed at the end of the project, unless otherwise directed by the Engineer.

If the curb ramp work within an individual Work Area is suspended due to the winter shut-down period, those curb ramp areas that have been completed prior to the shut-down period shall be seeded/sodded, as directed by the Engineer.

Work in Fremont shall not be performed during John C. Fremont Days in either 2016 or 2017. John C. Fremont Days are scheduled for July 8-10, 2016, and July 14-16, 2017.

The Contractor will be required to submit a construction schedule to the Engineer for review prior to beginning any work. The Contractor will also be required to notify the Engineer one week prior beginning work in any of the 8 specified Work Areas.

III. Internal Liquidated Damages

All work shall be completed in each of the 8 Work Areas within its specified time allowance, as shown in **Section II Project Scheduling**. If the Contractor fails to complete all work within a Work Area within its specified time allowance, the Contractor will be assessed a \$250/calendar

day internal liquidated damage assessment. Each assessment shall begin on the next day after the specified time allowance (i.e., 24 CD + 1 => Assessment begins on the 25th CD). This assessment has not been provided for elsewhere in the contract and shall be in addition to other liquidated damages that are part of the contract. The \$250/calendar day assessment was determined by administrative decision.

If concurrent work on intersection groupings within any of the eight Work Areas is approved by the Engineer, the Time Allowance (# of CD) for that specific Work Area will have to be adjusted accordingly by the Engineer to reflect the appropriate reduction of Calendar Days for that Work Area.

Additionally, if the Contractor fails to complete the pavement removal/concrete pavement replacement operations at any curb ramp location within the 3 calendar day allowed (see **Section II**), the Contractor shall be responsible for the traffic control items associated with that curb ramp location, as directed by the Engineer.

SPECIAL PROSECUTION AND PROGRESS (ADA Accessibility)

The Project Manager will develop a traffic control plan for the project that will include signing for pedestrians using the sidewalks within the project limits that will direct the pedestrians to accessible routes. All sidewalk signing, as directed by the Engineer, will be accomplished using standard Type II barricades (not cones) and NDOR supplied signs attached to the Type II barricades. The bid items for this sidewalk signing will be Sign Days and Type II Barricades.

SPECIAL PROSECUTION AND PROGRESS (Form Work for Ramps)

The joint between the ramp and landing shall be formed prior to placement of the concrete. Only pouring either the ramp or landing separately or use of a false form to be removed after strike off is acceptable. The formed area shall comply with the acceptable slope and dimensions required by the ADA. If a false form is used, the false form shall be at least 42" in length, secured in such a manner as to provide support for strike-off tools, and shall be removed after initial strike-off. The use of grade stakes along this joint is not acceptable.

SPECIAL PROSECUTION AND PROGRESS (Pedestrian Push Button at Signals)

At signalized intersection locations where curb ramp work is completed, the new ramps and walks shall be completed such that access to the Pedestrian Push Buttons are accessible. This would require that a concrete surface is within 10 inches of the button location and that the button is within reach of a person in a wheelchair. If the button is not within reach, notify the NDOR representative so that relocation can be scheduled under another contract.

**SPECIAL PROSECUTION AND PROGRESS
(Access to Adjacent Properties During Construction)**

Pedestrian access to adjacent businesses and residences shall be maintained during work on this project. As the Contractor develops their detailed work plan they will need to consider the access needs to each of these properties. All work described under this Access to Adjacent Properties during Construction item shall be considered subsidiary to other bid items of work. The Contractor shall be responsible for notifying businesses and residents a minimum of 2 days before commencing removal operations.

ENVIRONMENTAL COMMITMENT

Control No.: 00922 **Project No.:** MISC-STWD(1076)
Project Name: District 1, 2 & 3 - Districtwide Curb Ramps

Below are the Conservation Conditions that will be required for this project. All conditions and regulations of any permit obtained for this project will be followed by the Contractor.

(Responsible Party for the measure is found in parentheses)

No wetland impacts are anticipated for this project; however, if impacts are found during design, the required permits would be obtained prior to letting. NDOR Environmental would notify FHWA of the change in impacts. (NDOR Environmental, NDOR Design).

The Contractor shall not stage, store, waste or stockpile materials and equipment in undisturbed locations, or in known/potential wetlands and/or known/potential streams that exhibit a clear “bed and Bank” channel. Potential wetland areas consist of any area that is known to pond water, swampy areas or areas supporting known wetland vegetation or areas where there is a distinct difference in vegetation (at lower elevations) from the surrounding upland areas. (Contractor, NDOR District)

Contact Person: Kimberly Baker, Highway Environmental Biologist, (402) 479-4544

Encountering Unexpected Waste

If contaminated soils and/or water or hazardous materials are encountered, then all work within the immediate area of the discovered hazardous material shall stop until NDOR/FHWA is notified and a plan to dispose of the Hazardous Materials has been developed. Then NDEQ shall be consulted and a remediation plan shall be developed for this project. The potential exists to have contaminants present resulting from minor spillage during fueling and service associated with construction equipment. Should contamination be found on the project during construction, the NDEQ shall be contacted for consultation and appropriate actions to be taken. The Contractor is required by NDOR's Standard Specification Section 107 (Legal Relations and Responsibilities to the Public) to handle and dispose of contaminated material in accordance with applicable laws. (Contractor)

Contact Person: Wendy Austin, Highway Environmental Biologist, (402) 479-3632

**SPECIAL PROSECUTION AND PROGRESS
(Migratory Birds)
(A-42-1112)**

The Department of Roads will, to the extent practicable, schedule the letting of projects such that clearing and grubbing can occur outside of the primary nesting season in Nebraska which has been determined to generally occur between April 1 and September 1. Work on structures, such as but not limited to bridges and culverts, should occur outside the primary swallow nesting season, April 15 to September 30, unless approved methods of avoiding nesting have been taken on the bridge and/or culvert structures. The nesting dates above are a guide only, nesting can occur outside of those dates. Work outside of those dates is not exempt from compliance with the Migratory Bird Treaty Act.

The Contractor shall, to the extent possible, schedule work on structures, such as but not limited to bridges and culverts, and clearing and grubbing activities to occur outside the primary nesting season in Nebraska. However, if circumstances dictate that project construction or demolition must be done when nesting migratory birds may be present, a survey of the number of active nests and species of birds shall be conducted by qualified personnel representing the Contractor, and assisted by the Project Manager (PM), NDOR Environmental Section staff, or the United States Department of Agriculture (USDA) Animal and Plant Health Inspection Service (APHIS) - Wildlife Services Office. If the survey finds that nests will be impacted by the proposed construction, the Contractor may be responsible for delays.

The following guidance is provided for compliance with the Migratory Bird Treaty Act for construction of NDOR projects:

1. The Contractor shall submit a plan to the NDOR regarding how he intends to accomplish bridge demolition or clearing and grubbing of the project to avoid conflict with nesting migratory birds.
2. The Contractor must submit a temporary erosion control plan tailored to fit the plan for clearing and grubbing.
3. If construction operations result in unavoidable conflict with nesting migratory bird's eggs or young, which will result in "taking" nests and their contents, the Contractor should notify the NDOR Project Manager (PM). The PM shall notify the Environmental Section of Planning and Project Development by telephone at 402-479-4766.
4. The NDOR Environmental Section will then determine if assistance in conducting the survey will be provided by the NDOR Environmental Section (if available) or from the USDA APHIS - Wildlife Services Office and arrange for assistance with the survey of nest numbers, bird species, etc. Results of the survey shall be maintained by the NDOR until project completion.
5. If the nesting survey is required, and the project was awarded prior to the nesting season, and the Contractor did not accomplish clearing/grubbing and/or work on bridge/culvert structures outside the nesting season, the Contractor will reimburse the Department of Roads for each survey required at \$1,000 per survey. If the project was awarded during the nesting season, and construction activities are such that clearing/grubbing and/or work on bridge/culvert structures must be accomplished prior to any other activity on the project, then there will be

no charge assessed for the initial survey. The Contractor is responsible for removing all trees surveyed, that do not contain active nests, and for taking appropriate measures on bridge/culvert structures, within 3 days of the survey. Reimbursement for additional surveys may be charged if the Contractor fails to remove the trees within 3 days of the survey, and requires an additional survey. Survey reimbursement will be determined on a project specific basis, considering the project timeline and associated activities.

6. If an active nest is found during the survey, the Contractor should do everything possible to restructure his activities and leave the nest undisturbed until the young fledge. Fledging could occur within a week, or up to a month, after the survey depending on the species of bird and whether the nest contained eggs or young. Also depending on the species of bird and their sensitivity to disturbance, a buffer of up to 30 feet surrounding the tree with the active nest could be required.
7. If construction cannot be rescheduled to allow the birds to fledge, and it is determined as an unavoidable "take" circumstance, the Contractor shall stop all work within 30 feet of the active nest and coordinate with the Construction Project Manager to determine how to proceed. The Construction Project Manager will then coordinate with the NDOR Environmental Section and they will facilitate coordination with the US Fish and Wildlife Service and the Federal Highway Administration (for projects using Federal-aid) to determine the appropriate way to address the active nest. No work shall occur within 30 feet of the active nest until US Fish and Wildlife Service coordination is complete and the requirements of the Migratory Bird Treaty Act are satisfied.
8. It is the Contractor's responsibility to schedule his work to accommodate the process of conducting a survey(s) and submitting the necessary documentation if avoidance is not practicable. The Contractor shall be responsible for using any legal and practical method to prevent the nesting of birds in order to prevent the need for any survey and prevent the need for additional surveys. It is understood and agreed that the Contractor has considered in the bid all of the pertinent requirements concerning migratory birds (including endangered species) and that no additional compensation, other than time extensions if warranted, will be allowed for any delays or inconvenience resulting in these requirements.

STORM WATER DISCHARGES (A-43-0408)

In compliance with the Federal Water Pollution Control Act, authorization to discharge storm water on this project has been granted under National Pollutant Discharge Elimination System (NPDES) General NPDES Permit Number NER110000 for Storm Water Discharges from Construction Sites to Waters of the State of Nebraska. This permit became effective on January 1, 2008.

Contractors are advised that, under the Construction Storm Water General Permit, ***plant sites, camp sites, storage sites, and borrow or waste sites not shown on the plans may be subject to separate NPDES permit authorization requirements for stormwater discharges from those locations.*** Contractors shall be responsible for verifying the need for NPDES permit coverage with the Nebraska Department of Environmental Quality (NDEQ). When

required for these locations, the filing of a "Notice of Intent" shall be made by the Contractor directly to the NDEQ.

Additionally, asphalt (SIC Code 2951) or concrete (SIC Code 3273) batch plants that are owned by a private contractor and are operated on a contract-for-service basis to perform work for the Contractor completing the project may be subject to NPDES General Permit Number NER000000 for Industrial Storm Water Discharges. While the plant may be required for completion of the project, it is not under the control of the Department (or other project owner); and the filing of a "Notice of Intent" shall be made by the Contractor directly to the NDEQ.

The NDEQ may be contacted at 402-471-4220 for additional information.

REQUIRED SUBCONTRACTOR/SUPPLIER QUOTATIONS LIST (A-43-0307)

All bidders must provide to the NDOR the identity of all firms who provided quotations on all projects, including both DBEs and non-DBEs. This information must be on a form provided by the NDOR Contracts Office.

If no quotations were received, the bidder must indicate this in the space provided.

Each bidder will be required to submit one list per letting to cover all projects bid.

PROPOSAL GUARANTY BID BOND (A-43-0307)

Paragraphs 1.a. and 1.b. of Subsection 102.15 in the *Standard Specifications* are void and superseded by the following:

- a. OPTION 1 - (Project Specific Paper Bid Bond). The Bid Bond shall be executed on an original Department Bid Bond Form, which may be obtained from the Department. The original Bid Bond shall be delivered to the Department with the bid. A reproduction or a copy of the original form will not be accepted and will cause the bid not to be opened and read.
- b. OPTION 2 - (Annual Bid Bond). The Department at its discretion may allow a bidder to place an "Annual Bid Bond" on file with the Department. This bond would cover all projects the bidder bids for a 12-month period shown in the bond. The bidder must indicate in the bid submittal to the Department that their "Annual Bid Bond" applies to the submitted bid. The original Annual Bid Bond shall be executed on the Department of Roads Bid Bond Form, which may be obtained from the Department. A reproduction or a copy of the original form will not be accepted.

**WORKER VISIBILITY
(A-43-0507)**

Pursuant to Part 634, Title 23, Code of Federal Regulations, the following modified rule is being implemented:

Effective on January 1, 2008, all workers within the right-of-way who are exposed either to traffic (vehicles using the highway for purposes of travel) or to construction equipment within the work area shall wear high-visibility safety apparel.

High-visibility safety apparel is defined to mean personal protective safety clothing that:

- 1 - is intended to provide conspicuity during both daytime and nighttime usage, and
- 2 - meets the Performance Class 2 or Class 3 requirements of the ANSI/ISEA 107-2004 publication titled "American National Standards for High-Visibility Safety Apparel and Headwear."

**VALUE ENGINEERING PROPOSALS (VEP)
(A-43-0807)**

Subsection 104.03 in the *Standard Specifications* is amended to include the following:

14. A VEP will not be accepted if the proposal is prepared by an Engineer or the Engineering Firm who designed the contract plans.

**LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC
(A-43-0210)**

Paragraph 4.a. of Subsection 107.01 in the *Standard Specifications* is void and superseded by the following:

4. a. Whenever the Contractor violates any governing Federal, State or Local environmental quality regulation and/or is in noncompliance with any environmental commitment, the violating activity must cease immediately until the appropriate remedy can be determined by: the Engineer, the NDOR Environmental Section, the Federal Highway Administration (for projects utilizing Federal-aid) and other agencies, as deemed appropriate. The Engineer, with assistance from the NDOR Environmental Section and the FHWA, will provide a written order confirming the appropriate corrective action to the Contractor. Work can resume to normal conditions once the Engineer determines that the violation or non-compliance has been addressed in accordance with the order for corrective action.

Subsection 107.01 in the *Standard Specifications* is amended to include the following two paragraphs:

5. Should the Contractor encounter any previously unidentified hazardous materials, the Engineer shall be promptly notified. The Contractor shall suspend operations in the area involved until such time that arrangements are made for their proper treatment or removal.
6. The Contractor shall prevent the transfer of invasive plant and animal species. The Contractor shall wash equipment at the Contractor's storage facility prior to entering the construction site. The Contractor shall inspect all construction equipment and remove all attached vegetation and animals prior to leaving the construction site.

**SPECIAL PROSECUTION AND PROGRESS
(Federal Immigration Verification System)
(A-43-1209)**

The Contractor shall register with and use a Federal Immigration Verification System to determine the work eligibility status of newly hired employees physically performing services within the State of Nebraska. The Prime Contractor shall contractually require every subcontractor to register with and use a Federal Immigration Verification System to determine the work eligibility status of newly hired employees physically performing services within the State of Nebraska.

The Federal Immigration Verification System shall be an electronic verification of the work authorization program of the Illegal Immigration Reform and Immigration Responsibility Act of 1996, 8 U.S.C. 1324a, known as the E-Verify Program. The Contractor may use an equivalent Federal program designated by the United States Department of Homeland Security or other Federal agency authorized to verify the work eligibility status of a newly hired employee. The equivalent program shall comply with the Immigration Reform and Control Act of 1986.

The Prime Contractor shall furnish a letter to the NDOR Construction Division in Lincoln on company letterhead and signed by an officer of the company stating that documentation is on file certifying that the Contractor and all subcontractors have registered with and used a Federal Immigration Verification System. The Contractor shall maintain all records of registration and use for a period of three years and make records available upon request. The Contractor shall contractually require subcontractors to maintain all records for a period of three years and make records available upon request.

Payment will not be made to the Contractor for using the Federal Immigration Verification System or the maintenance of the records. This work shall be subsidiary to the work being performed.

The Contractor's Certification shall become part of the final records of the Contract. The Department considers this document to have direct bearing to the beginning interest date and may affect the amount of interest earned.

**CONTRACT TIME ALLOWANCE
(A-43-0911)**

Paragraph 5. of Subsection 108.02 of the *Standard Specifications* is void and superseded by the following:

5. Each week, the Engineer shall post on the Department's website a report of working days or calendar days charged. The Contractor then has 14 days from the day the Engineer's report is posted to provide a written explanation of why he/she does not concur with the working days or calendar days as assessed.

Paragraph 6.b. of Subsection 108.02 of the *Standard Specifications* is amended to include the following:

- (4) If the time allowance for the contract has been established on a calendar day basis, the Contractor is expected to schedule the work and assign whatever resources are necessary to complete the work in the time allowance provided regardless of the weather. Accordingly, regardless of anything to the contrary contained in these *Specifications*, the Department will not consider delays caused by inclement or unseasonable weather as justification for an extension of the contract time allowance unless:
 - i. the weather phenomena alleged to have contributed to or caused the delay is of such magnitude that it results in the Governor issuing a Disaster Declaration, **and**
 - ii. the weather phenomena alleged to have contributed to or caused the delay can clearly be shown to have directly impacted the work on the critical path identified on the Contractor's schedule.

Paragraphs 10.b. and 10.c. of Subsection 108.02 of the *Standard Specifications* are void and superseded by the following:

- b. (1) If the extra work is not in the original contract, time extensions will be granted by determining the actual time necessary to accomplish the extra work.
- (2) If the extra work is the result of the addition of additional quantities of existing contract items, time extensions will be granted by either:
 - (i) determining the actual time necessary to accomplish the extra work; or
 - (ii) determining the additional time to be granted by comparing the value of the additional quantities of work to the total amount of the original contract when measurement of the actual additional time is not possible or practical.
- (3) In either case, only the time necessary to perform the extra work of the additional quantities of existing contract items when the extra work or the additional quantities of existing contract items are deemed to be the current controlling operation will be granted as a time extension.

- c. Increases in quantities of work associated with traffic control items measured by the day will not be considered for extending the contract time allowance. Overruns of traffic control items that are measured by methods other than time may be considered for extending the contract time allowance, but they must be deemed to be a controlling operation when the overrun of quantities occurs.

**PARTIAL PAYMENT
(A-43-1110)**

Paragraph 2. of Subsection 109.07 of the *Standard Specifications* is void and superseded by the following:

- 2. When the value of the work completed during a semi-monthly period exceeds \$10,000, the Contractor will receive semi-monthly progress estimates from which the Department shall make such retentions as may be allowed by the contract, provided that the nature and quality of the completed work are satisfactory and provided further that the progress of the work conforms to the requirements of Subsection 108.07.

Paragraph 3.b. of Subsection 109.07 of the *Standard Specifications* is void and superseded by the following:

- b. Under normal circumstances, the Department shall not retain any earnings on a progress estimate. However, the Department reserves the right to retain such amounts as are necessary for material deficiencies, anticipated liquidated damages, unpaid borrow, and for other reasons to protect the Department's interests.

**PARTIAL PAYMENT
(A-43-0611)**

Paragraph 4. of Subsection 109.07 of the *Standard Specifications* is void and superseded by the following:

- 4. a. (1) Upon presentation by the Contractor of receipted bills, billing invoices, or such other documentation sufficient to satisfy the Engineer and verify the Contractor's or subcontractor's actual costs for the materials, payments may also be allowed for acceptable nonperishable materials purchased expressly to be incorporated into the work and delivered in the vicinity of the project or stored in acceptable storage places within Nebraska.
- (2) Materials not delivered and stored in the immediate vicinity of or on the actual project site must be clearly marked to identify the project on which they are to be used, must be segregated from similar materials at the storage site, and cannot be included in a supplier's inventory of material available for sale for other purposes.
- (3) All items eligible for partial payment as stored materials must be available for verification, sampling, and measurement.

- b. The amount to be included in the payment will be determined by the Engineer, but in no case shall it exceed 100 percent of the value of the materials documented. This value may not exceed the appropriate portion of the value of the contract item or items in which such materials are to be incorporated, nor shall the quantity in any case exceed the total estimated quantity required to complete the project.
- c. Payment will not be approved when the documented value of such materials amounts to less than \$1,000.00, when the progress of the work is not in accordance with the requirements set forth in Subsection 108.07, or when the material can reasonably be expected to be incorporated into the work and eligible for payment as completed work on a progress estimate within 15 days of being placed into storage.
- d. Deductions at rates and in amounts which are equal to the payments will be made from estimates as the materials are incorporated into the work.
- e. Payment for the materials shall not in itself constitute acceptance, and any materials which do not conform to the specifications shall be rejected in accordance with Subsection 106.05.
- f. The Contractor shall be responsible for all damages and material losses until the material is incorporated into the work and the work is accepted.
- g. Partial payment will not include payment for fuels, supplies, form lumber, falsework, other materials, or temporary structures of any kind which will not become an integral part of the finished construction.
- h. No partial payments will be made on living or perishable plant materials until planted.

**BUY AMERICA
(A-43-0212)**

Subsection 106.07 in the *Standard Specifications* is void and superseded by the following:

106.07 -- Buy America

- 1. The Buy America rule requires that steel or iron materials be produced domestically, and only those products which are brought to the construction site and permanently incorporated into the completed project are covered. Construction materials, forms, etc., which remain in place at the Contractor's convenience, but are not required by the contract, are not covered.
- 2. To further define the coverage, a domestic product is a manufactured steel construction material that was produced in one of the 50 States, the District of Columbia, Puerto Rico, or in the territories and possessions of the United States.

3. All manufacturing processes to produce steel or iron materials (i.e., smelting, and any subsequent process which alters the steel or iron material's physical form or shape, or changes its chemical composition) must occur within one of the 50 States, the District of Columbia, Puerto Rico, or in the territories and possessions of the United States, to be considered of domestic origin. This includes processes such as casting, rolling, extruding, machining, bending, grinding, drilling, and coating. Coating includes epoxy coating, galvanizing, painting, and any other coating that protects or enhances the value of the material. The manufacturer shall include a statement on the material test report or certification that all material described above except the coating material is a domestic product.
4. Raw materials used in the steel or iron materials may be imported. All manufacturing processes to produce steel or iron materials must occur domestically. Raw materials are materials such as iron ore, limestone, waste products, etc., which are used in the manufacturing process to produce the steel products. Waste products would include scrap; i.e., steel no longer useful in its present form from old automobiles, machinery, pipe, railroad tracks and the like. Also, steel trimmings from mills or product manufacturing are considered waste. Extracting, crushing, and handling the raw materials which is customary to prepare them for transporting are exempt from Buy America. The use of pig iron and processed, pelletized, and reduced iron ore manufactured outside of the United States may be used in the domestic manufacturing process for steel and/or iron materials.
5. Notwithstanding this requirement, a minimum of foreign steel or iron materials will be permitted if its value is less than one-tenth of one percent of the total contract cost or \$2,500, whichever is greater.
6. Upon completion of all work utilizing steel or iron products, the Prime Contractor shall furnish a letter to the State on company letterhead and signed by an officer of the company stating that documentation is on file certifying that all steel or iron materials brought to the construction site and permanently incorporated into the work complied in all respects with the Buy America requirements.

BORROW, WASTE, STOCKPILE, AND PLANT SITE APPROVAL (A-43-0512)

Subsection 107.02 in the Standard Specifications is amended to include the following:

4. Site Approval:
 - a. When borrow is obtained from a borrow site or waste excavation is placed at sites which are not shown in the contract, or the Contractor plans to use a plant or stockpile site which is not shown in the contract, the Contractor shall be solely responsible for obtaining all necessary site approvals. The Department will provide the procedures necessary to obtain approvals from the U.S. Army Corps of Engineers, U.S. Fish and Wildlife Service, Nebraska State Historical Society, Nebraska Game and Parks Commission, and Nebraska Department of Natural Resources on the NDOR website. The Contractor shall also be responsible for

obtaining a Discharge Number from the Nebraska Department of Environmental Quality (NDEQ) that allows work under the current Construction Stormwater Permit. The Contractor shall also be responsible for obtaining any and all other permits required by local governments.

- b. It is anticipated that it may require 60 calendar days or more for the Contractor to obtain the necessary approvals. The Contractor will not be allowed to begin work at borrow or waste sites until the necessary approvals are obtained. No extension of completion time will be granted due to any delays in securing approval of a borrow or disposal site unless a review of the time frames concludes that there were conditions beyond the Contractor's control.

Paragraph 7. of Subsection 205.02 in the Standard Specifications is void and superseded by the following:

7. Borrow and Waste Site Approval:
 - a. Borrow and waste site approvals shall be in accordance with Section 107.02.
 - b. Material shall not be removed from borrow sites until preliminary cross sections and representative soil samples have been taken by the Engineer. The Contractor shall notify the Engineer a sufficient time in advance of the opening of any borrow site so that cross sections may be taken.
 - c. Material shall be removed in a manner that will allow accurate final cross sections to be taken for determining the quantity of excavation. The surfaces of the borrow sites shall be bladed and shaped to drain as shown in the contract or as directed by the Engineer.

**SPECIAL PROSECUTION AND PROGRESS
(Subletting or Assigning of Contract)
(A-43-0414)**

Subsection 108.01 in the Standard Specifications is void and superseded by the following:

108.01 – Subletting or Assigning of Contract

1. a. (1) The Contractor will not be allowed to sublet, assign, sell, transfer, or otherwise dispose of any portion of the contract or any right, title, or interest therein; or to either legally or equitably assign any of the money payable under the contract or the claims without the prior written consent of the Engineer.
- (2) With the Engineer's consent, the Contractor may sublet up to 70 percent of the work.

- (3) Any items designated in the contract as “specialty items” may be performed by subcontract.
 - (4) The cost of any subcontracted “specialty items” may be deducted from the total contract cost before computing the percentage of work required to be performed by the Contractor.
 - (5) Subcontracts, or transfer of contract, will not release the Contractor of any liability under the contract and bonds.
 - b. Certain items of work may be performed without a subcontract. A list of items not requiring a subcontract is available from the Engineer.
 2. The performance of any work by a subcontractor before the date of authorization by the Department shall subject both the Contractor and subcontractor to the imposition of appropriate sanctions by the Department.
 3. a. The Contractor’s request to sublet work shall be made electronically to the NDR Construction Engineer using project management software identified by the Department. A signed subcontract agreement shall be on file in the Contractor’s office when the request is made. The subcontract agreement must provide that the subcontracted work will be completed according to the terms of the contract. The required and Special Provisions contained in the proposal shall be physically included in any subcontract.
 - b. **On all Federal-aid projects, a scanned copy (.pdf format) of the signed subcontract agreement shall be included with the subcontracting request. (Federal-aid projects can be identified by inclusion in the Proposal of Form FHWA-1273 (REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS)).**
 - c. Scanned copies (.pdf format) of all executed subcontracts, written agreements, and/or lease agreements used to meet DBE goals shall be submitted to the NDR Construction Engineer with the subcontracting request. These copies must show labor cost, material prices, overhead and profit.
4. a. Second tier subcontracts will be allowed.
 - b. If a DBE firm subcontracts work to another firm, only work subcontracted to another DBE firm can be counted toward meeting a DBE goal.
 - c. All requests for second tier subcontracting shall be submitted to and approved by the Prime Contractor before they are forwarded to the NDR Construction Engineer for approval.
5. All subcontract documents relating to the contract shall be maintained during the course of the work and preserved for a period of three years thereafter. These documents shall be available for inspection by authorized representatives of State and Federal agencies. Scanned copies (.pdf format) of the signed subcontract agreements not specifically identified elsewhere in this Subsection shall be furnished to the Department upon request.

6. The Contractor may discuss a proposed subcontract with the Engineer before entering into a signed subcontract agreement, but final approval will not be granted until a formal request and proper certification has been received by the Department.
7. On projects requiring submittal of certified payrolls, all subcontractor payrolls shall be checked by the Contractor before submittal to the Engineer.
8. a. The Prime Contractor, and subcontractors when subletting work to lower tier subcontractors, shall include language which can be identified as a "Prompt Payment Clause" as a part of every subcontract for work and materials.
 - b. (1) The language constituting the "Prompt Payment Clause" will require payment to all first tier subcontractors for all labor and materials --- for work completed to date --- within 20 calendar days of receipt of progress payments from the Department for said work. Similar language in a contract between a subcontractor and a lower-tier subcontractor will require payment to the lower tier subcontractor for all labor and materials --- for work completed to date --- within 10 calendar days of receipt of progress payments from the prime Contractor for said work.
 - (2) The language constituting the "Prompt Payment Clause" will also stipulate the return of retainage within 30 calendar days after the satisfactory completion of the work by the subcontractor as evidenced by inclusion of the work on a progress payment.
 - (3) Additionally, the language constituting the "Prompt Payment Clause" may stipulate the subcontractor's obligation to return to the Contractor or subcontractor, as the case may be, any overpayments which result from adjustments to measured and recorded quantities as part of the preparation of subsequent progress payments or the final records. Overpayments shall be returned to the Prime Contractor or subcontractor, as the case may be, within 20 calendar days of receiving notice of the adjusted quantities and the amount of the overpayment.
- c. The Prime Contractor of subcontractors, as the case may be, may withhold payment only for just cause and shall not withhold, delay, or postpone payment without first receiving written approval from the Department.
- d. (1) The failure by the Prime Contractor to abide by the agreements identified in the "Prompt Payment Clause" without just cause, including the timely return of retainage, is a material breach of this contract which may result in the Department withholding the amount of payment from the prime Contractor that should have been paid to the subcontractor, termination of this contract, or other such remedy as the Department deems necessary.
 - (2) Additionally, the failure of any subcontractor to abide by the agreements identified in the "Prompt Payment Clause" without just cause, including the timely return of retainage to lower tier subcontractors, or by failing to return overpayments in a timely manner when the language permitted in Paragraph 8.b.(3) above is included in the subcontract may result in the Department withholding subcontract approval for other work until the overpayments have been returned.

9. a. (1) For Davis Bacon (DBRA)-covered projects and Non-DBRA-covered projects, a Contractor or subcontractor may wish to use another individual owner-operator or trucking company to supplement his or her hauling fleet. (The Department will not recognize multiple individuals claiming to be collectively identified as a single "owner operator.")
- (2) This supplemental individual or company must either become a subcontractor (first tier or lower tier, as the case may be) or be otherwise documented by the utilizing Contractor or subcontractor by entering into a lease agreement for the trucks and showing the driver (or drivers) from the supplemental company on the Prime Contractor's or subcontractor's payrolls in the manner described below.
- (3) Payrolls will only be accepted from the Prime Contractor or approved subcontractors.
- b. (1) If the decision is made to subcontract the hauling, the Prime Contractor must first notify the NDOR Construction Office to request subcontract approval. As part of the subcontract approval process --- at any tier --- the proper certificates of insurance must be provided before approval will be granted.
- (2) Additionally, on DBRA-covered projects, the Prime Contractor must submit payrolls for all subcontractors --- at any tier.
- c. (1) Owner/Operators of trucks hired by a Contractor or subcontractor to supplement his or her hauling fleet are not subject to Davis Bacon wage requirements. However, they must still be shown on a payroll prepared by the Contractor or subcontractor for whom they are working with the notation "owner/operator."
- (2) Any other employees of the "owner/operator" must appear on the certified payroll in complete detail and must be compensated according to the wage rates established for the project.
- d. In the event a Prime Contractor or subcontractor elects to not subcontract the supplemental driver or drivers but instead chooses to "carry the workers/truckers on their payroll," the following requirements must be met:
 - (1) The Prime Contractor's or subcontractor's certified payroll must contain the names of all workers/truck drivers, and the payroll should identify their supervisors (including "owner-operators").
 - (2) Pay checks for the workers/truckers in question must be drawn against the Prime Contractor's or subcontractor's payroll or other account.
 - (3) Owner/Operators need only be identified as such on the payroll. Additional drivers, if any, from the "owner-operator's" company must appear on a payroll in complete detail and be compensated according to the wage rates established for the project.

- (4) The Prime Contractor or subcontractor must enter into a lease agreement for the trucks driven by such drivers, and the lease agreement must show that the compensation for the leased equipment is on a time basis and not based on the amount of work accomplished. The lease agreements must be available for inspection by NDOR personnel.
- (5) Any supplemental truckers employed under this arrangement must still carry the minimum automobile liability coverage specified in the contract. It shall be the duty of the Prime Contractor to ensure that the supplemental truckers have such coverage in effect. Evidence of proper insurance must be presented for verification on demand.

**ELECTRONIC SHOP DRAWINGS
(A-43-0215)**

Paragraphs 5, 6, and 7 of Subsection 105.02 of the Standard Specifications are void and superseded by the following:

5. a. The Contractor shall provide electronic working drawings in a Portable Document Format (PDF). The PDFs shall be sized to print on an 11x17 inch sheet of paper and have a minimum resolution of 300 dpi. Each sheet of the shop drawings shall have a space provided for an electronic stamp that measures 2.5 inches x 3.5 inches when printed.
- b. Electronic working drawing files shall be named with the following file naming format:
Control Number_Brief Description_Date.pdf

For example: 12345_FloorDrains_05Feb2015
12345_FloorDrainCoverLetter_05Feb2015
- c. The project number, control number, and project location as it appears on the plans shall be shown on the front sheet of each Shop Drawing file. Structure numbers shall be included, if applicable.
6. No electronic working drawings shall be submitted to the Engineer unless they have been checked by the Contractor. The electronic submittal shall be accompanied by a Contractor's letter of approval in a PDF format. This letter shall also be named with the format shown in the example above. The letter of approval shall clearly indicate that the Contractor is responsible for any errors on the working drawings.
7. a. Electronic submittals shall be submitted by email to the following address:

DOR.ShopDrawings@nebraska.gov
- b. Attachments shall be limited to 25 MB of data per email. Larger files shall be separated and sent in multiple emails.
- c. Electronic working drawings will only be accepted from the Prime Contractor.
8. Any reference to hard copy shop drawings in the contract shall be considered void.

**LIABILITY INSURANCE
(A-55-0414)**

Subsection 107.13 in the Standard Specifications is void and superseded by the following:

107.13 – Liability Insurance

Prior to execution of the contract, the Contractor shall obtain insurance coverage to fully protect it from loss associated with the work, and have at a minimum the insurance described below:

1. General Liability:
Limits of at least:
 - \$ 1,000,000 per Occurrence
 - \$ 2,000,000 General Aggregate
 - \$ 2,000,000 Completed Operations Aggregate
 - \$ 1,000,000 Personal and Advertising Injury
- a. Contractor shall be responsible for the payment of any deductibles.
- b. Coverage shall be provided by a standard form Commercial General Liability Policy (CG0001 or equivalent) covering bodily injury, property damage including loss of use, and personal injury.
- c. The General Aggregate shall apply on a Per Project Basis.
- d. The State of Nebraska, Department of Roads, shall be named as an Additional Insured on a primary and non-contributory basis including completed operations for three (3) years after final acceptance and payment.
- e. Contractor agrees to waive its rights of recovery against the State of Nebraska, Department of Roads. Waiver of Subrogation in favor of the State of Nebraska, Department of Roads shall be added to the policy.
- f. Contractual liability coverage shall be on a broad form basis and shall not be amended by any limiting endorsements.
- g. If work is being performed near a railroad track, the 50' railroad right-of-way exclusion must be deleted.
- h. Products and completed operations coverage in the amount provided above shall be maintained for the duration of the work, and shall be further maintained for a minimum period of three years after final acceptance and payment.
- i. Coverage shall be included for demolition of any building or structure, collapse, explosion, blasting, excavation and damage to property below surface of ground (XCU coverage).

- j. Policy shall not contain a total or absolute pollution exclusion. Coverage shall be provided for pollution exposures arising from products and completed operations as per standard CG0001 Pollution Exclusion or equivalent. If the standard pollution exclusion as provided by CG0001 has been amended, coverage must be substituted with a separate Pollution Liability policy of \$1.0 million per occurrence and \$2.0 million aggregate. If coverage is provided by a “claims made” form, coverage will be maintained for three years after project completion. Any applicable deductible is the responsibility of the Contractor.
2. Automobile Liability:
Limits of at least:
\$ 1,000,000 CSL per Accident
- a. Coverage shall apply to all Owned, Hired, and Non-Owned Autos.
 - b. If work is being performed near a railroad track, the 50-foot railroad right-of-way exclusion must be deleted.
 - c. Contractor agrees to waive its rights of recovery against the State of Nebraska, Department of Roads. Waiver of Subrogation in favor of the State of Nebraska, Department of Roads, shall be added to the policy.
 - d. Automobile liability coverage shall be obtained from an insurance carrier who is licensed with the Nebraska Department of Insurance.
3. Workers' Compensation:
Limit: Statutory coverage for the State where the project is located.
Employer's Liability limits: \$500,000 Each Accident
\$500,000 Disease – Per Person
\$500,000 Disease – Policy Limit
- a. Contractor agrees to waive its rights of recovery against the State of Nebraska, Department of Roads. Waiver of Subrogation in favor of the State of Nebraska, Department of Roads shall be added to the policy.
 - b. Workers' compensation coverage shall be obtained from an insurance carrier who is licensed with the Nebraska Department of Insurance.
 - c. Where applicable, the Longshore and Harborworkers Compensation Act endorsement shall be attached to the policy.
4. Umbrella/Excess:
Limits of at least:
\$1,000,000 per Occurrence
- a. Policy shall provide liability coverage in excess of the specified Employers Liability, Commercial General Liability and Automobile Liability.
 - b. The State of Nebraska, Department of Roads, shall be an “Additional Insured.”
 - c. Contractor agrees to waive its rights of recovery against the State of Nebraska, Department of Roads. Waiver of subrogation in favor of the State of Nebraska, Department of Roads shall be provided.

5. Pollution Liability:
 - a. When “hazardous wastes” or contaminated or polluted materials must be handled and/or moved, the Contractor shall obtain Pollution Liability Coverage with minimum limits of \$1,000,000 per occurrence and \$2,000,000 aggregate.
 - b. If, during the course of construction, hazardous wastes, contaminated or polluted material are discovered on the project, the Contractor shall immediately cease any operation that may disturb these materials, and shall immediately notify the Engineer of all facts related to the discovery of these materials.
 - c. Unforeseen work related to the discovery of hazardous, contaminated or polluted materials on the project, and the extra cost, if any, of pollution liability coverage will be handled as “extra work.”
6. Additional Requirements:
 - a. The Contractor shall provide and carry any additional insurance required by the Special Provisions.
 - b. Except as otherwise provided herein, all insurance shall be kept in full force and effect until after the State releases the Contractor from all obligations under the contract.
 - c.
 - (1) If any of the work is sublet, equivalent insurance shall be provided by or on behalf of the subcontractor or subcontractors (at any tier) to cover all operations.
 - (2) Approved trucking subcontractors (at any tier) who are being utilized only for the purpose of hauling materials shall be exempt from the requirements of Paragraphs 1, 4, and 5.
 - (3)
 - (i) When a Contractor or subcontractor chooses to employ a trucker by carrying the driver on his or her payroll and entering into a lease agreement for the truck, the owner-operator of the truck shall be required to comply with the Automobile Liability provisions of Paragraph 2.
 - (ii) Furthermore, it shall be the duty of the Prime Contractor to ensure that the owner-operator of the truck has such insurance in effect. The Prime Contractor shall maintain evidence that any truckers so utilized (at any tier) are insured to the minimum limits specified and be able to furnish documentation of the same on demand.
 - (iii) Failure to ensure that insurance coverage exists and failure to maintain evidence thereof shall be considered a breach of the contract.
 - d. Any insurance policy shall be written by an insurance company with a Best’s Insurance Guide Rating of A – VII or better.
 - e. Prior to execution of the contract, Contractor shall provide the State of Nebraska, Department of Roads evidence of such insurance coverage in effect in the form of an Accord (or equivalent) certificate of insurance executed by a licensed representative of the participating insurer(s). Certificates of insurance shall show the Nebraska Department of Roads as the certificate holders.

- f. For so long as insurance coverage is required under this agreement, the Contractor shall have a duty to notify the Department when the Contractor knows, or has reason to believe, that any insurance coverage required under this agreement will lapse, or may be cancelled or terminated. The Contractor must forward any pertinent notice of cancellation or termination to the Department at the address listed below by mail (return receipt requested), hand-delivery, or facsimile transmission within 2 business days of receipt by Contractor of any such notice from an insurance carrier. Notice shall be sent to:
- Nebraska Department of Roads
Construction Division --- Insurance Section
1500 Highway 2, P.O. Box 94759
Lincoln, NE 68509-4759
Facsimile No. 402-479-4854
- g. Failure of the owner or any other party to review, approve, and/or reject a certificate of insurance in whole or in part does not waive the requirements of this agreement.
- h. The limits of coverage set forth in this document are suggested minimum limits of coverage. The suggested limits of coverage shall not be construed to be a limitation of the liability on the part of the Contractor or any of its subcontractors/tier subcontractors. The carrying of insurance described shall in no way be interpreted as relieving the Contractor, subcontractor, or tier subcontractors of any responsibility or liability under the contract.
- i. If there is a discrepancy of coverage between this document and any other insurance specification for this project, the greater limit or coverage requirement shall prevail.

CONSTRUCTION DETAILS

TEMPORARY WATER POLLUTION CONTROL (B-3-1014)

Section 204 in the Standard Specifications is void.

CONSTRUCTION STORMWATER MANAGEMENT CONTROL (B-3-1014)

A. General

1. This Section defines some best management practices (BMPs) for erosion and sediment control measures and construction practices the Contractor shall use to prevent soil erosion and avoid water pollution.
2.
 - a. The Department and the Contractor are co-permittees of the NPDES Construction Storm Water General Permit.
 - b. The Contractor shall comply with all conditions required by the current NPDES Construction Storm Water General Permit.
3. The Contractor shall exercise every reasonable precaution throughout the life of the contract to prevent silting of the waters of the state, the project site, and adjacent property. Construction of drainage facilities, as well as performance of other contract work which will contribute to the control of siltation, shall be carried out in conjunction with earthwork operations or as soon thereafter as is practicable.
4.
 - a. The Contractor shall take sufficient precautions to prevent pollution of the waters of the state, the project site, and adjacent property from construction debris, petroleum products, chemicals, or other harmful materials.

The Contractor shall conduct and schedule the operations to avoid interference with any protected species.
 - b. The Contractor shall comply with all applicable statutes relating to pollution of the waters of the state and fish and game regulations.
5. All construction debris shall be disposed in a manner that it cannot enter any waterway. Excavation shall be deposited as to protect the waters of the state from siltation.
6. All erosion and sediment control measures shall be properly installed and maintained by the Contractor until all permanent drainage facilities have been constructed, and all slopes are sufficiently vegetated to be an effective erosion deterrent; or until tentative acceptance of the work.

7. All erosion and sedimentation resulting from the Contractor's operations and the weather conditions must be corrected by the Contractor.

LIMITATION OF OPERATIONS (B-3-1014)

A. General

1. The maximum exposed surface area for the Contractor's operations in excavation, borrow, and embankment is 18 acres (72,800 m²) plus an equal area of clearing and grubbing/large tree removal. A written request for an increase in the maximum exposed surface area may be approved by the Engineer. This approval will be based on the soil, moisture, seasonal conditions, the Contractor's operation, or other conditions.
2. The Engineer shall have the authority to reduce the maximum exposed surface area when any of the following conditions warrant:
 - a. Soil and moisture conditions are such that erosion is probable.
 - b. Seasonal conditions may force extended delays.
 - c. Proximity to the waters of the state requires more stringent controls.
 - d. Equipment and personnel available on the job is not sufficient to properly maintain erosion and dust control measures.
 - e. Any other environmental condition in the area that may exist which would be affected by erosion from the project.
3. Construction operations in rivers, streams, wetlands, and impoundments shall be restricted to those areas specifically shown in the contract. Rivers, streams, wetlands, and impoundments shall be promptly cleared of all false work, piling, debris, or other obstructions placed therein or caused by the construction operations.
4. Fording and operation of construction equipment within streams and wetlands will not be allowed, unless explicitly allowed in the contract. Streams are defined as any area between the high banks, regardless of the flow conditions.

CONSTRUCTION METHODS (B-3-1014)

A. General

1. The Contractor shall conduct all construction activities and install temporary erosion control measures, as necessary, to control sediment and avoid soil erosion during construction.

2. The Contractor shall incorporate all permanent erosion control features into the project at the earliest practicable time.
3. Construction stormwater management control measures for Contractor obtained work areas located outside the right-of-way, such as borrow site operations, haul roads, plant sites, staging sites, waste sites, equipment storage sites, etc. are the sole responsibility of the Contractor. All construction stormwater management control measures for these areas are at the Contractor's expense. The Contractor is responsible for securing all required permits for use of these sites.
4. The construction stormwater management procedures contained herein shall be coordinated with any permanent erosion control measures specified elsewhere in the contract to the extent practical to assure economical, effective, and continuous erosion and sediment control throughout the construction period.
5. The Contractor shall be responsible to limit erosion and prevent siltation into the waters of the state during the construction period, as well as during the times that work may be suspended.
6.
 - a. All erosion and sediment control items shall be installed by personnel who are knowledgeable in the principles and practice of various BMP installations.
 - b. The installation of all erosion and sediment control items shall be done under the direct supervision of the Contractor's employee who has successfully completed training provided by the Department and has been certified as an Erosion and Sediment Control Inspector (Inspector). The Contractor's Inspector shall be present at each site during installation to direct and inspect all erosion and sediment control BMP installations.
 - i. The NDOR Erosion and Sediment Control Inspector Certification is obtained by completing an Erosion and Sediment Control Inspector Training Course provided by the Nebraska Department of Roads and passing the examination that accompanies the training.
 - c. The Contractor shall notify the Engineer of all employees, who have been certified as Inspectors, who will be on the project to direct and inspect all erosion and sediment control BMP installations.
 - d. No payment will be made for any erosion and sediment control item unless a Contractor's Inspector was present to directly supervise and inspect the work.
 - e. No payment will be made for any erosion and sediment control item that is not properly installed. All erosion and sediment control items shall be installed as per the contract.

**ENVIRONMENTAL COMMITMENT DOCUMENT
(B-3-1014)**

A. Environmental Commitment Document

1. a. An Environmental Commitment Document will be created by the Department to identify all project specific environmental commitments and will be included in the Contract.
- b. The Department will provide information for the following, when applicable:
 - i. Storm Water Pollution Prevention Plan (SWPPP)
 - ii. U.S. Army Corps of Engineers (USACE) Section 404 Permit
 - iii. Nebraska Department of Environmental Quality 401 Water Quality Certification
 - iv. State Title 117 Waters (USACE Non-Jurisdictional)
 - v. Floodplain Permit
 - vi. Historic Clearance
 - vii. Endangered Species Act Clearance
 - viii. Nebraska Nongame and Endangered Species Conservation Act Clearance
 - ix. National Environmental Policy Act Compliance
 - x. NPDES Construction Stormwater Permit (within Right-of-Way limits, only)
 - xi. Conservation Measures
 - xii. Migratory Bird Treaty Act
 - xiii. Bald and Golden Eagle Protection Act Compliance
 - xiv. Other pertinent issues
- c. The Contractor shall provide information for the following, when applicable:
 - i. Temporary Erosion Control Plan
 - ii. Spill Prevention and Control Plan
 - iii. Migratory Bird Treaty Act Compliance Plan
 - iv. Name and telephone number of the Contractor's representative responsible for the Environmental Commitments
 - v. Name and telephone number of the employees that are NDOR-Certified Erosion and Sediment Control Inspectors
 - vi. Critical Path Construction Schedule
 - vii. Other items as defined elsewhere in the contract

**STORM WATER POLLUTION PREVENTION PLAN (SWPPP)
(B-3-1014)**

A. General

1. A SWPPP is required for projects that construction activities will cause a land disturbance of one (1) acre or more. The Department will prepare the SWPPP for the areas within the Right-of-Way, temporary easements and permanent easements.
2. For projects not requiring a SWPPP, the Contractor shall comply with the requirements of Environmental Commitment Document, Paragraph 1.b. of this Special Provision, as applicable.
3. Contractor obtained work areas, located on private property, are not included in the NDOR Project SWPPP.

B. Temporary Erosion Control Plan

1. The Contractor shall prepare and submit the Temporary Erosion Control Plan prior to the start of any work. The Contractor shall not begin work until the Temporary Erosion Control Plan has been submitted to the Engineer and appropriate erosion control measures are in place. Payment for any work on the contract will be withheld if erosion control measures are not in place or properly maintained.
2. The Temporary Erosion Control Plan will be reviewed at project progress meetings. All active Contractors shall have their Inspectors present and work in cooperation to determine any necessary changes. Necessary changes will be documented on the Temporary Erosion Control Plan by the Engineer.
3. Payment for preparing the Temporary Erosion Control Plan, inspections and meeting reviews are subsidiary to items that direct payment is made.

C. Spill Prevention and Control Plan

1. All project activities shall be addressed in the Spill Prevention and Control Plan. The Contractor shall prepare and submit the plan to the Engineer and install all appropriate spill prevention and control measures prior to the start of any work.
2. The Spill Prevention and Control Plan shall clearly state measures to prevent, contain, document and clean up a spill. It shall state measures for disposal of the contaminated material, disposal documentation and incident review to train personnel to prevent spills from reoccurring.
3. Spill Prevention and Control Plans are applicable to construction sites where hazardous materials are stored, used and/or generated onsite. Hazardous materials include, but not limited to: hazardous wastes, pesticides, paints, cleaners, petroleum products, fertilizers, solvents and porta-potty wastes.
4. Direct payment will not be made for the Spill Prevention and Control Plan.

D. Migratory Bird Treaty Act Compliance Plan

1. The Contractor shall not begin work until a Migratory Bird Treaty Act Compliance Plan has been submitted to the Engineer and appropriate nesting migratory bird avoidance measures are in place.
2. a. The Contractor shall clearly state the necessary measures they intend to use to avoid a “Take” of nesting migratory birds in the Migratory Bird Treaty Act Compliance Plan. Measures may include but are not limited to:
 - i. Clearing and grubbing prior to April 1st or after September 1st
 - ii. Tree removal prior to April 1st or after September 1st
 - iii. Clearing empty nests on structures prior to April 1st
 - iv. Maintaining clear structures until commencement and throughout the duration of work on structures
 - v. Netting structures to prevent nesting
 - vi. Commitment to perform surveys according to protocol
 - vii. Hire a biologist to survey areas to be disturbed prior to commencement of work during the nesting season
 - viii. Submittal of required bird survey reports
 - ix. Training of Contractor Personnel to insure compliance
3. a. The Migratory Bird Treaty Act Compliance Plan is applicable to the entire project site to avoid the “Take” of migratory birds protected under the Migratory Bird Treaty Act.

b. “Take” is defined as: pursuit, hunt, shoot, wound, kill, trap, capture, collect, or attempt to pursue, hunt, shoot, wound, kill, trap, capture, or collect.
4. The Migratory Bird Treaty Act Compliance Plan shall adhere to the NDOR’s Avian Protection Plan located at:
<http://www.transportation.nebraska.gov/environment/guides/avian-protection-plan.pdf>

Direct payment will not be made for the Migratory Bird Treaty Act Compliance Plan.

E. SWPPP Inspection

1. The Contractor shall accompany the Engineer on inspections in accordance with the NPDES Construction Storm Water General Permit.
2. The SWPPP will be maintained and updated by the Engineer as work progresses and site conditions change to accurately describe the BMPs that are currently in place.
3. The Contractor’s participation in SWPPP inspections, maintenance and updates shall begin on the first day construction activities cause land disturbance and end on the date of project completion as evidenced as the completion date in the District Engineer’s Letter of Tentative Acceptance.

4. a. The Contractor's Inspector shall be responsible for ensuring that all BMPs are installed in accordance with the contract or the manufacturers' recommendations. The Contractor's Inspector shall be capable of reading and interpreting these documents.
- b. The Contractor's Inspector shall be familiar with product and structural BMPs. The Contractor's Inspector shall inspect, assess, and supervise the maintenance of erosion and sediment control BMPs to ensure compliance with the NPDES Construction Storm Water General Permit while preserving BMP functionality.
5. Payment for project inspection is subsidiary to items that direct payment is made.

**ENVIRONMENTAL COMMITMENT ENFORCEMENT
(B-3-1215)**

A. General

1. This specification establishes payment and disincentive assessment for the Contractor's performance in complying with Contract Environmental Commitments.
2. Deficiencies are described but not limited to:
 - a. Failure to install pollution prevention control BMPs as work progresses or as described in the SWPPP.
 - b. Failure to maintain existing pollution prevention control BMPs.
 - c. Failure to remove non-functioning pollution prevention control BMPs.
 - d. Failure to comply with USACE Section 404 Permit requirements.
 - e. Failure to comply with NPDES Construction Storm Water General Permit requirements.
 - f. Failure to comply with all applicable statutes relating to pollution of the waters of the state.
 - g. Exceeding the maximum exposed surface area for excavation of 18 Acres without written request for permission and written approval.
 - h. Failure to comply with wildlife species specific conservation conditions.
 - i. Failure to comply with the Contract.
 - j. Failure to comply with the Engineers directives.

B. SWPPP Deficiency Notification

1. The Engineer will document and direct the Contractor to correct deficiencies.
2.
 - a. The Contractor shall commence correcting deficiencies, provide adequate equipment and personnel, and diligently pursue correcting deficiencies without cessation until all deficiencies have been corrected.
 - b. The count of Working Days and/or Calendar Days will continue during the time period that corrective work is being performed.
 - c. Delays to the project as a result of the Contractor conducting corrective actions for the Contract Environmental Commitments will not constitute a valid reason for an extension of the contract time allowance.
3. Deficiencies shall be corrected within seven (7) calendar days of notification or within an approved extension. When deficiencies are not corrected within seven (7) calendar days or within an approved extension, the Engineer will make a disincentive assessment to the contract as stated herein.
4.
 - a. If soil, weather, or other conditions prevent the Contractor from completing the corrective actions within seven (7) calendar days, the Contractor shall notify the Engineer in writing. The Contractor's letter shall state the reasons preventing corrective action within the time allowed. The Contractor shall propose a written Corrective Action Plan within 48 hours. Corrective work shall continue while the Corrective Action Plan is developed. The Contractor's Corrective Action Plan must contain a course of action and a time frame for completion. If the reasons and the Corrective Action Plan are acceptable, the Engineer may extend the time in which to complete the corrective work.
 - b. The Contractor will be allowed to proceed with the plan as proposed without incurring a disincentive assessment. If all corrective work is completed within the time allowance shown in the Notification or within an approved extension, a disincentive assessment will not be imposed upon the Contractor.
 - c. Storm events or soil and weather conditions occurring on other projects, which interfere with a Contractor completing corrective actions on the project within seven (7) calendar days, will not be justification for a time extension to complete the corrective work.
5. If all corrective work identified in the Notification has not been completed at the end of the seventh (7th) calendar day after the Initial Notice Date or within an approved extension, a Shut-Down Notice will be issued on the eighth (8th) calendar day after the Initial Notice Date or on the calendar day following the last day of an approved extension.
6. All operations shall cease as of the date and time cited in the Shut-Down Notice. The Contractor shall work, exclusively, on the deficiencies until all have been corrected or as directed by the Engineer. Upon issuance of the Shut-Down Notice, a disincentive of \$500.00 per deficiency per calendar day will be assessed thru the day the corrective work is completed, inclusive.

7. The Engineer may require the Contractor to provide a written Procedures Plan that describes the process to prevent reoccurrence of deficiencies. The written Procedures Plan shall be provided within two (2) calendar days of the request. Failure to correct all deficiencies and provide a Procedures Plan may result in payments being withheld until such time that procedures are outlined.
 - a. Payment for preparing a written Procedures Plan is subsidiary to items that direct payment is made.

C. Storm Event Restoration – Incentive and Disincentive

1. The Department will pay “Storm Event Restoration - Incentive” when the Contractor completes the restoration work to eliminate the pollution prevention control deficiencies within seven (7) calendar days of Notification or within an approved extension. Multiple deficiencies may be included in one notification. If the restoration work has not been completed within seven (7) calendar days after the Initial Notice or within an approved extension, payment for the item of “Storm Event Restoration - Incentive” will not be made.
2. A storm event is defined as a storm exceeding 0.50 inch of rain in a 24 hour period.
3. The Department will notify the Contractor of pollution prevention control deficiencies.
4.
 - a. Payment for the item of “Storm Event Restoration - Incentive” may not be made when the Contractor is notified to correct pollution prevention devices not installed in accordance with the contract or the manufacturer’s recommended installation instructions.
5. If the restoration work is not completed within seven (7) calendar days or within an approved extension, a disincentive assessment of \$500.00 per deficiency per calendar day will be assessed. The disincentive assessment will begin on the eighth (8th) calendar day after the issuance of the Initial Notice Date or on the calendar day following the last day of an approved extension(s) and continue through the day that the restoration work is completed, inclusive.

D. Method of Measurement

1.
 - a. “Storm Event Restoration – Incentive” will be measured by the each upon completion of restoration of all deficiencies included in a notification within the allowed time and only one payment per notification is allowed when multiple deficiencies are included on the notification.
 - b. If deficiencies from multiple notifications are restored during the same restoration operation, only one (1) incentive is eligible for payment.
 - c. If multiple notifications are the result of successive storm events and deficiencies are transferred to ensuing notifications, incentive payment is only eligible for the latest notification.

2. "Storm Event Restoration – Disincentive" will be measured by the calendar day in accordance with Paragraph C.5. above.

E. Basis of Payment

1. Pay Item	Pay Unit
Storm Event Restoration – Incentive	Each
Storm Event Restoration – Disincentive	Calendar Day

2. All equipment, materials, etc. used in the restoration work will be paid for in accordance with Division 800 of the Standard Specifications.
3. Payment is full compensation for all other incidentals required to complete the restoration work included in the notification within the allowed time.

F. Environmental Commitments – Contractor Compliance

1. To provide payment for all plans, inspections, surveys, reports, travel, qualified inspection person's, carrion removal, and any other subsidiary activities for the work of implementing threatened and endangered species commitments, temporary erosion control or any other environmental commitments prescribed in the contract.
2. Multiple visits to the project may be required to comply with environmental commitments prescribed in the contract.

G. Method of Measurement

1. No measurement is required.

H. Basis of Payment

1. Pay Item	Pay Unit
Environmental Commitments – Contractor Compliance	Lump Sum

2. Partial payments will be made as follows:
 - a. The Department will pay 50 percent of the total amount bid for the item Environmental Commitments – Contractor Compliance within seven (7) calendar days after the Notice to Proceed Date.
 - b. Upon completion of 50 percent of the Original Contract Amount, the Department will pay 30 percent of the amount bid for the item Environmental Commitments – Contractor Compliance.
 - c. Upon completion of 75 percent of the Original Contract Amount, the Department will pay the remaining 20 percent of the amount bid for the item Environmental Commitments – Contractor Compliance.
 - d. Failure to comply with any or all of the contract requirements, included for payment under the item of Environmental Commitments – Contractor Compliance, will preclude all payment for the item, including any previous payment.
3. Payment is full compensation for all work prescribed in the contract.

I. Immediate Action Deficiencies

1. Deficiencies that pose an imminent threat to the environment are considered an emergency situation. These deficiencies will be identified in the Immediate Action Deficiencies Section of the Environmental Commitment Deficiency Notification Form. The corrective work for Immediate Action Deficiencies shall begin immediately and continue without cessation until completed.
2. The Engineer will issue a shut-down notice. All work on the contract shall cease until the corrective work has been completed. The Engineer may allow the Contractor to continue working in areas unaffected by the Immediate Action Deficiency, provided corrective actions are being actively performed on the deficiency.
3. Immediate Action Deficiencies are not eligible for an incentive payment.
4. The Contractor will be assessed a disincentive assessment of \$1,000.00 per deficiency per calendar day for failure to begin corrective actions or failing to continue to completion as directed by the Engineer or by the regulatory agency with jurisdiction.
5. Examples of Immediate Action Deficiencies include but are not limited to:
 - a. Threatened & Endangered Species habitat protection deficiencies
 - b. USACE Section 404 Permit Noncompliance
 - c. Petroleum Spills/Tank Leakage
 - d. Hazardous Material Spills

J. Rights Reserved

1. The Department reserves the right to initiate and perform corrective action on any deficiencies which result from the Contractors' actions, inactions, or for failure to comply with the NPDES Construction Stormwater General Permit, USACE Section 404 Permit, or any other applicable permit.
2. The Contractor shall be liable to the Department for any and all costs incurred by the Department for corrective actions taken by the Department.
3. It is expressly understood that the provisions of this specification shall not relieve the Contractor of their responsibilities nor shall it relieve the Surety of its obligation for and concerning any just claim.
4. The Contractor shall indemnify and save harmless the Department and all of its representatives from any and all actions or claims brought because of the Contractor's actions, inactions, or for failure to comply with the NPDES Construction Storm Water General Permit, USACE Section 404 Permit, or any other applicable permit.

**ACCEPTANCE TESTING OF SOILS BY USE OF THE LIGHT WEIGHT
DEFLECTOMETER (LWD) SCOPE
(B-4-0915)**

This test method covers the in-place measurement of deflection and moisture content of Class III embankments, subgrade preparation, granular fill and backfill for acceptance testing on Nebraska Department of Roads Projects. Refer to Subsection 205.03 of the NDOR Standard Specifications for Highway Construction for a definition of Class III embankments. Refer to NDR Test Method T 2835 for the proper operation of the LWD.

The deflection test measurement shall be the average measured deflection of the fourth, fifth, and sixth drops of the falling weight of the LWD. The first three drops are to be used to seat the LWD.

The Deflection Target Value (DTV) is the deflection value of each soil determined by using a test strip or from correlation with the Nebraska Group Index for an individual Soil.

Option 1

A. Determination of DTV using a Test Strip

1. A test strip shall be constructed for each soil type to determine the deflection target value.
2. A new test strip shall be constructed when there is an observed change in material or as determined by the Engineer.
3. The test strip dimensions for roadway embankment and subgrades shall have a minimum length of 200 feet and a width equal to the embankment or roadway. The total thickness shall be no less than 6 inches for roadway subgrade and no less than 1-foot and no more than 3 feet for roadway embankment.
4. The test strip dimensions for trenches, culverts, and structures shall have a minimum length of 10 feet and a width equal to that of the excavation. The total thickness shall be no less than 1-foot and no more than 3 feet.
5. The optimum moisture of fine grained soils shall either be determined in the NDOR Branch Lab or Central Lab, and shall be based on a correlation with the Plastic Limit or determined from AASHTO T-99. A 10-lb sample of proposed material shall be submitted to the NDOR Branch Lab or Central Lab a minimum of 14 days prior to grading operations.
6. The moisture content for granular soils shall be "as necessary" to achieve proper compaction.
7. The moisture content limits of the soil shall follow the requirements provided in Table 1.
8. The test strip area construction shall be incidental to the embankment construction.
9. The testing rate during the test strip construction is provided in Table 2.

Table 1 - Moisture Requirements

Location	Soil Type	Depth Below Finished Subgrade	Minimum %	Maximum %
Soil materials receiving concrete pavement	Silt – Clay Silt- Clay Granular	Upper 3 feet Greater than 3 feet All Depths	Opt. -3 Opt. -3 **	Opt. +2 Opt. +2 **
Soil materials receiving flexible pavement	Silt – Clay Silt- Clay Granular	Upper 3 feet Greater than 3 feet All Depths	Opt. -2 Opt. -3 **	Opt. +1 Opt. +2 **
Soil materials receiving gravel surfacing	All materials	All Depths	**	**
Subgrade prep. Shoulder subgrade prep (concrete pavement)	Silt – Clay Granular	The upper 6 inches of subgrade soil	Opt. -3 **	Opt +2 **
Subgrade prep. Shoulder subgrade prep (flexible pavement)	Silt – Clay Granular	The upper 6 inches of subgrade soil	Opt. -2 **	Opt +1 **
Stabilized Subgrade	-	-	See Specifications	
Granular Structural Fill (MSE Walls, bridges, culverts, et.)	Granular	All Depths	**	**

** Moisture as necessary to obtain proper compaction. The moisture target value for granular materials shall be established in the field by the Contractor during the compaction process. Once established the target moisture shall not vary by more than $\pm 2\%$.

Table 2 - Test Strip Testing Rate

Material Location	Minimum Testing Rate
Roadway embankment and subgrade	3 tests/ pass*
Trenches, culverts, and miscellaneous structures	1 test / pass*

* Number of passes with compaction equipment as described in paragraph 14c of Subsection 205.03 of the NDOR Standard Specifications for Highway Construction.

B. Test Strip Construction and Testing

1. Prior to placing the fill material for the test strip, the subgrade shall be scarified and re-compacted.
2. The fill material shall be placed with a lift thickness no greater than 8 inches uncompacted.
3. The test strip shall be constructed with uniform material and moisture content, and compaction; until it meets the requirements of numbers 3 or 4 of Section A of this provision.

4. The deflection target value is obtained when:
 - i. The moisture content is within the acceptable range.
 - ii. The average of the deflection test measurements for three consecutive passes of compaction equipment does not change by more than 10% with additional compaction. The DTV shall be based on the lowest average deflection test measurement from these passes.
5. A 10-lb sample of the test strip material shall be submitted to the NDOR Branch Lab or Materials and Research Soil Lab for index testing.
6. The DTV shall be re-evaluated when:
 - i. Deflection test measurements are consistently less than the DTV. (3 out of 5 consecutive deflection test measurements are less than 0.80 of the DTV).
 - ii. Failing test results are consistently occurring and adequate compaction is observed.

Option 2

C. Determination of Deflection Target Values based on the Nebraska Group Index (NGI)

1. Prior to construction a 10-lb bag of representative material shall be submitted to the nearest NDOR Branch Lab or Materials and Research Soil Lab for each different soil type no less than 21 days prior to grading operations.
2. From the laboratory testing NDOR will determine the Nebraska Group Index (NGI) for each soil type submitted and provide a correlated minimum DTV and optimum moisture content.
3. If no correlation data is available for an individual NGI, a test strip shall be used to determine the DTV as discussed in parts A and B in this provision.
4. The DTV shall be re-evaluated when:
 - i. Deflection test measurements are consistently less than the DTV. (More than 20% of the deflection test measurements are less than 0.80 of the DTV).
 - ii. Failing test results are consistently occurring and adequate compaction is observed.

Acceptance Testing

1. The Deflection Target Value for use as acceptance testing shall be:

$$DTV \leq 1.10 \times \text{average deflection value determined from Option 1, Part B, of this provision}$$

$$DTV \leq \text{Correlated DTV determined from the NGI correlation, Option 2, Part C}$$

2. The testing frequency for moisture and deflection shall follow the NDOR Materials Sampling Guide.
3. The moisture content of soil shall be performed using NDOR's approved equipment and methods. Approved equipment includes: 1) hot plates, stove, or microwave, 2) Speedy Moisture Method, or 3) Laboratory oven method.
4. Moisture content results shall be reported to the nearest tenth of a percent.

GENERAL CLEARING AND GRUBBING

Clearing of the site for construction of the curb ramps shall be considered subsidiary to other items of work on this project.

EARTHWORK

Earthwork required as part of the work shown on this project shall be considered subsidiary to other items of payment. Each site (ramp) is assumed to have excess soils or borrow of 5 cubic yards or less unless otherwise noted on the plan sheet. The Contractor shall shape the adjacent soils within the limits shown and the existing Right of Way after construction of the curb ramps to provide for drainage and ease of maintenance of the areas. Slopes steeper than 3:1 will not be allowed without approval by NDOR.

SAWING PAVEMENT

Paragraph 5. of Subsection 203.04 in the Standard Specifications is void.

SUBGRADE PREPARATION (C-1-0307)

Paragraph 2.a. of Subsection 302.03 in the Standard Specifications is amended to include that trimming on narrow, irregular or roadway grading of 1/2 mile (0.8 km) or less may be accomplished using conventional methods.

TYPE B HIGH INTENSITY WARNING LIGHTS (D-6-0307)

All references in the plans to Type B High Intensity Warning Lights shall be considered void. The plans will not be revised to reflect this change.

**TEMPORARY TRAFFIC CONTROL DEVICES
(Type II Barricades, Reflectorized Drums, 42" (1070 mm) Reflective Cones, and
Vertical Panels)
(D-6-1112)**

Paragraph 2.d. of Subsection 422.03 in the Standard Specifications is void and superseded by the following:

- d. (1) Reflectorized drums used for traffic warning or channelization shall be constructed of lightweight, flexible, and deformable materials, be a minimum of 36 inches (900 mm) in height, and have a minimum width of 18 inches (450 mm), regardless of orientation. The predominant color of the drum shall be orange.
- (2) Steel drums shall not be used.
- (3) The markings on drums shall be horizontal, shall be circumferential, and shall display four 6-inch (150 mm) wide bands of retroreflective sheeting, alternating fluorescent orange - white – fluorescent orange - white. The fluorescent orange sheeting shall meet the luminance requirements of the following table.

FHWA Luminance Factor

Sheeting Type	Luminance Factor Y_T		
	Min	Max	Fluorescence Luminance Factor Limit, Y_F
Fluorescent Orange	25	None	15

- e. When approved by the Engineer or shown in the plans, 42" (1070 mm) reflective cones may be used in lieu of Type II Barricades or Reflectorized Drums. 42" (1070 mm) reflective cones shall include a 30-pound (14 kg) rubber base and display four 6-inch (150 mm) wide bands of retroreflective sheeting, alternating fluorescent orange - white - fluorescent orange - white. 42" (1070 mm) reflective cones shall not be used for lane-closure tapers or shifts.
- f. Rubber base-mounted 36-inch vertical panels shall not be used for channelization when the speed limit exceeds 40 miles per hour.

Paragraph 2.b. of Subsection 422.04 of the Standard Specifications is void and superseded by the following:

- b. (i) Type II Barricades, Reflectorized Drums, and 42" (1070 mm) Reflective Cones shall be counted as "Barricades, Type II" and measured for payment by the number of calendar days each is in place and positioned as shown in the plans or as directed by the Engineer.
- (ii) Vertical Panels shall be measured for payment as permanent "Sign Days" (by the each) by the number of calendar days each vertical panel unit is in place and positioned as shown in the plans or as directed by the Engineer.

Paragraph 2.c. of Subsection 422.04 of the Standard Specifications is amended to include Reflectorized Drums.

Paragraphs 3. and 4. of Subsection 422.05 of the Standard Specifications are void and superseded by the following:

3. a. The pay item "Barricade, Type II" is used to pay for three items ("Barricades, Type II", "42" (1070 mm) Reflectorized Cones", and "Reflectorized Drums").
- b. "Barricades, Type II", which includes "42" (1070 mm) Reflectorized Cones", and "Reflectorized Drums", is paid for as an "established" contract unit price item. The established unit price is identified on the "Schedule of Items" shown in the Proposal.
4. Payment for vertical panels includes all posts, brackets, or hardware necessary to install and maintain the vertical panel units.

WORK ZONE TRAFFIC CONTROL SIGNS (D-6-1212)

The Department has adopted the FHWA 2009 Manual of Uniform Traffic Control (MUTCD) and the 2011 Nebraska Supplement to the MUTCD as the official guidance for work zone traffic control signs. Many work zone traffic control signs have been revised, redesigned, or replaced in the 2009 MUTCD (and 2011 Nebraska Supplement). Accordingly, all work zone signs shall comply with the following:

- 1 - All signs, regardless of age, shall meet the design standards of the 2009 MUTCD (and 2011 Nebraska Supplement).

REMOVE AND RESET SIGN AND POST

Traffic control signs that will interfere with the construction work shall be removed, stored, and then reset upon completion of the construction work. The item "Remove and Reset Sign and Post" will be measured by the each and shall include removal of the sign and post, storage, and installation. It is anticipated that the existing sign and post will be re-used. If the Contractor damages either the sign or post during removal or storage, they shall be replaced at no additional cost to the Department. Traffic control signs that do not interfere with the proposed work shall be left in place and not disturbed or damaged.

REMOVE AND RELOCATE SIGN AND POST

Traffic control signs that will interfere with the permanent construction and placement of facilities shall be removed, stored, and then reset in a new location as directed by the Engineer upon completion of the construction work. The item "Remove and Relocate Sign and Post" will be measured by the each and shall include removal of the sign and post, storage, and installation in the relocated location. It is anticipated that the existing sign and post will be re-used. If the Contractor damages either the sign or post during removal or storage, they shall be replaced at no additional cost to the Department.

CONCRETE SURFACE MILLING

Subsection 510.04 of the Standard Specifications is amended to include the following:

The Contractor shall use waterblasting equipment operated with sufficient consistent pressure to effectively clean the pavement surface of all dirt, foreign materials, loose surfacing material, and any residue before placement of the asphaltic concrete overlay. Care shall be taken to prevent any debris or construction materials from entering any inlets on the project that lead directly to:

1. waterways,
2. poorly-vegetated ditches, or
3. well-vegetated ditches having less than 200 feet between the conduit outlet and the point of discharge of the ditch into a waterway.

Inlets shall not be blocked or otherwise restricted in such a way to cause water to collect within an active traffic lane.

The concrete must be completely dry before placement of any asphaltic concrete on these areas.

All material salvaged from this operation shall become the property of the Contractor and shall be removed from the project.

CONCRETE PAVEMENT CORING (F-17-0110)

Paragraphs 3. a. and 3.b. of Subsection 603.05 of the Standard Specifications are void and superseded by the following:

3. a. (1) A pay factor will be applied to each unit based on the compressive strength of 1 core per unit tested in accordance with AASHTO T 24.
- (2) Concrete cores must have a minimum age of 28 days before testing.
- (3) The paved area shall be divided into units, and each unit will be considered separately.
- (4) Units are 750 linear feet (230 m) of pavement for each separately placed width or width of each class of concrete whether or not placed separately starting at the beginning of the pavement.
- b. (1) When any unit core fails to have the required minimum compressive strength, the Contractor will have the option to obtain, at no cost to the Department, two additional cores from that unit provided that:
 - (i) The cores shall be cut by the contractor. (The cutting to be witnessed by the Engineer)

- (ii) The cores shall be cut within seven (7) days of being notified of the strength deficiency, and
 - (iii) The cores shall be cut within 6 inches of the original unit core in the longitudinal direction.
- (2) The Engineer will take possession of the cores and have them tested within 24 hours at the Materials and Research laboratory.
 - (3) The results of all three cores sampled at the location will be averaged for the final compressive strength calculation and pay factor.
 - (4) The Department may agree to cut the additional cores if requested to do so by the Contractor, but will do so only if the Department's coring crew is available on the project and has sufficient time to cut and transport the cores for testing during normal working hours within seven (7) days of the Contractor being notified of the strength deficiency.

Paragraph 4.a.(4) of Section 603.05 in the Standard Specifications is void and replaced by the following:

A separately placed width is the width between field constructed longitudinal joints, between a longitudinal construction joint and the edge, or between two pavement edges. A separately placed width may include more than one pay class of concrete, such as doweled and non-doweled.

**PORTLAND CEMENT CONCRETE PAVEMENTS
GENERAL REQUIREMENTS
(F-20-0611)**

Paragraph 7.b. of Subsection 601.02 in the Standard Specifications is void and superseded by the following:

- b. The finishing machine shall travel at a controlled speed such that it produces a uniform, well consolidated pavement that does not contain large voids.

Paragraph 10.d. of Subsection 601.02 is void and superseded by the following:

- d. The Contractor shall always have a tachometer available to monitor vibrator frequency. The vibrator frequency shall be within the manufacturer's specifications not to exceed 9,000 vpm.

Paragraph 12.d.(1) of Subsection 601.02 is void and superseded by the following:

- (1) The mechanical joint saw shall have an adjustable guide to insure a true line is cut. The mechanical joint saw blade shall be water-cooled, or specifically designed for early-entry sawing if air cooled.

Paragraph 12.d.(2) of Subsection 601.02 is void.

Paragraph 12.d.(3) of Subsection 601.02 is void and superseded by the following:

- d. (3) The joint cut shall be made with a diamond-toothed blade.

**CONCRETE PAVEMENT
(F-21-0611)**

Paragraph 2.a. of Subsection 603.03 in the Standard Specifications is amended to include the following:

- (6) The base material shall be moistened through a uniform, lightly applied spray pattern prior to concrete placement as directed by the Engineer.

Paragraphs 2.d. and e. of Subsection 603.03 are void and superseded by the following:

- d. After being consolidated with internal mechanical vibration, the concrete shall be struck off to a uniform height approximately 0.5 inch (12 mm) above the finished surface and then finished to the final elevation by means of a vibrating mechanical or vibrating hand operated screed.
- e. Finished concrete shall be of uniform density with no segregation, honeycombing, or large voids.

Paragraph 3.f. of Subsection 603.03 is void and superseded by the following:

- f. (1) A wet burlap, carpet, or canvas drag will be drawn over the entire surface in a longitudinal direction for a final finish, dampening of this drag material will be accomplished through a uniform, lightly applied spray pattern.
- (2) The drag shall be suspended from a mandrel, or similar device, to insure a uniform texture.
- (3) The drag shall be lifted from the surface of the concrete pavement when the paving train is not in motion for 30 minutes or more and carefully reset before resuming the dragging operations.
- (4) Drags shall be rinsed or washed as necessary to obtain a uniform surface. Drags that cannot be cleaned shall be replaced.

Paragraphs 4.e., f., g., and h. of Subsection 603.03 are void and superseded by the following:

- e. For areas with pavement widening, dowel baskets shall be placed in all transverse contraction joints which are 6 feet (1.8 mm) or wider.
- f. If normal vibration is found inadequate to thoroughly consolidate the plastic concrete within and around the dowel basket assemblies, adjustments to the material and/or operations shall be made.
- g. Precautions shall be taken to assure that the sawed contraction joint is located directly over the center of the dowel bars.
- h. Transverse cracks which form in the concrete pavement panels between load transfer joints shall be stitched as shown in the plans, described in the Special Provision or repaired as directed by the Engineer. No payment will be made for this work.

Paragraph 6.b.(7)(i) of Subsection 603.03 is void and superseded by the following:

- (7) (i) The concrete shall be textured by dragging a wet burlap, carpet, or canvas belt over the full width of the surface in a longitudinal direction. Dampening of this drag material will be accomplished through a uniform, lightly applied spray pattern.

Paragraph 6.c.(4)(i) of Subsection 603.03 is void and superseded by the following:

- (4) (i) The concrete shall be textured by dragging a wet burlap, carpet, or canvas belt over the full width of the surface in a longitudinal direction. Dampening of this drag material will be accomplished through a uniform, lightly applied spray pattern.

Paragraph 7.a.(3) of Subsection 603.03 is void and superseded by the following:

- (3) (i) The curing compound shall be applied in 2 equal applications immediately following each other or other methods approved by the Engineer.
- (ii) The total rate of applications shall be at a minimum of 1 Gal/100 SF (0.3 L/m²) of surface area for tined surfaces or 1 Gal/150 SF (0.2 L/m²) of surface area for all other finishes.

Paragraph 8.a.(6) of Subsection 603.03 is voided and superseded by the following:

- (6) Any panels that contain random cracking will be considered unacceptable. The Engineer will decide whether to replace or repair the panel. The Contractor shall replace or repair these panels at the direction of the Engineer at no cost to the Department. A 20% deduction will be assessed on any repaired panel. Any panel that is replaced will not be assessed a 20% deduction.

Paragraph 8.d.(3) of Subsection 603.03 is void.

Paragraphs 8.d.(4), (5) and (6) of Subsection 603.03 are void and superseded by the following:

- (4) Before sealing, the joint wall (not the bottom of joint) surfaces shall be sandblasted or water-blasted to remove all dirt, curing compound residue, laitance, and any other foreign material. After sandblasting, the entire joint shall be cleaned with compressed air having a minimum pressure of 90 psi (620 kPa). The compressed air shall be free of oil, water, and other contaminants. The joints shall be dry at the time of sealing.
- (5) (i) Transverse contraction joints in Portland cement concrete pavements shall be sealed so that the joint is filled to approximately 1/8" to 3/8" (3 to 9 mm) below the top of the joint with an approved hot poured sealant.
 - (ii) All overflow material shall be removed from the surface of the pavement.
 - (iii) If adhesion is not satisfactory, the material shall be rejected.
- (6) The Contractor shall give the Engineer one copy of the hot pour manufacturer's sealing recommendations.

Paragraph 9.b. of Subsection 603.03 in the 2007 edition of the NDOR Standard Specifications for Highway Construction is void and superseded by:

- b. When the pay item "Portland Cement Concrete Smoothness Testing" is not included in the contract, the Contractor shall test the hardened concrete for surface irregularities with a California Profilograph. Areas showing high spots (bumps) in excess of 0.30 inches in a 25 foot span will be plainly marked on the pavement and on the printed pavement profile trace. All identified high spots shall be ground to the required profile. The grinding shall be performed so that the cement-aggregate bond is not broken. The equipment and profilograph test procedure requirements of Section 602 of the Standard Specifications for Highway Construction shall apply to this surface testing.

Paragraph 9.c of Subsection 603.03 is amended to include:

- c. At the Engineer's option, the use of a 10 foot straightedge to locate high spots in excess of 1/8 inch may be allowed in lieu of bump detection using a profilograph testing.

Paragraphs 11.c., d. and e. of Subsection 603.03 are void and superseded by the following:

- c. The Contractor's forces may be allowed on the concrete pavement when the concrete has reached a minimum age of 14 days or when the concrete has reached a compressive strength of 3000 psi (24 MPa) when tested in accordance with ASTM C 39.
- d. With the approval of the Engineer, the Contractor may elect to increase the early strength of the concrete by adding cement and/or reducing the water/cement ratio, and then the pavement may be opened to traffic provided it has attained a compressive strength of 3500 psi (24 MPa). The concrete in the area where the early strength is required shall be paid for at the bid price.
- e. When required by the Special Provisions or when requested by the Contractor, the maturity method, as provided for in ASTM C 1074, may be used in lieu of the requirements of Subsection 603.03, Paragraph 10.c. and d. to determine the strength of concrete pavement for the purpose of early opening to traffic. Requests by the Contractor for use of the maturity method shall be on a project basis and shall be made in writing to the Materials and Research Engineer. The Contractor shall be responsible to coordinate with the Materials & Research Division to develop the maturity curve.

Paragraph 3.a. and b. of Subsection 603.05 is void and superseded by the following:

3. a. A pay factor will be applied to each unit based on the compressive strength of 1 core per unit tested in accordance with AASHTO T 24. Concrete cores must have a minimum age of 28 days before testing. The Contractor will have the option to obtain two additional cores for any unit core that fail to have the required minimum compressive strength provided that the cores are:
 - (1) Obtained and tested within seven (7) days of being notified of the strength deficiency, under the supervision of the Engineer.
 - (2) Cut within 6 inches of the original unit core in the longitudinal direction.

The results of all three cores sampled at the location will be averaged for the final compressive strength calculation and pay factor.

- b. The paved area shall be divided into units. Each unit will be considered separately. Units are 750 linear feet (230 m) of pavement for each separately placed width, or width of each class of concrete whether or not placed separately starting at the beginning of the pavement.

Paragraph 4.a.(7) of Subsection 603.05 is void and superseded by the following:

- (7) At the option of the Engineer, cores may not be required from irregular areas with widths less than 8 feet (2.4 m) or from an individual pavement type that involve less than 5,000 square yards (4200 m²) of pavement.

Paragraph 4.c.(4) of Subsection 603.05 is void and superseded by the following:

- (4) If the average thickness of the cores is deficient by more than 0.25 inch (6 mm) but not more than 0.50 inch (12.5 mm) an adjusted unit price will be paid in accordance with Table 603.04. Cores deficient by more than 0.50 inch (12.5 mm) will be treated as prescribed in Paragraph 4.d. of this Subsection.

ADJUST PULL BOX TO GRADE

If the existing pull box is in satisfactory condition as determined by the NDOR, the Contractor shall raise or lower the pull box to be flush with the new grade. Any fill needed to accomplish this task shall be compacted to the density requirements of the project. The item "Adjust Pull Box to Grade" will be measured for payment as a complete unit for each existing pull box adjusted to grade. Payment shall be considered full compensation for all work prescribed.

ADJUST VALVE BOX TO GRADE

If the existing valve box is in satisfactory condition as determined by the NDOR, the Contractor shall raise or lower the valve box to be flush with the new grade. Any fill needed to accomplish this task shall be compacted to the density requirements of the project. The item "Adjust Valve Box to Grade" will be measured for payment as a complete unit for each existing valve box adjusted to grade. Payment shall be considered full compensation for all work prescribed.

COLORED AND IMPRINTED CONCRETE SIDEWALKS

The colored concrete sidewalks shall comply with the requirements of Section 607 in the Standard Specifications except as amended by this Special Provision.

The color of the concrete pavement shall match the color of the existing colored sidewalk, as approved by the Engineer. Color shall be uniform throughout the entire sidewalk. The Engineer shall approve the color based on concrete samples made from the same samples that will be used in the concrete sidewalks.

The sidewalk shall be stamped with a pattern to match the existing pattern to a depth of 1/4" to 3/8".

Paragraph 5 of Subsection 607.03 shall be voided and replaced with the following:
Curing shall be according to the recommendations of the supplier of the coloring admixture.

Paragraph 1 of Subsection 607.05 is amended to include the following:

Pay Item	Pay Unit
Colored Imprinted Concrete 47B-3000 Sidewalks	Square Yard (SY)

**CURB WALL
(Height of 9 inches or less)**

The concrete curb walls with a height of 9 inches or less shall be constructed integral with the sidewalk as per the detail in the plan sheets. The NDOR shall determine if the curb wall is to be constructed, and identify the limits of the curb wall construction. All curb walls shall daylight at each end to match the grades and elevations of the existing conditions. All curb walls shall be located behind the pedestrian accessible route to avoid acting as an obstacle for the pedestrians. The face of the wall shall be nearly vertical and neat in appearance. The top edges shall be edged on the front and back. The concrete for this curb wall shall match that of the sidewalk concrete mix. The reinforcing steel shall be grade 60. The work to construct the curb wall shall consist of the necessary forming, placement of concrete, reinforcing and finishing needed to construct an integral, vertically faced concrete curb wall along the back line of the sidewalk to meet the grades, slopes, and elevations of the existing ground conditions. Locations for this work shall be confirmed by the NDOR prior to installation. All work described under this Curb Wall item shall be considered subsidiary to the pay item for concrete sidewalks.

**CURB WALL
(Taller than 9 inches)**

In locations where a concrete curb wall would exceed 9 inches in height, the work shall be constructed using a minimum 6" tall modular blocks for retaining walls. The color of the modular blocks shall be a standard grey color unless the property has existing modular block retaining walls, then the color that best matches the existing shall be used. The work to construct the curb wall using modular blocks shall be completed as per Section 715 of the NDOR Standard Specifications for Highway Construction.

ADJUST INLET TO GRADE

At locations where the pavement around an area inlet is removed, the inlet shall be adjusted as needed to match the new pavement grades. In addition, some locations will require that the current grate and frame be replaced with one that is ADA compliant. The Contractor shall submit the proposed grate and frame specifications to the NDOR for approval prior to ordering or installing the grate and frame. The item "Adjust Inlet to Grade" will be measured for payment as a complete unit for each existing inlet adjusted to grade. Payment for the grate and frame will be paid under the pay item "Cast Iron Grate" based on the weight of the assembly. Payment shall be considered full compensation for all work prescribed.

SEEDING

Subsection 803.02 in the Standard Specifications is amended to include the following:

Type "C"	Minimum Purity	Broadcast Application Rate in lb. of Pure Live Seed/Acre	Approved Mechanical Drill Application Rate in lb. of Pure Live Seed/Acre
Fine-leaf perennial ryegrass	85	33.75	22.5
Turf-type tall fescue	85	594	396
Kentucky bluegrass	85	47.25	31.5

All seeds shall be origin Nebraska, adjoining states, or as specified. A contractor proposing to use a substitute variety or origin shall submit for the Engineer's consideration a seed tag representing the seed, which shows the variety, origin and analysis of the seed.

Rate of application of commercial inorganic fertilizer shall be:

	Rate of Application per Acre (Minimum)
Available Nitrogen (N ₂)	19 or 36 lbs.
Available Phosphoric Acid (P ₂ O ₅)	0 lbs.

Rate of application of granular sulphur coated urea fertilizer shall be:

Nitrogen (Total Available)	0 lbs.
----------------------------	--------

The contractor may, at his option, apply granular urea formaldehyde in lieu of the sulphur coated urea fertilizer at the following rate:

Nitrogen (Total Available)	0 lbs.
----------------------------	--------

Paragraph 6. of Subsection 803.02 is void and superseded by the following:

6. Mulch shall be hydromulch as prescribed elsewhere in these Special Provisions.

INLET PROTECTION

Description

This work shall consist of installing, maintaining, and removing manufactured or site constructed curb inlet and area inlet protection devices at locations shown on the plans, temporary erosion control plans, or as directed by the Engineer.

Material Requirements

1. Inlet protection devices shall be constructed as shown in the plans.
2. Manufactured inlet protection devices shall be selected from the NDOR Approved Products List.

Construction Methods

1. Inlet protection shall be manufactured or site constructed devices.
 - a. Inlet protection shall be the type shown on the plans, temporary erosion control plans, or approved by the Engineer.
 - b. Approved manufactured products shall be installed as per manufacturer's recommendations. The Engineer shall be given a copy of the instructions before installation.
 - c. Site constructed protection shall be approved by the Engineer.
 - d. Inlet protection devices shall be installed in a manner to prevent ponding of stormwater on the roadway.
2. Inlet protection devices shall be maintained, repaired, and repositioned to provide effective protection.
 - a. The Contractor shall remove and dispose of sediment that accumulates near the inlet protection device when it is at 50% capacity on closed roadways.
 - b. The Contractor shall remove and dispose of all sediment from the roadway within 24 hours of the end of a storm event on roadways open to traffic.
3. Inlet protection devices shall be removed at the completion of the project, or when the Engineer determines it is no longer effective, or as directed by the Engineer.

Method of Measurement

1. Area Inlet Protection will be measured based on each location installed.
2. Curb Inlet Protection will be measured based on each location installed.
3. Silt removal will be measured based on equipment rental.
4. Maintenance, repair, repositioning and any handwork required in the maintenance operation of an inlet protection device to a good working condition will not be measured for payment, but will be considered subsidiary to the appropriate inlet protection item.
5. Removal of inlet protection devices shall be subsidiary to the installation of the item. Inlet protection devices shall remain the property of the Contractor.

Basis of Payment

- | 1. Pay Item | Pay Unit |
|---------------------------------------|-----------------|
| Area Inlet Sediment Filter | Each |
| Curb Inlet Sediment Filter | Each |
| Rental of Skid Loader, Fully Operated | Hour |
| Rental of Loader, Fully Operated | Hour |
| Rental of Dump Truck, Fully Operated | Hour |
2. Payment will not be made for individual components of the device installed.
 3. Payment is full compensation for all work prescribed in this Section.

**HYDROMULCHING
(H-20-1015)**

Description

This work shall consist of furnishing and placing hydromulch on areas shown in the plans or as directed by the Engineer.

Material Requirements

1. Hydromulches will be specified in the contract and selected from the Approved Products List.
 - a. Bonded Fiber Matrix (BFM) is a hydraulically-applied matrix containing organic defibrated fibers and cross-linked insoluble hydro-colloidal tackifiers to provide erosion control and facilitate vegetation establishment on 3:1 slopes and ditches less than 2.5%. The products are designed to be functional for a minimum of 6 months.
2. The hydromulch shall be delivered to the site in packaging that clearly identifies the manufacturer, type of hydromulch and weight per bag.
3. The Contractor shall provide the necessary water required for the hydromulching operation.

Construction Methods

1. The Contractor shall apply the hydromulch within 24 hours after planting the seed or as directed by the Engineer. The hydromulch shall be applied uniformly over tilled areas with a hydromulch machine.
2. Application Rates:
 - a. Hydromulch shall be applied at 1.5 tons per acre.
 - b. The required tons of hydromulch will be determined by multiplying 1.5 tons per acre by the acres of application.

- c. The Engineer may direct the Contractor, in writing, to adjust the application rate resulting in an increase or decrease the required tons of hydromulch.
- 3. The Contractor shall refer to the manufacturer's recommendations for appropriate matrix to water ratios.
- 4. The hydromulch shall be applied ensure complete and uniform coverage. The Contractor shall apply the hydromulch from opposing directions or as directed by the Engineer.

Method of Measurement

- 1. Hydromulch is measured by the ton.
- 2. The weight of hydromulch applied will be computed on the basis of the weight per bag multiplied by the number of bags used.

Basis of Payment

- | | | |
|----|-------------------------------|------------------------|
| 1. | Pay Item
Hydromulch | Pay Unit
Ton |
|----|-------------------------------|------------------------|
- 2. Final Quantity Determination:
 - a. If the computed tons of the hydromulch applied are within 5 percent (+/-) of the tons required as determined by the approved application rate, the final pay quantity will be the computed weight.
 - b. If the computed tons of the hydromulch applied are less than 95 percent of the tons required as determined by the approved application rate, the Contractor shall apply additional hydromulch at locations as directed by the Engineer. The final pay quantity will be the computed weight after the additional application has been applied and will not exceed 105 percent of the tons required as determined by the approved application rate.
 - c. If the computed quantity of the hydromulch applied exceeds 105 percent of the tons required as determined by the approved application rate, the final pay quantity will not exceed 105 percent of the tons required as determined by the approved application rate.
 - d. If upon visual inspection, the Engineer determines that the hydromulch application is "light" in some areas, even though the required tons as determined by the approved application rate was applied to the overall area of application, the Contractor shall apply additional hydromulch as directed by the Engineer. The final pay quantity will be the computed weight after the additional application has been applied and will not exceed 105 percent of the tons required as determined by the approved application rate. The quantity of hydromulch applied that is in excess of 105 percent of the tons required as determined by the approved application rate shall be at no additional cost to the Department.

3. Direct payment for water incorporated into the hydromulch will not be made. Water is subsidiary to the item of Hydromulch.
4. Payment is full compensation for all work prescribed in this Section.

**PORTLAND CEMENT CONCRETE
(J-15-0216)**

Paragraph 1. of Subsection 1002.02 in the Standard Specifications is amended to include the following:

Concrete mixes will be in accordance of Table 1002.02.

Paragraph 3. of Subsection 1002.02 is void and superseded by the following:

3. Type IP, IS and IT Interground/Blended cement shall be used for all classes of concrete except for pavement repair. Type IP, IS and IT Interground/Blended cement shall meet all requirements of ASTM C 595. Pavement repair shall include Type I/II Portland Cement for Class PR1 Concrete and Type III Portland Cement shall be used in Class PR3 Concrete.

Tables 1002.02 and 1002.03 in Subsection 1002.02 are void and superseded by the following:

**ENGLISH
TABLE 1002.02**

Class of Concrete (1)	Base Cement Type	Total Cementitious Materials Min. lb/cy	Total Aggregate		Air Content % Min.-Max. (2)	Coarse Aggregate (%)	Water/Cement Ratio Max. (3)	Required Strength Min. psi
			Min. lb/cy	Max. lb/cy				
47B**	IP/IS/IT*	564	2850	3150	6.5 - 9.0	-	0.45	3500
47B***		564	2850	3150	6.0 - 8.5	-	0.45	3500
47BD		658	2500	3000	6.0 - 8.5	30+3	0.42	4000
47B-HE		752	2500	3000	6.0 - 8.5	30±3	0.40	3500
BX(4)		564	2850	3150	6.0 - 8.5	-	0.45	3500
47B-OL****		564	2850	3200	5.0 - 7.0	30±3	0.36	4000
PR1	I/II	752	2500	2950	6.0 - 8.5	30±3	0.36	3500
PR3	III	799	2500	2950	6.0 - 8.5	30±3	0.45	3500
SF(5)	I/II	589	2850	3200	6.0 - 8.5	50±3	0.36	4000

- (1) Each class of concrete shall identify the minimum strength requirement, per plans and specifications.
All classes of concrete shall be air-entrained and a water-reducing admixture shall be used per manufacture’s recommendations.
 - Class R Combined Aggregate shall use a mid-range water reducer admixture. The dosage shall be at the manufacture’s recommendation and the Engineer may approve a low-range water reducer admixture.
- (2) As determined by ASTM C 138 or ASTM C 231.
FOR INFORMATION ONLY. The Contractor may develop a Quality Control Program to check the quantity of air content on any given project; such as, checking the air content behind the paver.
- (3) The Contractor is responsible to adjust the water/cement ratio so that the concrete supplied achieves the required compressive strength without exceeding the maximum water/cement ratio. The minimum water/cement ratio for any slip form concrete pavement is 0.38, unless the Contractor requests approval from the Engineer in writing to change the minimum water/cement ratio to 0.36.
- (4) For temporary surfacing, Type I/II cement is allowed.
- (5) Minimum Portland Cement shall be 564 lbs/cyds and the total Silica Fume added shall be 25 lbs/cyds.

(*) Refer to Subsection 1004.02 for material characteristics.
Lithium Nitrate may be used in place of Supplemental Cementitious Materials (SCMs), see Section 1007 of the Standard Specifications as modified in these Special Provisions.
 (**) For slip form applications.
 (***) For hand-pours and substructures applications.
 (****) When IP using Class N pozzolan, the maximum water/cement ratio is 0.41.

Table 1002.03	
Table of Acceptable Concrete Class Substitutions	
Class Specified	Acceptable Class for Substitution
BX	47B, 47BD or 47B-HE
47B	47BD or 47B-HE

Paragraphs 5., 6., 7., 8., 9. and 10. of Subsection 1002.02 are void and superseded by the following:

5. Class PR1 and PR3 Concrete:
 - a. The calcium chloride for use in PR concrete shall be either:
 - (1) A commercially prepared solution with a concentration of approximately 32 percent by weight.
 - (2) A Contractor prepared solution made by dissolving 4.5 pounds of Grade 2 or 6.2 pounds of Grade 1 calcium chloride per gallon of water to provide a solution of approximately 32 percent by weight.
 - b. The 7.4 pounds of water in each gallon of solution shall be considered part of the total water per batch of concrete.
 - c. The calcium chloride solution shall be added, just prior to placement, at a rate of 0.375 gallons/100 pounds of cement (1.4 lb. calcium chloride per 100 lb. cement).
 - d. Class A, Flaked or Pellet Calcium Chloride shall be added at a rate not to exceed 2.0 percent of the weight of the cement for Grade 1, or 1.6 percent of the weight of the cement for Grade 2. Grade 1 Calcium Chloride purity is between 70 and 90 percent and Grade 2 Calcium Chloride is between 91 and 100 percent.
 - e. Where mixing trucks are used:
 - (1) For Class PR3 Concrete, calcium chloride shall be thoroughly mixed into the concrete before placement. The minimum mixing time is 2 minutes.
 - (2) For Class PR1 Concrete, calcium chloride shall be added first and then the concrete mixed at least 2 minutes or as required by manufacturer. Next, the Type F high range water-reducer admixture is added and the concrete is mixed an additional 5 minutes.

6. Class High Early (47B-HE) Concrete
 - a. High Early (47B-HE) concrete shall be cured as prescribed in Subsection 603.03, Paragraph 7. The Contractor shall take necessary curing measures so the required strength is achieved.
 - b. High Early concrete shall achieve a compressive strength of 3,500 psi at 48 hours after placement.

- c. The 48-hour compressive strengths shall be used to determine pay factor deductions for high early concrete in accordance with Table 603.03.
 - d. A non-calcium chloride accelerator shall be used when the ambient temperature at the time of the placement of concrete is 70°F or less.
 - e. When requested by the Contractor, the maturity method, as provided in NDR C 1074, may be used in lieu of the requirements of Subsection 603.03, Paragraphs 11.c. and d. to determine the strength of concrete pavement for the purpose of early opening to traffic and acceptance. Requests by the Contractor for use of the maturity method shall be on a project basis and shall be made in writing to the Engineer.
- 7. The yield of the concrete proportions shall be determined and adjusted by the Producer.
 - 8. All Classes of Concrete with the exception of PR1 and PR3 shall have a Durability Factor not less than 70 and a mass loss not greater than five percent after 300 freeze/thaw cycles when tested in accordance with ASTM C 666. The freeze/thaw testing shall be conducted according to Procedure A.

Paragraphs 1. & 2. of Subsection 1002.03 are void and superseded by the following:

- 1. The Contractor shall identify the plant that will supply the concrete 14 days before use and be entirely responsible for its calibration, batching of concrete, aggregate and sampling of cement per NDR Sampling Guide.
 - a. The Contractor shall be responsible for the following:
 - 1) Batching concrete.
 - 2) Contractor shall sample aggregate from the conveyor belt or stockpile. Gradations from a split sample shall be tested in accordance to Section 1033 and reported to the Engineer at the frequency required by the Materials Sampling Guide.
 - i. Contractor shall retain possession of the split samples on-site at the Contractor's facility until such a time as determined by the Engineer.
 - a. At the pre-construction meeting:
 - 1) Contractor shall determine the location of testing and report the names of the technician performing the sampling and testing.
 - 2) Engineer will notify the Contractor of the retrieval of the split samples.

- ii. The Contractor shall split the sample, place the Department's split sample into a cloth bag and immediately seal the split sample with the provided security seal. The cloth sample bag shall be supplied by the Department.
 - iii. The sampling splitting and placement of the security seal of aggregate samples shall be witnessed by certified Department personnel.
 - iv. Contractor shall secure the split sample using a consecutively numbered security seal of 75 pounds breaking strength provided by the Department. The Contractor shall use the consecutively numbered security seals to identify and track each Aggregate Class. Samples that are not consecutively numbered will be investigated for custody of the sample and the Engineer may cease production until it is determined what action will be required.
 - a. The Contractor shall report the security seal tracking number with the split sample gradation.
 - b. The following training shall be required for personnel who oversee the batching of the concrete:
 - 1) Concrete Technician Personnel
 - i. Concrete Plant Technician
 - 2) Portland Cement Sampler
 - i. NDR Portland Cement Sampler
2. Portland Cement Concrete shall be supplied by certified Ready Mix Plants that are in compliance with the requirements in the *Quality Control Manual*, Section 3, -- Certification of Ready Mixed Concrete Production Facilities published by the National Ready Mixed Concrete Association. Refer to NDR Material Sampling Guide for the policy on stationary and portable plants.

Paragraph 4. of Subsection 1002.03 is void and superseded by the following:

- 4. a. Mix times shall meet the requirements of ASTM C 94. Mixing time tests shall be repeated whenever the concrete appearance indicates that mixing was inadequate.
- b. Batch plants that are transporting the concrete in non-agitating trucks, the mixing time will not be less than 60 seconds, and for agitating trucks, the mixing time will not be less than 45 seconds.
- c. The Certification of stationary and portable ready mix plants will conform to the tests that are required in the NDR Materials Sampling Guide.

Paragraph 6. of Subsection 1002.03 is void and superseded by the following:

6. Batch tickets shall be prepared as prescribed in the National Ready Mixed Concrete Association's *Quality Control Manual*. The Contractor shall keep all gradations and batch tickets until final acceptance by the Department. Projects that have less than 200 cubic yards of concrete placed will be allowed to have hand written tickets. For projects greater than 200 cubic yards, hand written tickets will be at the Engineer's discretion. The concrete batch tickets shall show batch weights, aggregate moisture (shall be tested daily and moisture probes are allowed), admixtures used, water, and mix design calculations. A copy of the batch ticket shall be given to the Engineer upon delivery of concrete.

Paragraph 8. of Subsection 1002.03 is void and superseded by the following:

8. Coarse aggregate from a dry pit shall be uniformly saturated with water before it is used. The wetting shall begin 24 hours prior to the concrete mixing to allow complete saturation.

Paragraph 13.a. of Subsection 1002.03 is void and superseded by the following:

13. a. The quantity of water shall be determined by the Contractor. The minimum quantity of water should be used which will produce required workability. Any additional water used to rinse the charging hopper and fins after the batching of concrete is allowed. This water must be estimated and recorded on the batch ticket.

Subsection 1002.04 is void and superseded by the following:

1. Class 47B Concrete Mix Design Submittal:
 - a. The Contractor shall submit the Concrete Mix Design Worksheet consisting of design mix proportions, testing of mix design from a minimum of 4 cubic yards and aggregate data for 47B class of concrete being placed on the project.
 - (1) All testing must be performed by a qualified laboratory found on the NDR's Material and Research website, under the *Nebraska Qualified Consultant & LPA Laboratories* and submitted to the Engineer.
 - (2) The Concrete Mix Design shall be submitted to the Engineer 4 weeks prior to any concrete being placed on the project.
 - (3) The Concrete Mix Design shall not be paid for directly by the Department and shall be subsidiary to items which direct payment is made.
 - (4) Concrete shall not be placed on the project before the Concrete Mix Design Worksheet has been reviewed and approved by the Engineer.

b. The Contractor shall submit the Concrete Mix Design Worksheet to the Engineer. Email submissions are preferred but will be accepted by fax or postal mail.

(1) Contractor's Mix Design Worksheet can be found on the Materials and Research website. The submitted Mix Design Worksheet shall include the following:

- Contractor Name
- Project Number
- Date
- Location of ready mix or central mix plant
- Date submitted
- Signature of Contractor representative

(2) Material Source Information.

- Cement Manufacturer
- Type of Interground/Blended Cement
- Type of Admixtures
- Aggregate Pit and Quarry location

(3) Specific Gravity of each individual aggregate source.

(4) Sand Equivalent for dry pit sand-gravel aggregate.

(5) Combined Aggregate percent passing as described on Table 1033.03C.

(6) Contractor's Target combined aggregate gradation percent passing.

(i) The Contractor's required worksheet can be found on the Materials and Research website.

(7) Testing of Mix Design:

The mix design shall show the weights of all ingredients including Interground/Blended cements, aggregates, water, admixtures types and water cement ratio.

- Temperature of concrete at time of sampling, ASTM C 1064.
- The air content of plastic concrete, ASTM C 231.
- Weight per cubic foot, Yield, ASTM C 138. The relative Yield shall be a minimum of 97%.

- Compressive strength shall be performed with a minimum of three averaged specimens at 7-day and 28-day, ASTM C 39. The minimum 28-day compressive strength shall be 3500 psi.
- (8) Traditional 47B Mix Design is defined as a 70 percent Class B Aggregate and 30 percent Class E Aggregate may be exempt from the concrete testing described in Paragraph 1.(b)(7). All other requirements shall be included in the Concrete Mix Design Report.
- c. The PCC Engineer will notify the Contractor of the mix design approval for Class 47B Concrete. Approval of the mix design does not alleviate the Contractor of the responsibility of the in-place concrete. The Contractor may adjust admixtures, water cement ratio, vibrator frequency, etc., as needed in accordance to the specifications.
- d. The Contractor shall submit a new concrete mix design worksheet meeting the above requirements when a change occurs in the source, type, or proportions of cements or aggregates; unless otherwise approved by the Engineer.
2. The quantity of water to be used shall be determined by the Contractor. It shall not be varied without the Engineer's consent.
3. If the concrete mixture is excessively wet causing segregation, excessive bleeding, excessively dry or any other undesirable condition, the concrete shall be rejected. At the option of the Engineer, slump tests may be performed to determine the consistency.
4. Concrete which has developed initial set before it is consolidated and finished shall be rejected.
5. a. If false set is encountered, the batching operation shall be stopped until the problem is resolved.
- b. Each batch must be mixed or agitated for at least 3 additional minutes after observing the false set and the concrete must be of satisfactory consistency.
6. Compressive strength tests shall be made in accordance with ASTM C 39.
7. Concrete shall be sampled as prescribed in the NDR *Materials Sampling Guide*. Samples shall be taken at the point of placement, never before the discharge from the last conveyance.
8. Aggregate Acceptance, Verification, Sampling and Testing:
- a. The aggregate will be accepted based on the Contractor's testing results except as noted below.

- b. The aggregate verification sampling and testing by the Department will be randomly selected and tested according to subplot sizes in Table 1002.05.

Table 1002.05

Aggregate Class	Lot	Sublot
E and F	3000 tons	1000 tons
A,B and C	6000 tons	2000 tons
R	6000 tons	2000 tons

- c. The results of Contractor split sample will be verified by the Department's verification tests. Any samples outside of the tolerances as specified according to the Materials Sampling Guide, Section 28 under the *Acceptable Tolerance Limits for Independent Assurance* will result in an Independent Assurance (IA) review of testing and may result in the Department test results being applied.
- d. On any given Lot, if the results of the gradation from the verification test are within Department's specification, the Contractor's results will be used for the entire lot. On any given Lot, if the gradations results from the verification test are outside Department's specification, further investigation will be initiated by the Engineer for that subplot. Any or all of the remaining Department subplot samples may be tested and the Department subplot test results may be applied to the respective subplot and the acceptance will apply.
- e. When verification tests are within testing tolerance but results show a consistent pattern of deviation from the split sample results, the Engineer will exercise one or more of the following:
- Cease production.
 - Request additional verification testing.
 - Initiate a complete IA review.
- f. Independent Assurance (IA) Review of Testing:
- 1) The Contractor shall allow the Department personnel access to the Contractors' laboratory to conduct IA review of the technician testing procedures and apparatus. Any deficiencies discovered in the Contractor's testing procedures will be reported to the Contractor and corrected by the Contractor.
 - 2) During the IA review, the Department personnel and the Contractor shall split a sample for the purpose of IA testing. The samples selected will be tested in the Department's Branch Laboratory. Any IA test results found to be outside of defined testing tolerances as stated in Paragraph 8.c. of Subsection 1002.04 will be reported to the Contractor. The Contractor shall immediately correct any deficiencies found during the IA review.

- 3) If the project personnel and the Contractor cannot reach agreement on the accuracy of the test results, the Department Central Laboratory will be asked to resolve the dispute, which will be final. All dispute resolutions will be in accordance with the Quality Assurance Program requirements in the NDR's Materials Sampling Guide.

PORTLAND AND INTERGROUND/BLENDED CEMENT (J-15-0216)

Section 1004 in the Standard Specifications is void and superseded by the following:

1004.01 – Description

1. Portland cement is the binder in concrete, locking the aggregate into a solid structure. It is manufactured from Lime, Silica, and Alumina (with a small amount of plaster of Gypsum).
2. Equivalent alkali referred to herein is hereby defined as the sum of the Sodium Oxide (Na_2O) and the Potassium Oxide (K_2O) calculated as Equivalent Alkali $\text{Na}_2\text{O}_e = \text{Na}_2\text{O} + 0.658 \text{K}_2\text{O}$.
3. Interground and Blended cements consist of intimate and uniform intergrinding or blending of Portland cement clinker, Slag cement, Pozzolan and/or Limestone.

1004.02 – Material Characteristics

1. Type I, Type II, Type I/II and Type III Portland cement shall conform to the requirements in ASTM C 150 with the following additional requirements:
 - a. Portland cement shall not contain more than 0.60 percent equivalent alkali.
2. Interground and Blended Cement shall conform to the requirements in ASTM C 595 with the following additional requirements:
 - a. Interground/Blended cement (Type IP)
 - (1) For Type IP(25) shall be composed of Class F fly ash or Class N pozzolan replacement shall be $25\% \pm 2\%$.
 - (2) For Type IP(20) shall be composed of Class F fly ash or Class N pozzolan replacement shall be $20\% + 2\%$.
 - b. Interground/Blended cement (Type IS)
 - (1) For Slag Cement, the maximum replacement shall be $35\% +5$ when incorporated into the final Interground/Blended cement.

- c. Interground/Blended cement (Type IT)
 - (1) For SCMs, Slag cement and Limestone, the maximum replacement by weight shall be 40%. The manufacturer has a production tolerance of $\pm 2\%$ from the proposed replacement.
 - (2) For Limestone cement, the replacement range shall be from 5.1% to 10.0% when incorporated into the final Interground/Blended cement.
- d. No additional SCMs, Slag cement and Limestone will be added at the batch plant.

1004.03 – Procedures

1. The Contractor shall provide adequate protection for the Portland and Interground/Blended cement against dampness.
 - a. Portland and Interground/Blended cement shall be hauled or stored in railroad cars, dry bulk trailers or in suitable moisture-proof buildings.
 - b. The use of tarpaulins for the protection of the Portland and Interground/Blended cement against moisture will not be allowed.
2. No Portland and Interground/Blended cement which has become caked or lumpy shall be used.
3. Portland and Interground/Blended cement which has been spilled shall not be used.
4. Accepted Portland and Interground/Blended cement which has been held in storage at the concrete mix plant more than 90 days shall be retested.
5. Portland and Interground/Blended cement coming directly from the manufacturer shall not be used until the temperature is 150°F or less.
6. Portland cement having false set when tested in accordance with in ASTM C 150 will not be used.

1004.04 – Acceptance Requirements

1. For Department projects, Portland and Interground/Blended cements must be on the NDR Approved Product List (APL).
2. The Contractor shall submit any new Portland and Interground/Blended cements to the Engineer to be approved for the APL with the following:
 - a. Material source information:
 - 1) Mill Location
 - 2) Type of Portland and Interground/Blended cements
 - 3) Grinding Period

- 4) Associated Manufacture Product Name
 - 5) Provide source and type of each SCMs and/or Slag Cement used for final product.
 - (i) The Department will allow the use of ASTM C 1697.
 - a. When two or more SCMs and/or Slag Cement are pre-blended, the Contractor shall report chemical composition analysis of the final blend.
 - b. The final blend shall be reported as per ASTM C 1697, Paragraph 4.
 - 6) Portland cement shall conform to ASTM C 150.
 - 7) Interground/blended cements shall conform to ASTM C 595.
 - 8) Provide total cementitious materials replacement per ASTM C 595.
 - 9) Report test results per ASTM C 1567 at 28-days.
3. Alkali Silica Reaction Requirements and Testing:
- a. Interground/Blended cement shall be tested according to the provisions of ASTM C 1567.
 - (1) The mortar bars shall be composed of Type IP, IS or IT Interground/blended cement and sand and gravel from an approved Platte River Valley-Saunders County source.
 - i. When Elkhorn River-Madison County source or an out of state aggregate source is being used on a project, the Elkhorn River or an out of state aggregate source shall be used in lieu of the Platte River Valley-Saunders County source.
 - ii. When Contractor proposes a change of aggregate source, then the new aggregate source shall be tested by ASTM C 1567.
 - (2) The mortar bars for the ASTM C 1567 shall not exceed 0.10% expansion at 28 days.
4. Portland and Interground/Blended cements will be placed on NDR's APL based on the conformance with the NDR's Acceptance Policy Portland and Interground/Blended Cements.

1004.05 - Sampling and Testing Requirements

1. All Portland and Interground/Blended cements shall be sampled and tested at the rate as described in the NDR's Materials Sampling Guide.
 - a. The Department will inform the Contractor when a sample is required.

- b. A sample shall be taken by a Contractor's Certified Portland Cement Sampler and must be under the supervision of Department certified personnel.
 - c. The sample shall be taken at the plant from a bulk shipment of a rail car, dry bulk trailer, batch plant silo or from the line between the bulk truck and the silo. Upon sampling, the Department will take immediate custody of the sample.
2. Noncompliant material shall be tested in accordance with ASTM C 1567 and in accordance with Section 1004.04, Paragraph 3.a. (1).
 - i. The mortar bars for the ASTM C 1567 shall not exceed 0.10% expansion at 28 days.
 - ii. If the expansion is greater than 0.10% at 28 days, then the Interground/Blended cement shall be subject to removal, 40% pay and/or removal from NDR's APL in accordance with NDR's Acceptance Policy on Portland and Interground/Blended Cements.
 3. Noncompliant material from the mill, terminal or project will be temporarily removed from the Approved Products List pending further investigation.
 4. If the noncompliant Portland or Interground/Blended cement is removed from the Approval Products List, all shipments from the supplier will be held until the investigation of the failing samples have been completed by the NDR Materials and Research Division.

WATER FOR CONCRETE (J-15-0214)

Section 1005 in the Standard Specifications is void and superseded by the following:

1005.01 – Description

1. Water shall be free from objectionable quantities of oil, acid, alkali, salt, organic matter, or other deleterious materials and shall not be used until the source of supply has been approved.
2. Wash water from the mixer washout may be used only with the Engineer's approval. Use of wash water will be discontinued if undesirable reaction with admixtures or aggregates occurs.

1005.02 – Material Characteristics

1. Water which contains more than 0.25 percent total solids by weight shall not be used.
2. When required by the Engineer, the quality of mixing water shall be determined by NDR C 114, NDR T 290, NDR D 512, NDR C 1602, ASTM C 31, ASTM C 109, ASTM C 191, and ASTM C 1603.

3. Upon written request by the concrete producer and approval by Materials and Research, the concrete producer may utilize up to 10% wash water for batching all classes of concrete with the following conditions:
 - a. Wash water shall conform to the requirements in NDR's Material Sampling Guide under Policy for Certification of Ready Mix Plants.
 - b. Wash water must be clarified wash water that has been passed through a settling pond system.
 - c. Wash water must be scalped off of a settling basin that has been undisturbed for a minimum of 12 hours.
 - d. Wash water must be metered into each load.
 - e. Wash water quantities shall be shown on the batch ticket.

CALCIUM CHLORIDE (J-15-0214)

Section 1006 of the Standard Specifications is void and superseded by the following:

1006.01 – Description

Calcium Chloride shall be Type S (Solid) or Type L (Liquid). Calcium Chloride can be used for; but not limited to, dust control and acceleration of the set of concrete.

1006.02 – Material Characteristics

The requirements for calcium chloride shall be tested in accordance with ASTM D 98.

1006.03 – Acceptance Requirements

Acceptance shall be based on requirements contained in the NDR Materials Sampling Guide.

SECTION 1007 -- CHEMICAL ADMIXTURES (J-15-0214)

Section 1007 in the Standard Specifications is void and superseded by the following:

1007.01 -- Description

1. Admixtures are materials added to Portland cement concrete to change characteristics such as workability, strength, permeability, freezing point, and curing.
2. The Department's concrete admixture types are:
 - a. Type A - Water-Reducing Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump.

- b. Type B - Retarding Admixture - An admixture that slows the setting of concrete.
- c. Type C - Accelerating Admixture - An admixture that speeds the setting and early strength development of concrete.
- d. Type D - Water-Reducing and Retarding Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump and slows the setting of concrete.
- e. Type E - Water-Reducing and Accelerating Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump and speeds the setting and early strength development of concrete.
- f. Type F - Water-Reducing, High Range Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump by 12 percent or greater.
- g. Type G - Water-Reducing, High Range and Retarding Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump by 12 percent or greater and slows the setting of concrete.
- h. Air-Entraining - An admixture that encapsulates air in the concrete.
- i. Lithium Nitrate – An admixture used to control the Akali Silica Reaction (ASR) in concrete.

1007.02 -- Material Characteristics

- 1. Type A through G admixtures shall meet the requirements in ASTM C 494.
- 2. Air-entraining admixtures shall meet the requirements in ASTM C 260.
- 3. Use of admixtures other than those cited may be requested by the Contractor.
- 4. Admixtures shall not contain more than 1 percent of chlorides calculated as calcium chloride unless specified otherwise in the Specification.
- 5. Admixtures shall be used at the manufacturer's recommended dosage rates.
- 6. The air-entraining admixture characteristics shall produce concrete with satisfactory workability and total air content as prescribed in Table 1002.02.
- 7. a. When using the Lithium Nitrate admixture, the Contractor shall submit to the Engineer:
 - (i) A five pound sample of Portland cement that will be used on the project.
 - (ii) The Manufacturer's method for determining the recommendation for the required dose rate based on the equivalent alkali content.
 - (iii) Water content of the Lithium Nitrate admixture solution.

- b. The Engineer will report the equivalent alkali content to the Contractor. The Contractor shall use the reported equivalent alkali content to determine the required dose rate based on the manufacturer's recommendation.

1007.03 -- Procedures

- 1. The process for adding admixtures to a ready mix truck on the project site involves positioning the load of concrete up to the truck chute, stopping short of discharge.
 - a. The admixture is then poured over the surface of the concrete and mixed for at least 5 minutes.
 - b. No more than 1.3 gallons of water shall be used to rinse the admixture from the fins and top chute. This water must be shown on the proportioning report and shall not exceed the water cement ratio.
 - c. When Lithium Nitrate is used, the portion of the admixture that is water will be shown on the proportioning report and shall not exceed the water cement ratio.
 - d. The Contractor is responsible for the addition of the admixture.
- 2.
 - a. If the air content is less than the minimum specified, addition of air-entraining admixtures is allowed.
 - b. The Contractor shall take measures based on manufacturer's recommendations, that are within compliance of NDR Specifications, to bring the load of concrete into NDR prescribed limits according to Table 1002.02.
 - c. If the air content is then outside the limits in Table 1002.02, the load of concrete shall be rejected.

1007.04 -- Acceptance Requirements

- 1.
 - a. Approved chemical admixtures are shown on the NDR Approved Products List.
 - b. Admixture approval shall be based upon annual certifications and certified test results submitted to the NDR Materials and Research Division.
- 2. The admixture must be essentially identical in concentration, composition, and performance to the admixture tested for certification.
- 3. Admixtures not identified on the NDR Approved Products List may be used under the following conditions:
 - a. A certificate of compliance and certified test results must be submitted to the NDR Materials and Research Division and approval for use must be given by the NDR Materials and Research Division.

**SILICA FUME
(J-15-0307)**

Paragraph 2 of Subsection 1009.03 in the Standard Specifications is void and superseded by the following:

2. Silica fume shall be protected from temperatures in excess of 90°F (32°C).

**LIQUID MEMBRANE-FORMING COMPOUNDS FOR CURING CONCRETE
(J-15-0307)**

Subsection 1012.03 in the Standard Specifications is void and superseded by the following:

1012.03 – Acceptance Requirements

1. All curing compounds to be approved must be from the current calendar year with no carry-over from the previous years.
2. Approved compounds are on the NDR Approved Products List.
3. Products not on the NDR Approved Products List shall be sampled and tested in accordance with requirements of the NDR Materials Sampling Guide.

**BITUMINOUS LIQUID COMPOUNDS FOR CURING CONCRETE
(J-15-0515)**

Section 1013 in the Standard Specifications is void and superseded by the following:

1013.01 – Description

The compound shall consist essentially of an asphaltic base and shall be of a consistency suitable for spraying at temperatures existing at the time of construction operations. It shall form a continuous, uniform film. It shall be free of precipitated matter caused by conditions of storage or temperature. The compounds shall be relatively nontoxic.

1013.02 – Material Characteristics

- a. When tested in accordance with AASHTO T 155, the loss of water shall not be more than 0.11 lb/ft² (0.55 kg/m²) of surface area at 3 days, unless otherwise specified by the Engineer.
- b. The Contractor has the option of using bituminous tack coat. The tack coat shall conform to all requirements of Section 504.
- c. The base material shall conform to Sections 1030, 1031 and 1032.

1013.03 – Acceptance Requirements

Products shall be sampled and tested in accordance with requirements of the NDR Materials Sampling Guide.

JOINT AND CRACK SEALING FILLER (J-15-0813)

Section 1014 in the Standard Specifications is void and superseded by the following:

1014.01 – Description

Joint sealing filler shall be either a cold applied silicone product or an asphalt product (hot pour) conforming to the requirements of this Section. The type of joint filler to be used shall be as specified in the plans or special provisions. If not specified, any of the joint sealing fillers in this Section may be used.

Crack sealing filler shall be a hot pour sealer conforming to the requirements of this Section.

1014.02 -- Material Characteristics

1. NE-3405 and NE-3405LM (hot pour)
 - a. NE-3405 joint and crack sealer shall conform to the requirements of ASTM D6690, Type II. The material shall conform to the requirements of Table 1 with the following exception:
 - (i) The test of Bond, non-immersed, ASTM D5329, 3 specimens through 3 cycles shall be run at 0°F (-18°C), 100% extension.
 - b. NE-3405LM (Low Modulus) joint and crack sealer shall conform to the requirements of ASTM D6690, Type IV. The material shall conform to the requirements of Table 1.
 - c. The test of Bond, non-immersed, ASTM-D5329, will be tested on concrete blocks that will be constructed by the NDR Concrete Laboratory. The concrete blocks will be made of a 47B concrete mixture as prescribed in Section 1002 in the NDR Standard Specifications. The design is amended so that no fly ash is used in the mixture. All other specifications for Portland Cement Concrete apply.
 - d. Sample conditioning, preparation and heating shall be in accordance with ASTM D 5167 with the following exceptions:
 - (i) The following sentence of Section 8.1.2, “Also, if present, remove container liner by cutting it away”, is void and superseded by the following:

“Also, if present, as much of the polyethylene bag as possible, shall be removed by cutting it away. Wholly-meltable type container in contact with the sample section shall be left in place.”

- (ii) The last sentence of Section 8.1.2 “Solid Materials” is void and superseded by the following:

The entire vertical section which has been cut, shall be placed into the pot for melting.

- (iii) The Section of 8.2.2.1 “Solid Materials” is void.

- (iv) The Section of 8.2.3 is void and superseded by the following:

After the solid segment is added to the melter, the material shall be allowed to minimally melt to a uniform viscous state suitable for the installation of the stirrer or paddle. The sample shall then be stirred for one full hour. The oil bath temperature shall be regulated to bring the material to the maximum heating temperature within the one hour of stirring.

- (v) The Section of 8.2.4.1 is void and superseded by the following:

During the one full hour of stirring, check the temperature of the material at maximum 15 minute intervals using a Type K thermocouple with the calibration verified in accordance with Section 6.1.7 to ensure conformance with specified temperature requirements. Stop the mechanical stirrer when measuring temperatures. If material temperatures ever exceed the maximum heating temperature, or ever drop below the minimum application temperature after the maximum heating temperature was reached, discard the sample and re-do the heating. Maintain appropriate records of times and temperatures to verify conformance with specification requirements.

- (vi) The Section of 8.2.4.2 is void.

- e. ASTM D 5329 shall include the following changes:

- (i) Sections 6.4 and 12.4 “Specimen Preparation” shall have the reference of “177 ml (6 oz.)” replaced with “3 oz.”

- (ii) Section 6 “Cone Penetration, Non-Immersed” shall be superseded with the following exceptions:

- 1. Section 6.5 “Procedure” is void and superseded by the following:

Place the specimen in a water bath maintained at 77 +/- 0.2°F (25 +/- 0.1°C) for two hours immediately before testing. Remove the specimen from the bath and dry the surface by shaking gently to remove free water from the surface of the specimen. Using the apparatus described in Section 6.3, make one determination at or near the center of the specimen. Take care to ensure the cone point is placed on a point in the specimen that is representative of the material itself, and is free of dust, water, bubbles, or other foreign material.

2. Section 6.6 "Report" is void and superseded by the following:

Record the value as penetration of the specimen in dmm units.

- (iii) Section 12 "Resilience" shall be superseded with the following exceptions:
 1. Section 12.5 "Procedure", void the sentence "Make determinations at three points equally spaced from each other and less than 13mm (½ inch) from the container rim" and supersede with the sentence "Make one determination at or near the center of the tin."
 2. Section 12.6 "Report" is void.

2. Silicone Joint Sealer (cold applied)

- a. Silicone joint sealers may be either self-leveling or non-sag and shall meet the requirements in Table 1014.01.

Table 1014.01

Silicone Joint Sealer Requirement		
Property	Requirement	Test
As supplied:		
Specific Gravity	1.010-1.515	ASTM D792
Work Time, minimum	10 minutes	
Tack-Free, at 25°C	20-360 minutes	
Cure Time, at 25°C, maximum	14 days	
Full Adhesion, maximum	21 days	
As cured, at 25°C + 1.5		
Elongation, minimum	800%	ASTM D412
Durometer		
Non-Sag, Shore A	10-25	ASTM D2240
Self-Leveling, Shore 00, minimum	40	ASTM D2240
Joint Movement Capacity	+100% to -50%	ASTM C719
Tensile Stress, at 150% Elongation	45 psi	ASTM D412

1014.03 -- Packaging

1. NE-3405 and NE-3405LM
 - a. The joint and crack sealer can be packaged in either cardboard box of wholly-meltable type containers.
 - (i) Cardboard box containers shall be manufactured from double wall kraft board producing a minimum bursting test certification of 350 PSI (241 N/cm²) and using water-resistant adhesives. The use of metal staples or fasteners of any kind will be prohibited for closing the lids of the boxes. Tape or other like material is acceptable.
 - a. The joint and crack sealer shall be in meltable [300°F (149°C)] polyethylene bag(s).

- (ii) Wholly-meltable type containers, and any of their components, shall be fully meltable and integrational with the joint and crack sealer by the time the manufacturer's minimum application temperature is reached.
 - a. The wholly-melted and integrated container must not adversely affect the test specifications of the joint and crack sealer.

2. Silicone Joint Sealer

- a. Each container shall include information regarding manufacturer and product name.

1014.04 -- Acceptance Requirements

1. NE-3405 and NE-3405LM

- a. Acceptance of the manufactured material is based on pre-approval by either on or off-site sampling. Acceptable hot pour sealant lots are listed on the NDR Approved Products List.
 - (i) NDR on-site field sampling shall be in accordance with the NDR Materials Sampling Guide.
 - (ii) Off-site (Proxy) sampling shall be in accordance with ASTM D 6690.
 - 1. Proxy sampling shall be overseen by an outside party approved by the NDR, preferably another DOT Agency. Proxy samples shall include a manufacturer's Certificate of Compliance. Proxy samples shall also include a dated signature of origin by the Representative that is not affiliated with the manufacturer, and can either be on the Certificate of Compliance, or separate letter.
 - 2. For convenience in both sampling and shipping samples, sample containers smaller than a manufacturer's usual production containers are allowed, as long as the sample is 1500 grams min.
 - 3. Samples shall be sent to the NDR Bituminous Laboratory, or alternatively, sent to an NDR-approved independent laboratory for testing which will be at no cost to the Department. If a NDR-approved independent laboratory will be used for testing purposes, the NDR Bituminous Laboratory must be notified so that NDR concrete blocks for Bond testing can be sent to it.

2. Silicone Joint Sealer

- a. Acceptance of applied silicone joint sealers shall be in accordance with the NDR *Materials Sampling Guide*.
- b. Acceptable silicone joint sealer manufacturer products are listed on the NDR Approved Products List.
 - (i) For products that are not listed, approval may be based upon test results from an independent laboratory submitted to the NDR Concrete Materials Section by the manufacturer, and testing by the NDR. Approval must be made prior to product use.

EPOXY COMPOUNDS AND ADHESIVES (J-15-0308)

Section 1018 in the Standard Specifications is void and superseded by the following:

1018.01 – Description

This specification provides requirements for two-component, epoxy-resin bonding systems for use in non-load bearing applications and resin adhesives for application to Portland cement concrete.

1018.02 – Material Characteristics

1. Epoxy-resin bonding systems shall conform to the requirements of ASTM C 881. Approved systems are shown on the NDR Approved Products List.
2. The classification of Epoxy-Resin Bonding Systems is as follows:
 - a. Type I For use in non-load bearing applications for bonding hardened concrete and other material to hardened concrete.
 - Type II For use in non-load bearing applications for bonding freshly mixed concrete to hardened concrete.
 - Type III For use in bonding skid resistant materials to hardened concrete, and as a binder in epoxy mortars or epoxy concretes.
 - b. Grade 1 Low viscosity.
 - Grade 2 Medium viscosity.
 - Grade 3 Non-sagging consistency.
 - c. Class A For use below 40°F (4°C); the lowest allowable temperature to be defined by the manufacturer of the product.
 - Class B For use between 40°F and 60°F (4°C and 15°C).
 - Class C For use above 60°F (15°C); the highest allowable temperature to be defined by the manufacturer of the product.
 - Class D For use between 40°F and 65°F (4°C and 18° C).
 - Class E For use between 60°F and 80°F (15°C and 26°C).
 - Class F For use between 75°F and 90°F (24°C and 32°C).

1018.03 – Procedures

1. The compounds shall be of the type and grade specified in the plans or as directed by the Engineer.

2. The class of the compounds shall be selected for use according to climatic conditions at the time of application.
3. All bonding surfaces shall be clean and free of all oil, dirt, grease, or any other materials which would prevent bonding.
4. Mixing and application shall be in strict accordance with the manufacturer's instructions.

1018.04 – Acceptance Requirements

1. Epoxy-resin bonding systems and resin adhesives approved for use are shown on the NDR Approved Products List.
2. Epoxy-resin bonding systems that are not on the NDR Approved Products List may be accepted based on a manufacturer's certificate of compliance.

**DEFORMED METAL CENTER JOINT AND METAL KEYWAY
(J-15-0307)**

Paragraph 1 a. of Subsection 1027.01 in the Standard Specifications is void and superseded by the following:

a. Metal Center Joint:

Metal center joint sections shall be manufactured from sheets no less than 18 gauge [0.05 inch (1.3 mm)] thick and shall be of the size and trapezoidal shape shown in the plans. The sections shall be punched along the centerline of the narrow face of the trapezoid to admit the tie bars required by the plans and also at intervals of not greater than 2 feet (600 mm) to receive pins that are driven vertically into the subgrade to support the metal center joint.

**AGGREGATES
(J-15-0316)**

Subsection 1033.01 is amended to include the following paragraphs and Subsection 1033.02, Paragraphs 1., 2. and 3. of the Standard Specifications are void and superseded by the following:

1033.01 – Description

This combined aggregate gradation using Class R aggregate is to optimize aggregate blends utilizing more locally available materials.

Achieving a uniform gradation for Class R may require the use of two or more different aggregates. It is the responsibility of the contractor to consider additional material characteristics; such as, but not limited to particle shape, cubicity, angularity, etc., when designing a mix.

1033.02 -- Material Characteristics

1. Sampling and Testing Procedures:

All materials shall be sampled and tested in accordance with Table 1033.01. All material source locations and quarries must be approved by the Department for prior to use.

Table 1033.01

Sampling and Testing Procedures	
Procedure	Method
Sampling	NDR T 2
Sieve Analysis	NDR T 27
Clay Lumps, Shale, and Soft Particles	NDR T 504
Abrasion	AASHTO T 96
Freeze and Thaw Soundness	NDR T 103
Specific Gravity and Absorption (course aggregate)	AASHTO T 85
Specific Gravity and Absorption (fine aggregate)	AASHTO T 84
Total Evaporable Moisture Content of Aggregates by Drying	AASHTO T 255
Plastic Fines in Graded Aggregates and Soils by Use of the Sand Equivalent Test	AASHTO T 176
Sodium Sulfate Soundness	AASHTO T 104
Calcium Carbonate	NDR C 25
Organic Impurities	AASHTO T 21
Mortar-Making Properties	AASHTO T 71
Reducing Field Samples of Aggregate to Testing Size	AASHTO T 248
Lightweight Pieces in Aggregates	NDR T 113

2. General Aggregate Properties:

- a. Aggregates shall be free from injurious quantities of dust, soft or flaky particles, loams, alkali, organic matter, paper, wood or other deleterious matter as determined by the Engineer.
- b. Dolomite as herein defined is a magnesium limestone containing calcium carbonate and magnesium carbonate in approximately a 4 to 3 ratio.
- c. The calcium carbonate content of limestone shall be at least 80 percent (computed as CaCO₃ from the value determined for CaO).
- d. Fine Sand shall have at least 95 percent of its particles pass the No. 10 (2.0 mm) sieve and no more than 25 percent pass the No. 200 (75 µm) sieve. This definition applies to sodium sulfate soundness test.
- e. Once an aggregate's soundness and abrasion quality has been determined, additional quality testing for soundness and abrasion loss will be at the Engineer's discretion.
- f. All aggregates or combined aggregates shall not exceed 3.5 percent with any combinations of clay lumps, shale and soft particles (all percent by weight values), plus the lightweight pieces (a percent by volume value).

- g. All aggregates or combine aggregates that have been washed or coming from a wet pit shall be stockpiled for a minimum of 48 hours before being introduced into concrete.

3. Portland Cement Concrete Aggregates:

a. Fine Aggregate:

- (1) Aggregate shall be washed and composed of clean, hard, durable and uncoated particles.
- (2) Aggregates produced from wet pits by pumping must be adequately washed by means approved by the Department.
- (3) Aggregates from dry pits shall be adequately washed by means approved by the Department and have a Sand Equivalent value not less than 90 in accordance with AASTHO T 176.
 - (i) If the Sand Equivalent is less than 90, the Engineer may elect to stop aggregate production until such a time ASTM C 109 has been completed. The aggregate, when subjected to the test for mortar-making properties, shall produce a mortar having a compressive strength at the age of 7 days equal to or greater than that developed by mortar of the same proportions and consistency made of the same cement and aggregate after the aggregate has been washed to a sand equivalent greater than 90. Materials failing to produce equal or greater strength shall be unacceptable.
- (4) Aggregate for concrete shall have a soundness loss of not more than 10% by weight at the end of 5 cycles using Sodium Sulfate Soundness test AASHTO T 104.
- (5) The weight of the aggregate shall not contain more than 0.5% clay lumps.
- (6) Aggregate subjected to the colorimetric test for organic impurities which produces a color darker than the standard shall be further tested for its mortar-making properties in accordance with AASHTO T 71. The Engineer may elect to stop aggregate production until such a time AASHTO T 71 testing has been completed.
 - (i) Aggregate, when subjected to the test for mortar-making properties, shall produce a mortar having a compressive strength at the age of 7 days equal to or greater than that developed by mortar of the same proportions and consistency made of the same cement and aggregate after the aggregate has been treated in a 3% solution of sodium hydroxide. Materials failing to produce equal or greater strength shall be unacceptable, except when determined to be acceptable under the provisions of Subsection 105.03.

- (7) Aggregate shall meet the requirement in Tables 1033.02A, 1033.02B and 1033.03C.

Table 1033.02A

		Percentage	Percent Passing									
			1½"	1"	¾"	½"	3/8"	No.4	No.10	No.20	No.30	No.200
AGGREGATE SPECIFICATION RANGE	Class A	Max	--	--	--	--	100	100	90	--	40	3
		Min	--	--	--	--	100	92	64	--	10	0
	Class B	Max	--	100	--	--	--	97	70	--	40	3
		Min	--	100	--	--	--	77	50	--	16	0
	Class C	Max	--	100	--	--	--	88	50	--	20	3
		Min	--	100	--	--	--	44	24	--	4	0

Table 1033.02B

Aggregate Classes and Uses	
Aggregate Class	Concrete Description
A	Overlay Concrete SF
B	47BD, 47B-HE, 47B-OL, PR 1 and PR 3
C	BX

b. Coarse Aggregate:

- (1) Aggregate shall consist of Limestone, Quartzite, Dolomite, Gravel and Granite composed of clean, hard, durable, and uncoated particles.
- (2) The percent of clay lumps, shale, or soft particles shall not exceed the following amounts:

Clay Lumps	0.5%
Shale	1.0%
Soft Particles	3.5%
Lightweight Pieces	3.5%

- (3) Any combination of clay lumps, shale and soft particles (all percent by weight values), plus the lightweight pieces (a percent by volume value) shall not exceed 3.5%.
- (4) Aggregate for concrete shall be free of coatings that will inhibit bond and free of injurious quantities of loam, alkali, organic matter, thin or laminated pieces, chert, or other deleterious substances as determined by the Engineer.
- (5) Aggregate for concrete shall not have a soundness loss greater than 8.0% by weight at the completion of 16 cycles of alternate freezing and thawing.
- (6) Aggregates for concrete shall have a Los Angeles Abrasion loss percentage of not more than 40.
- (7) All fractions passing the No.4 sieve shall meet quality requirement of soundness loss of not more than 10% by weight at the end of 5 cycles using sodium sulfate solution.

- (8) The coarse aggregate shall be tested according to ASTM C 1260.
 - (a) The mortar bars for the ASTM C 1260 shall not exceed 0.10% expansion at 28 days.
 - (i) If the proposed coarse aggregate exceeds 0.10% expansion at 28 days, the aggregate proportions used on the project shall be tested in accordance to ASTM C 1567.
 - a. The ASTM C 1567 mortar bars shall be composed of Interground/blended cement being used on the project.
 - b. If the expansion is greater than 0.10%, the coarse aggregate shall not be used.
- (9) Aggregate shall meet the requirements in Tables 1033.03A, B, and C.

Table 1033.03A

AGGREGATE SPECIFICATION RANGE	Class	Percent	Percent Passing									
			1 1/2"	1"	3/4"	1/2"	3/8"	No.4	No.10	No.20	No.30	No.200
	Class E	Max	100	100	90	--	45	12	--	*4	--	3
		Min		92	66		15	0		0		0
	Class F	Max	--	--	100	100	90	30	8	--	--	3
		Min				96	40	4	0			0

*If the No. 200 sieve is less than 1.5% passing the No.20 sieve could be increased to maximum of 6% passing.

Table 1033.03B

Aggregate Classes and Uses	
Aggregate Class	Concrete Description
E	47BD, 47B-HE, PR 1 and PR 3
F	47B-OL, Overlay Concrete SF

c. Combined Aggregates:

- (1) The Contractor shall design and meet the specification requirements. It is the Contractor's responsibility to provide desirable mix properties; such as, but not limited to, workability, resistance to segregation, stable air void system, good finishing properties and good consolidation properties.
- (2) The combined blended aggregate shall meet the requirement in Table 1033.03C and 1033.03D.

Table 1033.03C

*Class R - Combined Aggregate Gradation Limits (Percent Passing)								
Sieve Size	1 1/2 inch	1 inch	3/4 inch	No.4	No.10	No.30	No. 50	No.200
Max	100	100	98.0	70.0	50.0	30.0	12.0	3.0
Min	-	92.0	85.0	45.0	31.0	8.0	2.0	0

* Refer to Subsection 1002.04, Paragraph 1.b.(8) for the traditional 47B Mix Design

Table 1033.03D

Aggregate Classes and Uses	
Aggregate Class	Concrete Description
R	47B

d. Aggregate Production and Testing:

- (1) Any change greater than 3% in the original verified constituent percentage of the combined aggregates gradation will be considered non-compliant. Any change of the combined gradation targets must remain within the Combined Aggregate Gradation Limits in Table 1033.03C. The Contractor shall resubmit a new mix design if the material is deemed non-compliant in accordance with Subsection 1002.04, Paragraph 1.
- (2) The blended gradation tolerance ranges from the approved mix design are established in Table 1033.03E.
 - (i) The Contractor shall assume the responsibility to cease operations when the specifications are not met. Production shall not be started again without the approval of the Engineer.

Table 1033.03E Blended Aggregate Production Tolerances

Sieve Size	Tolerances
No. 4 or greater	+ 5%
No. 10 to No. 30	+ 4%
No. 50	+ 3%
Minus No. 200	+ 1%

- (3) Coarse aggregate from a dry pit shall be uniformly saturated with water before it is used. The wetting shall begin 24 hours before concrete mixing to allow complete saturation.

**DOWEL BARS
(J-15-0812)**

Paragraph 1.c. of Subsection 1022.01 in the Standard Specifications is void and superseded by the following:

- 1. c. Both Type A and Type B coated dowel bars shall be coated with a bond breaker shown on the NDR Approved Products List, dipped in asphalt or paraffin, or greased in accordance with the specified requirements as shown in the Standard Plans.

**EPOXY COATED REINFORCING STEEL
(J-15-0509)**

Paragraph 5. of Subsection 1021.03 in the Standard Specifications is void and superseded by the following:

5. In order to protect the coated reinforcement from damage, the Contractor shall use padded or nonmetallic slings and padded straps. Bundled bars shall be handled in a manner which will prevent excessive sagging of bars which will damage the coating. If circumstances require storing coated steel reinforcing bars outdoors for more than two months, protective storage measures shall be implemented to protect the material from sunlight, salt spray and weather exposure. Coated steel reinforcing bars, whether individual bars or bundles of bars, or both, shall be covered with opaque polyethylene sheeting or other suitable opaque protective material. For stacked bundles, the protective covering shall be draped around the perimeter of the stack. The covering shall be secured adequately, and allow for air circulation around the bars to minimize condensation under the covering. Coated steel reinforcing bars, whether individual bars or bundles of bars, or both, shall be stored off the ground on protective cribbing. The bundled bars shall not be dropped or dragged. If, in the opinion of the Engineer, the coated bars have been extensively damaged, the material will be rejected. The Contractor may propose, for the approval of the Engineer, alternate precautionary measures.

**PROPOSAL GUARANTY
(A-40-0307)**

As an evidence of good faith in submitting a bid for this work, the bidder shall indicate the type of bid bond applied to this project in accordance with the Proposal Guaranty Bid Bond Section of these Special Provisions.

* * * * *

300INFMAR16

INDEX

ACCEPTANCE TESTING OF SOILS BY USE OF THE LIGHT WEIGHT DEFLECTOMETER (LWD) SCOPE 43

ADJUST INLET TO GRADE 55

ADJUST PULL BOX TO GRADE 54

ADJUST VALVE BOX TO GRADE 54

AGGREGATES 82

BITUMINOUS LIQUID COMPOUNDS FOR CURING CONCRETE 76

BORROW, WASTE, STOCKPILE, AND PLANT SITE APPROVAL 22

BUY AMERICA..... 21

CALCIUM CHLORIDE..... 73

COLORED AND IMPRINTED CONCRETE SIDEWALKS..... 54

CONCRETE PAVEMENT 51

CONCRETE PAVEMENT CORING 49

CONCRETE SURFACE MILLING..... 49

CONSTRUCTION DETAILS..... 32

CONSTRUCTION METHODS 33

CONSTRUCTION STORMWATER MANAGEMENT CONTROL 32

CONTRACT TIME ALLOWANCE 19

CURB WALL

 (Height of 9 inches or less) 55

 (Taller than 9 inches) 55

DEFORMED METAL CENTER JOINT AND METAL KEYWAY..... 82

DOWEL BARS 87

EARTHWORK 46

ELECTRONIC SHOP DRAWINGS 27

ENVIRONMENTAL COMMITMENT 13

ENVIRONMENTAL COMMITMENT DOCUMENT 35

ENVIRONMENTAL COMMITMENT ENFORCEMENT 38

EPOXY COATED REINFORCING STEEL..... 88

EPOXY COMPOUNDS AND ADHESIVES 81

GENERAL CLEARING AND GRUBBING 46

GENERAL CONDITIONS..... 6

HYDROMULCHING..... 58

INLET PROTECTION 56

JOINT AND CRACK SEALING FILLER 77

LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC..... 17

LIABILITY INSURANCE 28

LIMITATION OF OPERATIONS..... 33

LIQUID MEMBRANE-FORMING COMPOUNDS FOR CURING CONCRETE..... 76

PARTIAL PAYMENT	20
PORTLAND AND INTERGROUND/BLENDED CEMENT	69
PORTLAND CEMENT CONCRETE	60
PORTLAND CEMENT CONCRETE PAVEMENTS	
GENERAL REQUIREMENTS	50
PROPOSAL GUARANTY	88
PROPOSAL GUARANTY BID BOND	16
REMOVE AND RELOCATE SIGN AND POST	48
REMOVE AND RESET SIGN AND POST	48
REQUIRED SUBCONTRACTOR/SUPPLIER QUOTATIONS LIST	16
SAWING PAVEMENT	46
SECTION 1007 -- CHEMICAL ADMIXTURES	73
SEEDING	56
SILICA FUME	76
SPECIAL PROSECUTION AND PROGRESS	
(Access to Adjacent Properties During Construction)	12
(ADA Accessibility)	11
(Federal Immigration Verification System)	18
(Form Work for Ramps)	11
(General Requirements)	7
(Migratory Birds)	14
(Pedestrian Push Button at Signals)	11
(Subletting or Assigning of Contract)	23
STATUS OF RIGHT OF WAY	7
STATUS OF UTILITIES	6
STORM WATER DISCHARGES	15
STORM WATER POLLUTION PREVENTION PLAN (SWPPP)	36
SUBGRADE PREPARATION	46
TEMPORARY TRAFFIC CONTROL DEVICES	
(Type II Barricades, Reflectorized Drums, 42" (1070 mm) Reflective Cones, and Vertical Panels)	47
TEMPORARY WATER POLLUTION CONTROL	32
TYPE B HIGH INTENSITY WARNING LIGHTS	46
VALUE ENGINEERING PROPOSALS (VEP)	17
WATER FOR CONCRETE	72
WORK ZONE TRAFFIC CONTROL SIGNS	48
WORKER VISIBILITY	17

CONTRACT ID: 0922

PROJECT(S): MISC-STWD(1076)

CALL ORDER NO.: 300

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 1 GROUP 3 CONCRETE PAVEMENT

0001	0001.08	BARRICADE, TYPE II	10139.000 BDAY	0.50000		5,069.50
0002	0001.75	TEMPORARY SIGN DAY	325.000 EACH	.		.
0003	0001.90	SIGN DAY	2200.000 EACH	.		.
0004	0002.97	FLASHING ARROW PANEL	150.000 DAY	.		.
0005	0003.10	FLAGGING	210.000 DAY	.		.
0006	0030.30	MOBILIZATION	LUMP	LUMP		.
0007	1101.00	REMOVE PAVEMENT	451.000 SY	.		.
0008	1101.25	SAWING PAVEMENT	2310.000 LF	.		.
0009	1106.00	REMOVE DRIVEWAY	79.000 SY	.		.
0010	1107.00	REMOVE WALK	918.000 SY	.		.
0011	1108.00	REMOVE COMBINATION CURB AND GUTTER	12.000 LF	.		.
0012	1137.51	REMOVE AND RESET SIGN	5.000 EACH	.		.
0013	3008.05	TIE BARS	594.000 EACH	.		.
0014	3014.11	COMBINATION CONCRETE CLASS 47B-3500 CURB AND GUTTER	12.000 LF	.		.
0015	3016.22	CONCRETE CLASS 47B-3500 SIDEWALKS	1115.000 SY	.		.

CONTRACT ID: 0922

PROJECT(S): MISC-STWD(1076)

CALL ORDER NO.: 300

LINE NO	ITEM DESCRIPTION		APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
				DOLLARS	CTS	DOLLARS	CTS
0016	3016.27	COLORED IMPRINTED CONCRETE 47B-3000 SIDEWALKS	33.000 SY	.		.	
0017	3016.39	DETECTABLE WARNING PANEL	832.000 SF	.		.	
0018	3017.28	CONCRETE CLASS 47B-3500 MEDIAN SURFACING	19.000 SY	.		.	
0019	3020.23	CONCRETE CLASS 47B-3500 DRIVEWAY 8"	71.000 SY	.		.	
0020	3075.42	9" CONCRETE PAVEMENT, CLASS 47B-3500	451.000 SY	.		.	
0021	4004.00	CAST IRON GRATE	175.000 LB	.		.	
0022	4014.71	ADJUST INLET TO GRADE	1.000 EACH	.		.	
0023	4015.00	ADJUST MANHOLE TO GRADE	5.000 EACH	.		.	
0024	4093.80	WALL MATERIALS	234.000 SF	.		.	
0025	4095.15	COMPACTED EARTH LEVELING PAD	117.000 LF	.		.	
0026	4900.24	AREA INLET SEDIMENT FILTER	1.000 EACH	.		.	
0027	4900.25	CURB INLET SEDIMENT FILTER	19.000 EACH	.		.	
0028	8024.50	SELECT GRANULAR BACKFILL FOR RETAINED EARTH STRUCTURE	14.000 CY	.		.	
0029	9034.00	PREPARATION OF INTERSECTIONS AND DRIVEWAYS	71.000 SY	.		.	
0030	9110.01	RENTAL OF LOADER, FULLY OPERATED	10.000 HOUR	.		.	
0031	9110.03	RENTAL OF DUMP TRUCK, FULLY OPERATED	10.000 HOUR	.		.	

CONTRACT ID: 0922

PROJECT(S): MISC-STWD(1076)

CALL ORDER NO.: 300

LINE NO	ITEM DESCRIPTION		APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
				DOLLARS	CTS	DOLLARS	CTS
0032	9110.07	RENTAL OF SKID LOADER, FULLY OPERATED	10.000 HOUR	.		.	
0033	9111.00	WATER	2.000 MGAL	.		.	
0034	9173.20	SUBGRADE PREPARATION	453.000 SY	.		.	
0035	9186.00	CONCRETE SURFACE MILLING	4.000 SY	.		.	
0036	A449.00	ADJUST PULL BOX TO GRADE	1.000 EACH	.		.	
0037	L001.03	SEEDING, TYPE C	1.000 ACRE	.		.	
0038	L032.80	HYDROMULCH	1.500 TON	.		.	
0039	L860.50	ENVIRONMENTAL COMMITMENTS - CONTRACTOR COMPLIANCE	LUMP	LUMP		.	
0040	W600.03	ADJUST VALVE BOX TO GRADE	2.000 EACH	.		.	
0041	W750.23	REMOVE AND RELOCATE SIGN & POST	1.000 EACH	.		.	
SECTION 1 TOTAL						.	
TOTAL BID						.	