

INFORMATIONAL PROPOSAL

(For information only, not to be used for bidding)

NEBRASKA DEPARTMENT OF ROADS
LETTING DATE: April 13, 2017

CALL ORDER: 320
CONTROL NO. SEQ. NO.: M3275C 000

CONTRACT ID: M3275C
PROJECT NO.: M3275C

TENTATIVE START DATE: 09/25/2017

CONTRACT TIME: 20 Working Days

LOCATION: US-275, MEADOW GROVE DECK REPAIR

IN COUNTY: MADISON

BIDDER

GROUP 6 BRIDGE AT STA.325+41.00

NOTES

THE TOTAL AMOUNT OR WORK WHICH WILL BE ACCEPTED IN
THIS LETTING IS LIMITED TO \$ _____

THE NUMBER OF GROUP _____ CONTRACTS WHICH WILL BE
ACCEPTED IN THIS LETTING IS LIMITED TO _____.



NOTICE TO ALL BIDDERS

To report bid rigging activities, call: 1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free “hotline” Monday through Friday, 8:00 a.m. to 5:00 p.m. eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the “hotline” to report such activities.

The “hotline” is part of the DOT’s continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

LETTING QUESTIONS

Prior to the letting, any questions pertaining to the Special Provisions or the Plans for this project should be submitted to NDOR in a written format through the Bid Express (BidX) website at <https://www.bidx.com/ne/lettings>. Likewise, NDOR will post answers exclusively to the BidX website. All official answers will be identified as “Authorized by NDOR.” **Questions will not be answered verbally.**

STATE OF NEBRASKA
DEPARTMENT OF ROADS

Required Provisions Supplemental to the

Standard Specifications for Highway Construction

I. Application

These contract provisions shall apply to all work performed on the contract by the contractor with his own organization and with the assistance of workmen under his immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

The contractor shall insert in each of his subcontracts all of the stipulations contained in the Special Provisions and these Required Provisions.

A breach of any of the stipulations contained in these Required Provisions may be grounds for termination of the contract.

II. Equal Opportunity

1. **Selection of Labor**

During the performance of this contract, the contractor shall not discriminate against labor from any other state.

2. **Nebraska Fair Employment Practices Act**

The contractor shall not discriminate against any employee or applicant for employment, to be employed in the performance of this contract with respect to his hire, tenure, terms, conditions, or privileges of employment, because of his race, color, religion, sex or national origin. The contractor agrees to post in a conspicuous place or places a notice to be provided by the State Highway Department which sets forth excerpts of the Act.

3. **Nebraska Equal Pay Act**

The contractor shall not discriminate on the basis of sex by paying wages to employees of one sex at a lesser rate than the rate paid to employees of the opposite sex for comparable work on jobs which have comparable requirements. An abstract of the Act is included on the notice which is provided by the State Highway Department.

April 4, 1995

III. Employment of Labor

1. General

No person under the age of sixteen (16) years, and no one whose age or physical condition is such as to make his employment dangerous to his health or safety, or to the health and safety of others shall be employed on any project. This paragraph shall not be construed to deny the employment of older people or physically handicapped persons, otherwise employable, where such persons may be safely assigned to work which they can ably perform.

No person currently serving sentence to a penal or correction institution shall be employed on any project.

Except as specifically provided under this section, workers who are qualified by training or experience to be assigned to projects of this character shall not be discriminated against on any grounds whatsoever.

2. Payrolls

Payrolls and basic records relating thereto will be maintained during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working on the site of the work.

The contractor's and subcontractor's payroll records shall be available for inspection by authorized representatives of the State Highway Department and authorized representatives of Federal Agencies.

The wages of labor shall be paid in legal tender of the United States, except that this condition will be considered satisfied if payment is made by a negotiable check, on a solvent bank, which may be cashed readily by the employee in the local community for the full amount, without discount or collection charges of any kind. Where checks are used for payment the contractor shall make all necessary arrangements for them to be cashed and shall give information regarding such arrangements.

No fee of any kind shall be asked or accepted by the contractor or any of his agents from any person as a condition of employment on the project.

No laborers shall be charged for any tools used in performing their respective duties except for reasonably avoidable loss or damage thereto.

Every employee on the work covered by this contract shall be permitted to lodge, board and trade where and with whom he elects and neither the contractor nor his agents, nor his employees shall directly or indirectly require as a condition of employment that an employee shall lodge, board or trade at a particular place or with a particular person.

No charge shall be made for any transportation furnished by the contractor or his agents to any person employed on the work.

April 4, 1995

No individual shall be employed as a laborer on this contract except on a wage basis, but this shall not be construed to prohibit the rental of teams, trucks or other equipment from individuals. No such rental agreement, or any charges for feed, gasoline, supplies, or repairs on account of such agreement, shall cause any deduction from the wages accruing to any employee except as authorized by the regulations hereinbefore cited.

IV. Safety and Accident Prevention

In the performance of this contract, the contractor shall comply with all applicable Federal, State and local laws governing safety, health and sanitation. The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions, on his own responsibility or as the contracting officer may determine, reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.

V. Subletting or Assigning the Contract

The contractor shall perform with his own organization contract work amounting to not less than 30 percent of the total contract amount except that any items designated in the contract as "Specialty Items" may be performed by subcontract and the amount of any such "Specialty Items" so performed may be deducted from the total contract amount before computing the amount of work required to be performed by the contractor with his own organization.

Any items that have been selected as "Specialty Items" for the contract are listed as such in the Special Provisions found elsewhere in the contract.

No portion of the contract shall be sublet, assigned, or otherwise disposed of except with the written consent of the contracting officer or his authorized representative. Requests for permission to sublet assign or otherwise dispose of any portion of the contract shall be in writing and accompanied by a showing that the organization which will perform the work is particularly experienced and equipped for such work. The contractor shall give assurance that the minimum wage for labor as stated in his proposal shall apply to labor performed on all work sublet, assigned or otherwise disposed of in any way. Consent to sublet, assign or otherwise dispose of any portion of the contract shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract.

April 4, 1995

**SPECIAL PROVISIONS
FOR
STATE
PROJECT NO. M3275C**

GENERAL CONDITIONS

Bids for the work contemplated in this proposal form will be received at the office of the Nebraska Department of Roads in Room 104 of the Central Office Building at 1500 Highway 2 at Lincoln, Nebraska, on April 13, 2017, until 1:30 P.M.

- a. Bids submitted by mail should be addressed to the Nebraska Department of Roads, c/o Contract Lettings Section, P.O. Box 94759, Lincoln, NE 68509-4759.
- b. Bids submitted electronically over the internet, shall be submitted using www.bidx.com.

The 2007 Edition of the Standard Specifications for Highway Construction, including all amendments and additions thereto effective at the date of the contract, are made a part of these Special Provisions, through reference.

The Required Provisions dated April 4, 1995, are attached to and are a part of this proposal form.

The attention of bidders is directed to the Required Provisions covering subletting or assigning the contract.

The proposal contains a statement that the contractor is complying with, and will continue to comply with, fair labor standards in the pursuit of his business and in the execution of the work contemplated in this proposal.

Fair labor standards shall be construed to mean such a scale of wages and conditions of employment as are paid and maintained by at least fifty percent of the contractors in the same business or field of endeavor as the contractor filing this proposal.

TRAINING SPECIAL PROVISIONS

This On-the-Job Training (OJT) Program was created by the Federal Highway Administration (FHWA) and the Nebraska Department of Roads (NDOR) to fulfill the Training Special Provisions requirements of federal-aid construction contracts (23 CFR 230, Appendix B to Subpart A). The purpose of the provision is to address the under-representation of minority and female workers in the construction trades through the assignment of OJT training goals. Therefore, the training and upgrading of minorities and women toward journeyman status is a primary objective of this Training Special Provision.

Accordingly, the Contractor shall make every effort to enroll minority and women trainees (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority and women trainees) to the extent that such persons are available within a reasonable area of recruitment.

All Contractors will be responsible for demonstrating the steps that they have taken to recruit minority and women trainees prior to a determination as to whether the Contractor is in compliance with this Training Special Provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a

minority group or not. The Contractor shall provide on-the-job training aimed at developing full journey-level status in the type of trade or job classification involved. The number of training hours under this Training Special Provision will be assigned to each Contractor as set forth below.

1. Under the NDOR Contractor-Specific On-the-Job Training (OJT) Program, OJT hours will be assigned to Contractors and will not be contract or project specific, except as noted in paragraph "a." below.
 - a. Contractors who **have not** received an OJT assignment and are awarded a federally funded project let by NDOR will be required to fulfill the number of OJT hours as identified in each contract. The number of training hours to be provided under this contract shall be: 0 hours.

A Contractor who has received an OJT assignment will be allowed to provide training on any NDOR-let project on which the Contractor is working as either a Prime Contractor or a subcontractor. A Contractor will have the flexibility to transfer trainees from one project to another after providing notification of the transfer to NDOR.
 - b. If this project does not have a contract-specific training requirement, or if the number of training hours is set at zero (0), NDOR will add a training pay item with a nominal 100-hour quantity, that may overrun or underrun, which will be utilized only if the Contractor elects to provide training on this contract.
2. In January each year, NDOR will allocate OJT assignments to Contractors based on the total average dollar amount of all work performed by a Contractor on NDOR-let projects during the previous three (3) calendar years. The total dollar amount will consist of:
 - a. The total dollar amount of the Contractor's prime contracts let by NDOR (both federal and state funded) minus the total dollar amount of the work subcontracted out to others, and
 - b. The total dollar amount of the subcontract work the Contractor performed for others on NDOR-let projects.

The Contractor’s average dollar amount for the previous three calendar years will be calculated, and training hours will then be assigned as follows:

<u>Three Year Average</u>	<u>Training Assignments</u>
Under \$2,500,000	0 hours
\$2,500,000 to 5,000,000	1,000 hours
Over \$5,000,000 to 7,500,000	1,500 hours
Over \$7,500,000 to 10,000,000	2,000 hours
Over \$10,000,000 to 15,000,000	3,000 hours
Over \$15,000,000 to 20,000,000	4,000 hours
Over \$20,000,000 to 25,000,000	5,000 hours
Over \$25,000,000 to 30,000,000	6,000 hours
Over \$30,000,000 to 40,000,000	8,000 hours
Over \$40,000,000 to 50,000,000	10,000 hours
Over \$50,000,000 to 60,000,000	12,000 hours
Over \$60,000,000	15,000 hours

Example: Contractor A, who averaged \$28.66 million, would be assigned 6,000 hours of OJT. Contractor B, who averaged \$10.33 million, would be assigned 3,000 hours of OJT. Contractor C, who averaged \$2.26 million, would not be assigned any OJT hours.

	2011	2012	2013	3 Year Average	2014 OJT Assignment
Contractor A	24.3	33.4	28.3	28.66	6,000 hours
Contractor B	9.3	11.9	9.8	10.33	3,000 hours
Contractor C	2.3	1.4	3.1	2.26	0 hours

3. The OJT hours assigned to a Contractor in January are to be completed during that calendar year (e.g., OJT hours assigned in January of 2014 are to be completed during the period of January 1, 2014 thru December 31, 2014).
 - a. If a Contractor exceeds the number of OJT hours assigned for a calendar year, the Contractor may request to bank up to 30 percent of the excess hours. Banked hours may then be credited toward the Contractor’s OJT assignment for the next calendar year.
4. A Contractor who has not received an annual OJT assignment and is required to provide OJT on a contract-specific basis cannot receive credit for any OJT hours provided by any other Contractor working on the project who has received a Contractor-specific OJT assignment.
5. Completion of the annual OJT assignment is the Contractor’s responsibility. The Contractor is not allowed to assign any of the OJT hours to any other Contractor. The Contractor must make a Good Faith Effort to enroll an adequate number of trainees and provide the trainees a sufficient number of hours training to achieve the Contractor’s annual OJT assignment.
6. While trainees may be assigned to NDOR-let federally or state funded projects, the Contractor should attempt to schedule and assign trainees so that at least 50 percent of a trainee’s hours are earned on federally funded projects - unless otherwise approved in advance by NDOR.

7. The Contractor must use an OJT program approved by NDOR and/or the FHWA. An OJT program shall be approved if it is reasonably calculated to meet the equal employment opportunity obligations of the Contractor and qualify the average trainee for journey-level status in the job classification concerned by the end of the training period. An approved OJT program must specify the number of hours required for a trainee to achieve journey-level status in each job classification. Furthermore, apprenticeship programs registered with the U.S. Department of Labor, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau and training programs approved but not necessarily sponsored by the U.S. Department of Labor, Manpower Administration, Bureau of Apprenticeship and Training, shall also be considered acceptable provided they are being administered in a manner consistent with the equal employment obligations of federal-aid highway construction contracts.
8. The Contractor shall furnish each trainee a copy of the OJT Program he/she will follow in providing the training. The Contractor shall also provide each trainee with a certification showing the type and length of training satisfactorily completed.
9. The Contractor's Equal Employment Opportunity (EEO) Officer shall be responsible for administering the Contractor's OJT and monitoring the trainees' progress. The EEO Officer shall serve as the point of contact for NDOR regarding OJT information, documentation, and conflict resolution. If necessary, the EEO Officer may designate another individual to assist with the OJT monitoring responsibilities. NDOR must be provided the name and contact information for any such designee.
10. At least seven (7) days prior to commencing training, the Contractor must submit a "Request for Trainee Approval" form to NDOR for each individual to be enrolled as a trainee and a tentative list of the projects to which the trainee will be assigned. Requests for Trainee Approval may be submitted by mail, fax, or email.
11. If the Contractor submits a "Request for Trainee Approval" form to NDOR for an individual who is not a minority or female, or cannot replace departing trainees with minorities or females, the Contractor must also produce sufficient Good Faith Efforts documentation of the type set forth below. NDOR may reject non-minority male trainees for entry into the program if it determines that a Contractor failed to make sufficient Good Faith Efforts to hire minorities or female trainees and/or the Contractor failed to document or submit evidence of its Good Faith Efforts to do so.
12. Any training hours provided to a trainee prior to the Contractor receiving approval from NDOR will not be credited toward the Contractor's annual OJT assignment.
13. When an individual is first enrolled as a trainee, the individual will be approved for the number of hours of OJT required to achieve journey-level status in the classification for which the individual is to receive training. (A Contractor will not be penalized if a trainee does not achieve the full number of hours for which the trainee is approved.)
14. If the Contractor is unable to provide a trainee the full number of training hours required to achieve journey-level status on one project, the trainee should be transferred to other NDOR-let projects on which the Contractor is working.
15. At least one (1) day before all such transfers of trainees are made, the Contractor must provide NDOR in writing the name of the trainee and current project, the project to which

the trainee will be transferred, and when the transfer is to take place. Notifications of trainee transfers may be submitted by mail, fax, or email.

16. Any training hours provided to a transferred trainee prior to the Contractor having notified NDOR of the transfer will not be credited toward the Contractor's annual OJT assignment.
17. No individual may be employed as a trainee in any classification in which they have successfully completed training leading to journey-level status or in which they have been employed at journey-level. No individual may be employed as a trainee in any classification with a lower skill level than any classification in which they have successfully completed training leading to journey-level status or in which they have been employed at journey-level (e.g., an individual who has achieved journey-level status as an equipment operator may not be trained as a laborer). The Contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used, the Contractor's records should document the findings in each case.

An individual may be trained in multiple classifications that require relatively equal skill levels but different skill sets (e.g., an individual who has received training as a milling machine operator may also receive training as a roller operator, or a scraper operator, etc.). Preferably, an individual should have achieved journey-level status in a classification before beginning training in another classification.

The Contractor must request and receive approval from NDOR for an individual to receive training in a classification other than the classification for which the individual was originally approved. Any training hours provided prior to receiving approval from NDOR will not be credited toward the Contractor's annual OJT assignment.

18. Training shall be provided in construction crafts rather than clerk-typist or secretarial-type positions. Training is permissible in positions that are not assigned to a specific project such as office engineers, estimators, timekeepers, shop mechanics, etc., if the selected OJT program includes these classifications. Training in such positions will not be eligible for reimbursement, but will be eligible to be credited toward the Contractor's annual OJT assignment.
19. Some off-site training is permissible as long as the training is an integral part of an approved OJT program and does not comprise a significant part of the overall training (e.g., 16 hours training per trainee per year in areas such as jobsite safety or accident response would be permissible). A copy of a training certificate, agenda, or curriculum must be provided to verify off-site training.
20. The Contractor will be reimbursed \$2.00 per each hour of training provided in accordance with an approved OJT program and the NDOR Training Special Provisions.
21. Contractors shall be allowed to transfer trainees or utilize trainees on other NDOR-let projects which do not contain the Training Special Provisions. NDOR will utilize a Change Order / Supplemental Agreement to incorporate the Training Special Provisions and the appropriate pay item into the contracts of such projects.
22. On all federally funded NDOR-let projects, trainees must be paid at least 60 percent of the appropriate minimum journey-level rate specified in the contract for the first half of

the training period, 75 percent for the third quarter, and 90 percent for the last quarter of the training period - or the appropriate rates approved by the U.S. Department of Labor or the U.S. Department of Transportation in connection with the program in which the trainee is enrolled.

23. In order to document and evaluate a trainee's progress toward journey-level status, the Contractor must provide NDOR at the end of each month a "Special Training Provision Monthly On-The-Job Training Report" listing each trainee, the number of hours trained during the month, and the total number of hours trained as of the date of the report.

NOTE: The monthly reporting requirements may change if/when on-line reporting is implemented by NDOR.

24. If a trainee's employment is terminated for any reason prior to completion of the number of OJT hours for which the individual was approved, the Contractor must make Good Faith Efforts to replace the trainee with another minority or female.
25. Contractors must submit an annual summary report to NDOR by January 15th each year giving an account of all trainee hours provided during the previous year. The report shall show a breakdown of training provided on each project and/or contract.
26. Contractors will have fulfilled their OJT responsibilities if they have provided acceptable training for the number of hours assigned, or have demonstrated that they made a Good Faith Effort to provide the number of OJT hours assigned. Where a Contractor cannot meet his or her annual training hour goal with females and minorities, the Contractor remains responsible for demonstrating the Good Faith Efforts taken in pursuance of the goal. Examples of what actions constitute Good Faith Efforts are set forth below. NDOR will make compliance determinations regarding the Training Special Provisions based upon either attainment of the annual goal or Good Faith Efforts to meet it.
27. Good Faith Efforts are those designed to achieve equal opportunity through positive, aggressive, and continuous results-oriented measures (23 CFR § 230.409(g)(4)). Good Faith Efforts should be taken as trainee hiring opportunities arise and when minorities and women are under-represented in the Contractor's workforce. NDOR will consider all Contractors' documentation of Good Faith Efforts on a case-by-case basis and take into account the following:
 - a. Availability of minorities, females, and disadvantaged persons for training;
 - b. The potential for effective training;
 - c. Duration of the contract;
 - d. Dollar value of the contract;
 - e. Total normal work force that the average Contractor could be expected to use;
 - f. Geographic location;
 - g. Type of work;
 - h. The need for journey level individuals in the area.

Good Faith Efforts may include, but are not limited to, documentation of efforts to:

- Contact minority and female employees to gain referrals on other minority and female applicants;
- Refer specific minorities and females to training programs and specifically request these trainees by name in the future;
- Upgrade minority and female unskilled workers into the skilled classifications when possible;
- Accept applications at the project site or at the Contractor's home office;
- Review and follow up on previously received applications from minorities and females when hiring opportunities arise;
- Maintain monthly evaluations that monitor efforts made to achieve diversity in the Contractor's workforce in general (i.e., significant numbers of minorities and females employed on a company-wide basis);
- Provide incentives for project management personnel or superintendents when hiring goals are met on a project (i.e., similar to performance bonuses paid when a job is completed in a timely manner and under budget).

28. Liquidated damages will be assessed the Contractor for failure to demonstrate a Good Faith Effort to achieve their full OJT assignment or for failure to demonstrate a Good Faith Effort to achieve their full OJT assignment with minority and women trainees.

Liquidated damages will be assessed at the rate of \$4.00 per hour for the number of OJT hours not achieved or, even if achieved, the number of OJT hours in which the Contractor fails to demonstrate Good Faith Efforts to hire minorities and women. (e.g., if the Contractor was assigned 3,000 hours but only achieved 2,000 hours and did not demonstrate a Good Faith Effort, the liquidated damages would be assessed at 1,000 hours x \$4.00 = \$4,000.00.)

29. NDOR will invoice a Contractor for liquidated damages assessed as a result of the Contractor's failure to demonstrate a Good Faith Effort to achieve the number of OJT hours assigned.

The Contractor's failure to promptly pay any invoice for liquidated damages may result in the Contractor being disqualified to bid work with NDOR for a time period determined by the Director/State Engineer.

30. At the end of the calendar year, if the dollar amount of work the Contractor performed on NDOR-let projects is substantially below the three-year average upon which the Contractor's OJT assignment was based, the Contractor's OJT goal for that year may be adjusted according to the table in Paragraph 2. above.

31. The established per hour unit price for the item "Training" shall be full compensation for all costs incurred, which includes but is not limited to providing the necessary

supervision, labor, equipment, tools and material. Any additional costs due to payment of wages in excess of the minimum rates specified and for the payment of any fringe benefits shall not be paid for directly, but shall be considered subsidiary to the items for which direct payment is made.

AMENDMENT TO CONSTRUCTION TRAINING REPORT REQUIREMENTS

The last sentence under Paragraph C., on Page 5 of the Standard Federal Equal Employment Opportunity Construction Contract Specifications, dated November 3, 1980, is void.

FHWA Form 1409 "Federal-aid Highway Construction Contractor's Semi-Annual Training Report" is not required.

STATUS OF UTILITIES

The following information is current as of February 27, 2017.

Aerial and/or underground utilities may exist within the limits of this project. The Contractor shall determine to their satisfaction the extent of occupancy of any utility facilities located within the project construction areas and the extent of conflict with the proposed work under this contract.

At this time, no utilities have been required to relocate their facilities.

Any utility adjustments or interruption of service for the convenience of the Contractor shall be the sole responsibility of the Contractor.

To arrange for utilities to locate and flag their underground facilities, contact Diggers Hotline of Nebraska at 1-800-331-5666, or dial 811.

Any work necessary will be concurrent with construction.

STATUS OF RIGHT-OF-WAY

All work is to be performed within the existing Right of Way as located by the Engineer.

ENVIRONMENTAL COMMITMENT

Bid No.: _____ **Control/Contract No.:** M3275C

Maintenance Activity: Meadow Grove Deck Repair

Below are the Conservation Conditions that will be required for this project. All conditions and regulations of any permit obtained for this project will be followed by the Contractor. The NDOR District Environmental Coordinator and District Maintenance Superintendent(s) will serve as an NDOR point of contact.

Wetlands

The Contractor shall not stage, store, waste or stockpile materials and equipment in known/potential wetlands and/or known/potential streams that exhibit a clear “bed and bank” channel. Potential wetland areas consist of any area that is known to pond water, swampy areas or areas supporting known wetland vegetation or areas where there is a distinct difference in vegetation (at lower elevations) from the surrounding upland areas. Deck debris shall be captured as to not allow debris to enter the channel. (Contractor, District)

Threatened & Endangered Species

District 3 is within the range of multiple State and Federally Listed Threatened & Endangered Species. Range maps and County Lists for these species can be found on the Nebraska Game and Parks Commission website (found below).

Bridge deck and joint repair as outlined below is allowed with the following General Conservation Conditions.

General Conservation Conditions

Threatened and Endangered Species. The Contractor shall reference the Nebraska Game and Parks Commission website for a reference of federal and state listed species that may occur in the project vicinity prior to starting project maintenance operations. These guidance documents can be found at:

- <http://outdoornebraska.gov/atriskspecies/>

If federal or state listed species are observed during maintenance operations, stop work and contact the NDOR District Environmental Coordinator and District Maintenance Superintendent to determine action required prior to resuming work. Coordination with NDOR Environmental Section will be required if Night-Time work is needed.

Refueling. The Contractor shall conduct refueling only within non-wetland and non-stream locations. Areas adjacent to wetlands and/or streams will be avoided. Spills shall be reported to the NDOR District Environmental Coordinator and District Maintenance Superintendent. The contractor shall be responsible for cleanup of spilled fuel or any other Hazardous Materials, such as engine oil, hydraulic fluid, antifreeze, etc. used in the contract specified maintenance activity. The Contractor is required by NDOR's Standard Specification section 107 (legal relations and responsibilities to the public) to handle and dispose of contaminated material in accordance with applicable laws.

The District Environmental Coordinator shall be responsible for recording and tracking of the spill event through NDOR's DIRK Database.

<http://www.transportation.nebraska.gov/ref-man/specbook-2007.pdf>

Restricted Activities. The following project activities shall, to the extent possible, be restricted to between the beginning and ending points of the project, within the right-of-way designated on the project plans.

- Construction debris waste disposal areas
- Asphalt plants
- Stockpiling areas
- Staging areas
- Material storage sites

Waste/Debris. Construction waste/debris will be disposed of in areas or a manner which will not adversely affect state and/or federally listed species and/or designated critical habitat. Deck debris shall be captured as to not allow debris to enter the channel. (Contractor)

Encountering Unexpected Waste

If contaminated soils and/or water or hazardous materials are encountered, then all work within the immediate area of the discovered hazardous material shall stop until NDOR/FHWA is notified and a plan to dispose of the Hazardous Materials has been developed. Then NDEQ shall be consulted and a remediation plan shall be developed for this project. The potential exists to have contaminants present resulting from minor spillage during fueling and service associated with construction equipment. Should contamination be found on the project during construction, the NDEQ shall be contacted for consultation and appropriate actions to be taken. The Contractor is required by NDOR's Standard Specification section 107 (legal relations and responsibilities to the public) to handle and dispose of contaminated material in accordance with applicable laws. (Contractor)

Ground Disturbance

Any and all ground disturbance shall be limited to fill material locations only, with any fill material disturbances not to exceed the depth of the fill material. (Contractor)

Unmarked Human Burial Sites

The contractor shall comply with the Nebraska Unmarked Human Burial Sites and Skeletal Remains Protection Act, Sections 12-1201 – 12-1212. If human skeletal remains or burial goods associated with an unmarked human burial in the ground or on the ground are discovered, then all work in the immediate area of the discovery shall stop and the contractor shall contact the NDOR District Environmental Coordinator. The NDOR District Environmental Coordinator will then comply with Section 12-1205, notification of local law enforcement in the county in which the remains or burial goods are found. The NDOR District Environmental Coordinator will promptly consult with the appropriate federal, state, and tribal agencies to determine if further field investigations are required before maintenance operations may resume. Pertinent legal authorities covering such discoveries include: the National Historic Preservation Act, the Native American Graves Protection and Repatriation Act, the Archeological Resources Protection Act, the Nebraska Unmarked Burial Sites and Skeletal Remains Protection Act, and the Nebraska Archeological Resources Protection Act.

Any discovered archeological or paleontological objects or deposits are not the property of the Contractor. The NDOR Environmental Coordinator will consult with appropriate federal, state, or tribal agencies to determine the proper disposition of such remains.

FLOODPLAIN PERMIT

Nebraska Department of Roads Floodplain/Floodway Development Permit/Application

Permit Application No. FP001.16
Date: 5/13/16

This form is used for any man-made change to improved or unimproved transportation facility, including, but not limited to, buildings or other structures, mining, dredging, filling, grading, paving, excavation, drilling operations, or storage of equipment or materials.

Nebraska Department of Roads will obtain all other necessary federal, state, or local permits (e.g., Corps of Engineers 404 Permit, Local Levee District, etc.)

1.	Name of Applicant: Nebraska Department of Roads PO Box 94759 Lincoln NE 68509-4759		
2.	Type and Use of Development: Maintenance	3.	Specific Location of Development: Highway 275 near Meadow Grove

The following section is provided by NDOR for the community official's monitoring/tracking purposes:

4.	<p>Is the Development Substantial Improvement? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>Complete this section if the proposed development involves the improvement of a structure (i.e., walled and roofed building).</p> <p>Pre-improvement Value of Structure: \$ _____</p> <p>Cost of Improvement: \$ _____</p>
5.	<p>Is the development in an identified floodplain? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Please see attached documentation.</p> <p>If Yes, complete the following:</p> <p>a. Elevation of the Base (100-Year) Flood _____ Ft. MSL/NGVD 29 or NAVD 88</p> <p style="text-align: center;">Or</p> <p>Worst case impact _____ rise in the Base (100-year) Flood</p> <p>* If project includes multiple floodplain crossings, this information is summarized in attached documentation.</p> <p>b. Elevation/Floodproofing Requirement (if applicable) _____ NA Ft. MSL/NGVD 29 or NAVD 88</p> <p>c. Is the development in a designated Floodway?</p> <p><input type="checkbox"/> Yes New structures for human habitation are prohibited. For any other Floodway development, the NDOR must provide certification by a registered professional engineer that the development would result in no increase along the floodway water surface profile.</p> <p><input checked="" type="checkbox"/> No If a floodway has not been designated, the NDOR may be required to submit hydraulic data demonstrating that the proposed development will not increase flood heights more than one foot at any location.</p>

If the development is in a floodplain, the following shall apply:

If work includes a new or substantially improved nonresidential building, NDOR will provide certification by a Registered Engineer, Architect, or Land Surveyor that the building is elevated or flood proofed at least one foot above the base flood elevation.

By signing below, the local authorizing official acknowledges the above and any floodplain information submitted with this permit application.

All provisions of the Madison Co. Floodplain Management Resolution/Ordinance (Number Article 6) shall be complied with.
(County or City)

Heather McWorter, Administrator 5/18/2016
Local Authorizing Official (Name & Title) Date

KTO 5-13-2016
NDOR Environmental Permits Manager Date

Project Name: Meadow Grove Deck Repairs	
Project No.: NA	
Control No.: M3275C/M3275D	Structure No.: Multiple

**SPECIAL PROSECUTION AND PROGRESS
(Migratory Birds)
(A-42-0417)**

The Department of Roads will, to the extent practicable, schedule the letting of projects such that clearing and grubbing can occur outside of the primary nesting season in Nebraska which has been determined to generally occur between April 1 and September 1. Work on structures, such as but not limited to bridges and culverts, should occur outside the primary swallow nesting season, April 15 to September 30, unless approved methods of avoiding nesting have been taken on the bridge and/or culvert structures. The nesting dates above are a guide only, nesting can occur outside of those dates. Work outside of those dates is not exempt from compliance with the Migratory Bird Treaty Act.

The Contractor shall, to the extent possible, schedule work on structures, such as but not limited to bridges and culverts, and clearing and grubbing activities to occur outside the primary nesting season in Nebraska. However, if circumstances dictate that project construction or demolition must be done when nesting migratory birds may be present, a survey of the number of active nests and species of birds shall be conducted by qualified personnel representing the Contractor, and assisted by the Project Manager (PM) or NDOR Environmental Section staff. If the survey finds that nests will be impacted by the proposed construction, the Contractor may be responsible for delays.

The following guidance is provided for compliance with the Migratory Bird Treaty Act for construction of NDOR projects:

1. The Contractor shall submit a plan to the NDOR regarding how he intends to accomplish bridge demolition or clearing and grubbing of the project to avoid conflict with nesting migratory birds.
2. The Contractor must submit a temporary erosion control plan tailored to fit the plan for clearing and grubbing.
3. If construction operations result in unavoidable conflict with nesting migratory bird's eggs or young, which will result in "taking" nests and their contents, the Contractor should notify the NDOR Project Manager (PM). The PM shall notify the Environmental Section of Planning and Project Development by telephone at 402-479-4766.
4. The NDOR Environmental Section will then determine if assistance in conducting the survey will be provided by the NDOR Environmental Section (if available) and arrange for assistance with the survey of nest numbers, bird species, etc. Results of the survey shall be maintained by the NDOR until project completion.
5. If the nesting survey is required, and the project was awarded prior to the nesting season, and the Contractor did not accomplish clearing/grubbing and/or work on bridge/culvert structures outside the nesting season, the Contractor will reimburse the Department of Roads for each survey required at \$1,000 per survey. If the project was awarded during the nesting season, and construction activities are such that clearing/grubbing and/or work on bridge/culvert structures must be accomplished prior to any other activity on the project, then there will be no charge assessed for the initial survey. The Contractor is responsible for removing all trees surveyed, that do not contain active nests, and for taking

appropriate measures on bridge/culvert structures, within 3 days of the survey. Reimbursement for additional surveys may be charged if the Contractor fails to remove the trees within 3 days of the survey, and requires an additional survey. Survey reimbursement will be determined on a project specific basis, considering the project timeline and associated activities.

6. If an active nest is found during the survey, the Contractor should do everything possible to restructure his activities and leave the nest undisturbed until the young fledge. Fledging could occur within a week, or up to a month, after the survey depending on the species of bird and whether the nest contained eggs or young. Also depending on the species of bird and their sensitivity to disturbance, a buffer of up to 30 feet surrounding the tree with the active nest could be required.
7. If construction cannot be rescheduled to allow the birds to fledge, and it is determined as an unavoidable "take" circumstance, the Contractor shall stop all work within 30 feet of the active nest and coordinate with the Construction Project Manager to determine how to proceed. The Construction Project Manager will then coordinate with the NDOR Environmental Section and they will facilitate coordination with the US Fish and Wildlife Service and the Federal Highway Administration (for projects using Federal-aid) to determine the appropriate way to address the active nest. No work shall occur within 30 feet of the active nest until US Fish and Wildlife Service coordination is complete and the requirements of the Migratory Bird Treaty Act are satisfied.
8. It is the Contractor's responsibility to schedule his work to accommodate the process of conducting a survey(s) and submitting the necessary documentation if avoidance is not practicable. The Contractor shall be responsible for using any legal and practical method to prevent the nesting of birds in order to prevent the need for any survey and prevent the need for additional surveys. It is understood and agreed that the Contractor has considered in the bid all of the pertinent requirements concerning migratory birds (including endangered species) and that no additional compensation, other than time extensions if warranted, will be allowed for any delays or inconvenience resulting in these requirements.

STORM WATER DISCHARGES (A-43-0408)

In compliance with the Federal Water Pollution Control Act, authorization to discharge storm water on this project has been granted under National Pollutant Discharge Elimination System (NPDES) General NPDES Permit Number NER110000 for Storm Water Discharges from Construction Sites to Waters of the State of Nebraska. This permit became effective on January 1, 2008.

Contractors are advised that, under the Construction Storm Water General Permit, ***plant sites, camp sites, storage sites, and borrow or waste sites not shown on the plans may be subject to separate NPDES permit authorization requirements for stormwater discharges from those locations.*** Contractors shall be responsible for verifying the need for NPDES permit coverage with the Nebraska Department of Environmental Quality (NDEQ). When

required for these locations, the filing of a "Notice of Intent" shall be made by the Contractor directly to the NDEQ.

Additionally, asphalt (SIC Code 2951) or concrete (SIC Code 3273) batch plants that are owned by a private contractor and are operated on a contract-for-service basis to perform work for the Contractor completing the project may be subject to NPDES General Permit Number NER000000 for Industrial Storm Water Discharges. While the plant may be required for completion of the project, it is not under the control of the Department (or other project owner); and the filing of a "Notice of Intent" shall be made by the Contractor directly to the NDEQ.

The NDEQ may be contacted at 402-471-4220 for additional information.

REQUIRED SUBCONTRACTOR/SUPPLIER QUOTATIONS LIST (A-43-0307)

All bidders must provide to the NDOR the identity of all firms who provided quotations on all projects, including both DBEs and non-DBEs. This information must be on a form provided by the NDOR Contracts Office.

If no quotations were received, the bidder must indicate this in the space provided.

Each bidder will be required to submit one list per letting to cover all projects bid.

PROPOSAL GUARANTY BID BOND (A-43-0307)

Paragraphs 1.a. and 1.b. of Subsection 102.15 in the *Standard Specifications* are void and superseded by the following:

- a. OPTION 1 - (Project Specific Paper Bid Bond). The Bid Bond shall be executed on an original Department Bid Bond Form, which may be obtained from the Department. The original Bid Bond shall be delivered to the Department with the bid. A reproduction or a copy of the original form will not be accepted and will cause the bid not to be opened and read.
- b. OPTION 2 - (Annual Bid Bond). The Department at its discretion may allow a bidder to place an "Annual Bid Bond" on file with the Department. This bond would cover all projects the bidder bids for a 12-month period shown in the bond. The bidder must indicate in the bid submittal to the Department that their "Annual Bid Bond" applies to the submitted bid. The original Annual Bid Bond shall be executed on the Department of Roads Bid Bond Form, which may be obtained from the Department. A reproduction or a copy of the original form will not be accepted.

**WORKER VISIBILITY
(A-43-0507)**

Pursuant to Part 634, Title 23, Code of Federal Regulations, the following modified rule is being implemented:

Effective on January 1, 2008, all workers within the right-of-way who are exposed either to traffic (vehicles using the highway for purposes of travel) or to construction equipment within the work area shall wear high-visibility safety apparel.

High-visibility safety apparel is defined to mean personal protective safety clothing that:

- 1 - is intended to provide conspicuity during both daytime and nighttime usage, and
- 2 - meets the Performance Class 2 or Class 3 requirements of the ANSI/ISEA 107-2004 publication titled "American National Standards for High-Visibility Safety Apparel and Headwear."

**VALUE ENGINEERING PROPOSALS (VEP)
(A-43-0807)**

Subsection 104.03 in the *Standard Specifications* is amended to include the following:

14. A VEP will not be accepted if the proposal is prepared by an Engineer or the Engineering Firm who designed the contract plans.

**LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC
(A-43-0210)**

Paragraph 4.a. of Subsection 107.01 in the *Standard Specifications* is void and superseded by the following:

4. a. Whenever the Contractor violates any governing Federal, State or Local environmental quality regulation and/or is in noncompliance with any environmental commitment, the violating activity must cease immediately until the appropriate remedy can be determined by: the Engineer, the NDOR Environmental Section, the Federal Highway Administration (for projects utilizing Federal-aid) and other agencies, as deemed appropriate. The Engineer, with assistance from the NDOR Environmental Section and the FHWA, will provide a written order confirming the appropriate corrective action to the Contractor. Work can resume to normal conditions once the Engineer determines that the violation or non-compliance has been addressed in accordance with the order for corrective action.

Subsection 107.01 in the *Standard Specifications* is amended to include the following two paragraphs:

5. Should the Contractor encounter any previously unidentified hazardous materials, the Engineer shall be promptly notified. The Contractor shall suspend operations in the area involved until such time that arrangements are made for their proper treatment or removal.
6. The Contractor shall prevent the transfer of invasive plant and animal species. The Contractor shall wash equipment at the Contractor's storage facility prior to entering the construction site. The Contractor shall inspect all construction equipment and remove all attached vegetation and animals prior to leaving the construction site.

**SPECIAL PROSECUTION AND PROGRESS
(Federal Immigration Verification System)
(A-43-1209)**

The Contractor shall register with and use a Federal Immigration Verification System to determine the work eligibility status of newly hired employees physically performing services within the State of Nebraska. The Prime Contractor shall contractually require every subcontractor to register with and use a Federal Immigration Verification System to determine the work eligibility status of newly hired employees physically performing services within the State of Nebraska.

The Federal Immigration Verification System shall be an electronic verification of the work authorization program of the Illegal Immigration Reform and Immigration Responsibility Act of 1996, 8 U.S.C. 1324a, known as the E-Verify Program. The Contractor may use an equivalent Federal program designated by the United States Department of Homeland Security or other Federal agency authorized to verify the work eligibility status of a newly hired employee. The equivalent program shall comply with the Immigration Reform and Control Act of 1986.

The Prime Contractor shall furnish a letter to the NDOR Construction Division in Lincoln on company letterhead and signed by an officer of the company stating that documentation is on file certifying that the Contractor and all subcontractors have registered with and used a Federal Immigration Verification System. The Contractor shall maintain all records of registration and use for a period of three years and make records available upon request. The Contractor shall contractually require subcontractors to maintain all records for a period of three years and make records available upon request.

Payment will not be made to the Contractor for using the Federal Immigration Verification System or the maintenance of the records. This work shall be subsidiary to the work being performed.

The Contractor's Certification shall become part of the final records of the Contract. The Department considers this document to have direct bearing to the beginning interest date and may affect the amount of interest earned.

**CONTRACT TIME ALLOWANCE
(A-43-0911)**

Paragraph 5. of Subsection 108.02 of the *Standard Specifications* is void and superseded by the following:

5. Each week, the Engineer shall post on the Department's website a report of working days or calendar days charged. The Contractor then has 14 days from the day the Engineer's report is posted to provide a written explanation of why he/she does not concur with the working days or calendar days as assessed.

Paragraph 6.b. of Subsection 108.02 of the *Standard Specifications* is amended to include the following:

- (4) If the time allowance for the contract has been established on a calendar day basis, the Contractor is expected to schedule the work and assign whatever resources are necessary to complete the work in the time allowance provided regardless of the weather. Accordingly, regardless of anything to the contrary contained in these *Specifications*, the Department will not consider delays caused by inclement or unseasonable weather as justification for an extension of the contract time allowance unless:
 - i. the weather phenomena alleged to have contributed to or caused the delay is of such magnitude that it results in the Governor issuing a Disaster Declaration, **and**
 - ii. the weather phenomena alleged to have contributed to or caused the delay can clearly be shown to have directly impacted the work on the critical path identified on the Contractor's schedule.

Paragraphs 10.b. and 10.c. of Subsection 108.02 of the *Standard Specifications* are void and superseded by the following:

- b.
 - (1) If the extra work is not in the original contract, time extensions will be granted by determining the actual time necessary to accomplish the extra work.
 - (2) If the extra work is the result of the addition of additional quantities of existing contract items, time extensions will be granted by either:
 - (i) determining the actual time necessary to accomplish the extra work; or
 - (ii) determining the additional time to be granted by comparing the value of the additional quantities of work to the total amount of the original contract when measurement of the actual additional time is not possible or practical.
 - (3) In either case, only the time necessary to perform the extra work of the additional quantities of existing contract items when the extra work or the additional quantities of existing contract items are deemed to be the current controlling operation will be granted as a time extension.

- c. Increases in quantities of work associated with traffic control items measured by the day will not be considered for extending the contract time allowance. Overruns of traffic control items that are measured by methods other than time may be considered for extending the contract time allowance, but they must be deemed to be a controlling operation when the overrun of quantities occurs.

**PARTIAL PAYMENT
(A-43-1110)**

Paragraph 2. of Subsection 109.07 of the *Standard Specifications* is void and superseded by the following:

- 2. When the value of the work completed during a semi-monthly period exceeds \$10,000, the Contractor will receive semi-monthly progress estimates from which the Department shall make such retentions as may be allowed by the contract, provided that the nature and quality of the completed work are satisfactory and provided further that the progress of the work conforms to the requirements of Subsection 108.07.

Paragraph 3.b. of Subsection 109.07 of the *Standard Specifications* is void and superseded by the following:

- b. Under normal circumstances, the Department shall not retain any earnings on a progress estimate. However, the Department reserves the right to retain such amounts as are necessary for material deficiencies, anticipated liquidated damages, unpaid borrow, and for other reasons to protect the Department's interests.

**PARTIAL PAYMENT
(A-43-0611)**

Paragraph 4. of Subsection 109.07 of the *Standard Specifications* is void and superseded by the following:

- 4. a. (1) Upon presentation by the Contractor of receipted bills, billing invoices, or such other documentation sufficient to satisfy the Engineer and verify the Contractor's or subcontractor's actual costs for the materials, payments may also be allowed for acceptable nonperishable materials purchased expressly to be incorporated into the work and delivered in the vicinity of the project or stored in acceptable storage places within Nebraska.
- (2) Materials not delivered and stored in the immediate vicinity of or on the actual project site must be clearly marked to identify the project on which they are to be used, must be segregated from similar materials at the storage site, and cannot be included in a supplier's inventory of material available for sale for other purposes.
- (3) All items eligible for partial payment as stored materials must be available for verification, sampling, and measurement.

- b. The amount to be included in the payment will be determined by the Engineer, but in no case shall it exceed 100 percent of the value of the materials documented. This value may not exceed the appropriate portion of the value of the contract item or items in which such materials are to be incorporated, nor shall the quantity in any case exceed the total estimated quantity required to complete the project.
- c. Payment will not be approved when the documented value of such materials amounts to less than \$1,000.00, when the progress of the work is not in accordance with the requirements set forth in Subsection 108.07, or when the material can reasonably be expected to be incorporated into the work and eligible for payment as completed work on a progress estimate within 15 days of being placed into storage.
- d. Deductions at rates and in amounts which are equal to the payments will be made from estimates as the materials are incorporated into the work.
- e. Payment for the materials shall not in itself constitute acceptance, and any materials which do not conform to the specifications shall be rejected in accordance with Subsection 106.05.
- f. The Contractor shall be responsible for all damages and material losses until the material is incorporated into the work and the work is accepted.
- g. Partial payment will not include payment for fuels, supplies, form lumber, falsework, other materials, or temporary structures of any kind which will not become an integral part of the finished construction.
- h. No partial payments will be made on living or perishable plant materials until planted.

**BUY AMERICA
(A-43-0212)**

Subsection 106.07 in the *Standard Specifications* is void and superseded by the following:

106.07 -- Buy America

- 1. The Buy America rule requires that steel or iron materials be produced domestically, and only those products which are brought to the construction site and permanently incorporated into the completed project are covered. Construction materials, forms, etc., which remain in place at the Contractor's convenience, but are not required by the contract, are not covered.
- 2. To further define the coverage, a domestic product is a manufactured steel construction material that was produced in one of the 50 States, the District of Columbia, Puerto Rico, or in the territories and possessions of the United States.
- 3. All manufacturing processes to produce steel or iron materials (i.e., smelting, and any subsequent process which alters the steel or iron material's physical form or

shape, or changes its chemical composition) must occur within one of the 50 States, the District of Columbia, Puerto Rico, or in the territories and possessions of the United States, to be considered of domestic origin. This includes processes such as casting, rolling, extruding, machining, bending, grinding, drilling, and coating. Coating includes epoxy coating, galvanizing, painting, and any other coating that protects or enhances the value of the material. The manufacturer shall include a statement on the material test report or certification that all material described above except the coating material is a domestic product.

4. Raw materials used in the steel or iron materials may be imported. All manufacturing processes to produce steel or iron materials must occur domestically. Raw materials are materials such as iron ore, limestone, waste products, etc., which are used in the manufacturing process to produce the steel products. Waste products would include scrap; i.e., steel no longer useful in its present form from old automobiles, machinery, pipe, railroad tracks and the like. Also, steel trimmings from mills or product manufacturing are considered waste. Extracting, crushing, and handling the raw materials which is customary to prepare them for transporting are exempt from Buy America. The use of pig iron and processed, pelletized, and reduced iron ore manufactured outside of the United States may be used in the domestic manufacturing process for steel and/or iron materials.
5. Notwithstanding this requirement, a minimum of foreign steel or iron materials will be permitted if its value is less than one-tenth of one percent of the total contract cost or \$2,500, whichever is greater.
6. Upon completion of all work utilizing steel or iron products, the Prime Contractor shall furnish a letter to the State on company letterhead and signed by an officer of the company stating that documentation is on file certifying that all steel or iron materials brought to the construction site and permanently incorporated into the work complied in all respects with the Buy America requirements.

BORROW, WASTE, STOCKPILE, AND PLANT SITE APPROVAL (A-43-0512)

Subsection 107.02 in the Standard Specifications is amended to include the following:

4. Site Approval:
 - a. When borrow is obtained from a borrow site or waste excavation is placed at sites which are not shown in the contract, or the Contractor plans to use a plant or stockpile site which is not shown in the contract, the Contractor shall be solely responsible for obtaining all necessary site approvals. The Department will provide the procedures necessary to obtain approvals from the U.S. Army Corps of Engineers, U.S. Fish and Wildlife Service, Nebraska State Historical Society, Nebraska Game and Parks Commission, and Nebraska Department of Natural Resources on the NDOR website. The Contractor shall also be responsible for obtaining a Discharge Number from the Nebraska Department of Environmental Quality (NDEQ) that allows work under the current

Construction Stormwater Permit. The Contractor shall also be responsible for obtaining any and all other permits required by local governments.

- b. It is anticipated that it may require 60 calendar days or more for the Contractor to obtain the necessary approvals. The Contractor will not be allowed to begin work at borrow or waste sites until the necessary approvals are obtained. No extension of completion time will be granted due to any delays in securing approval of a borrow or disposal site unless a review of the time frames concludes that there were conditions beyond the Contractor's control.

Paragraph 7. of Subsection 205.02 in the Standard Specifications is void and superseded by the following:

- 7. Borrow and Waste Site Approval:
 - a. Borrow and waste site approvals shall be in accordance with Section 107.02.
 - b. Material shall not be removed from borrow sites until preliminary cross sections and representative soil samples have been taken by the Engineer. The Contractor shall notify the Engineer a sufficient time in advance of the opening of any borrow site so that cross sections may be taken.
 - c. Material shall be removed in a manner that will allow accurate final cross sections to be taken for determining the quantity of excavation. The surfaces of the borrow sites shall be bladed and shaped to drain as shown in the contract or as directed by the Engineer.

**SPECIAL PROSECUTION AND PROGRESS
(Subletting or Assigning of Contract)
(A-43-0414)**

Subsection 108.01 in the Standard Specifications is void and superseded by the following:

108.01 – Subletting or Assigning of Contract

- 1. a. (1) The Contractor will not be allowed to sublet, assign, sell, transfer, or otherwise dispose of any portion of the contract or any right, title, or interest therein; or to either legally or equitably assign any of the money payable under the contract or the claims without the prior written consent of the Engineer.
- (2) With the Engineer's consent, the Contractor may sublet up to 70 percent of the work.
- (3) Any items designated in the contract as "specialty items" may be performed by subcontract.

- (4) The cost of any subcontracted “specialty items” may be deducted from the total contract cost before computing the percentage of work required to be performed by the Contractor.
 - (5) Subcontracts, or transfer of contract, will not release the Contractor of any liability under the contract and bonds.
 - b. Certain items of work may be performed without a subcontract. A list of items not requiring a subcontract is available from the Engineer.
2. The performance of any work by a subcontractor before the date of authorization by the Department shall subject both the Contractor and subcontractor to the imposition of appropriate sanctions by the Department.
3. a. The Contractor’s request to sublet work shall be made electronically to the NDR Construction Engineer using project management software identified by the Department. A signed subcontract agreement shall be on file in the Contractor’s office when the request is made. The subcontract agreement must provide that the subcontracted work will be completed according to the terms of the contract. The required and Special Provisions contained in the proposal shall be physically included in any subcontract.
 - b. On all Federal-aid projects, a scanned copy (.pdf format) of the signed subcontract agreement shall be included with the subcontracting request. (Federal-aid projects can be identified by inclusion in the Proposal of Form FHWA-1273 (REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS)).**
 - c. Scanned copies (.pdf format) of all executed subcontracts, written agreements, and/or lease agreements used to meet DBE goals shall be submitted to the NDR Construction Engineer with the subcontracting request. These copies must show labor cost, material prices, overhead and profit.
4. a. Second tier subcontracts will be allowed.
 - b. If a DBE firm subcontracts work to another firm, only work subcontracted to another DBE firm can be counted toward meeting a DBE goal.
 - c. All requests for second tier subcontracting shall be submitted to and approved by the Prime Contractor before they are forwarded to the NDR Construction Engineer for approval.
5. All subcontract documents relating to the contract shall be maintained during the course of the work and preserved for a period of three years thereafter. These documents shall be available for inspection by authorized representatives of State and Federal agencies. Scanned copies (.pdf format) of the signed subcontract agreements not specifically identified elsewhere in this Subsection shall be furnished to the Department upon request.
6. The Contractor may discuss a proposed subcontract with the Engineer before entering into a signed subcontract agreement, but final approval will not be

granted until a formal request and proper certification has been received by the Department.

7. On projects requiring submittal of certified payrolls, all subcontractor payrolls shall be checked by the Contractor before submittal to the Engineer.
8. a. The Prime Contractor, and subcontractors when subletting work to lower tier subcontractors, shall include language which can be identified as a "Prompt Payment Clause" as a part of every subcontract for work and materials.
 - b. (1) The language constituting the "Prompt Payment Clause" will require payment to all first tier subcontractors for all labor and materials --- for work completed to date --- within 20 calendar days of receipt of progress payments from the Department for said work. Similar language in a contract between a subcontractor and a lower-tier subcontractor will require payment to the lower tier subcontractor for all labor and materials --- for work completed to date --- within 10 calendar days of receipt of progress payments from the prime Contractor for said work.
 - (2) The language constituting the "Prompt Payment Clause" will also stipulate the return of retainage within 30 calendar days after the satisfactory completion of the work by the subcontractor as evidenced by inclusion of the work on a progress payment.
 - (3) Additionally, the language constituting the "Prompt Payment Clause" may stipulate the subcontractor's obligation to return to the Contractor or subcontractor, as the case may be, any overpayments which result from adjustments to measured and recorded quantities as part of the preparation of subsequent progress payments or the final records. Overpayments shall be returned to the Prime Contractor or subcontractor, as the case may be, within 20 calendar days of receiving notice of the adjusted quantities and the amount of the overpayment.
- c. The Prime Contractor of subcontractors, as the case may be, may withhold payment only for just cause and shall not withhold, delay, or postpone payment without first receiving written approval from the Department.
- d. (1) The failure by the Prime Contractor to abide by the agreements identified in the "Prompt Payment Clause" without just cause, including the timely return of retainage, is a material breach of this contract which may result in the Department withholding the amount of payment from the prime Contractor that should have been paid to the subcontractor, termination of this contract, or other such remedy as the Department deems necessary.
 - (2) Additionally, the failure of any subcontractor to abide by the agreements identified in the "Prompt Payment Clause" without just cause, including the timely return of retainage to lower tier subcontractors, or by failing to return overpayments in a timely manner when the language permitted in Paragraph 8.b.(3) above is included in the subcontract may result in the Department withholding subcontract approval for other work until the overpayments have been returned.

9. a. (1) For Davis Bacon (DBRA)-covered projects and Non-DBRA-covered projects, a Contractor or subcontractor may wish to use another individual owner-operator or trucking company to supplement his or her hauling fleet. (The Department will not recognize multiple individuals claiming to be collectively identified as a single "owner operator.")
- (2) This supplemental individual or company must either become a subcontractor (first tier or lower tier, as the case may be) or be otherwise documented by the utilizing Contractor or subcontractor by entering into a lease agreement for the trucks and showing the driver (or drivers) from the supplemental company on the Prime Contractor's or subcontractor's payrolls in the manner described below.
- (3) Payrolls will only be accepted from the Prime Contractor or approved subcontractors.
- b. (1) If the decision is made to subcontract the hauling, the Prime Contractor must first notify the NDOR Construction Office to request subcontract approval. As part of the subcontract approval process --- at any tier --- the proper certificates of insurance must be provided before approval will be granted.
- (2) Additionally, on DBRA-covered projects, the Prime Contractor must submit payrolls for all subcontractors --- at any tier.
- c. (1) Owner/Operators of trucks hired by a Contractor or subcontractor to supplement his or her hauling fleet are not subject to Davis Bacon wage requirements. However, they must still be shown on a payroll prepared by the Contractor or subcontractor for whom they are working with the notation "owner/operator."
- (2) Any other employees of the "owner/operator" must appear on the certified payroll in complete detail and must be compensated according to the wage rates established for the project.
- d. In the event a Prime Contractor or subcontractor elects to not subcontract the supplemental driver or drivers but instead chooses to "carry the workers/truckers on their payroll," the following requirements must be met:
 - (1) The Prime Contractor's or subcontractor's certified payroll must contain the names of all workers/truck drivers, and the payroll should identify their supervisors (including "owner-operators").
 - (2) Pay checks for the workers/truckers in question must be drawn against the Prime Contractor's or subcontractor's payroll or other account.
 - (3) Owner/Operators need only be identified as such on the payroll. Additional drivers, if any, from the "owner-operator's" company must appear on a payroll in complete detail and be compensated according to the wage rates established for the project.

- (4) The Prime Contractor or subcontractor must enter into a lease agreement for the trucks driven by such drivers, and the lease agreement must show that the compensation for the leased equipment is on a time basis and not based on the amount of work accomplished. The lease agreements must be available for inspection by NDOR personnel.
- (5) Any supplemental truckers employed under this arrangement must still carry the minimum automobile liability coverage specified in the contract. It shall be the duty of the Prime Contractor to ensure that the supplemental truckers have such coverage in effect. Evidence of proper insurance must be presented for verification on demand.

ELECTRONIC SHOP DRAWINGS (A-43-0215)

Paragraphs 5, 6, and 7 of Subsection 105.02 of the Standard Specifications are void and superseded by the following:

5. a. The Contractor shall provide electronic working drawings in a Portable Document Format (PDF). The PDFs shall be sized to print on an 11x17 inch sheet of paper and have a minimum resolution of 300 dpi. Each sheet of the shop drawings shall have a space provided for an electronic stamp that measures 2.5 inches x 3.5 inches when printed.
- b. Electronic working drawing files shall be named with the following file naming format:

Control Number_Brief Description_Date.pdf

For example: 12345_FloorDrains_05Feb2015
12345_FloorDrainCoverLetter_05Feb2015
- c. The project number, control number, and project location as it appears on the plans shall be shown on the front sheet of each Shop Drawing file. Structure numbers shall be included, if applicable.
6. No electronic working drawings shall be submitted to the Engineer unless they have been checked by the Contractor. The electronic submittal shall be accompanied by a Contractor's letter of approval in a PDF format. This letter shall also be named with the format shown in the example above. The letter of approval shall clearly indicate that the Contractor is responsible for any errors on the working drawings.
7. a. Electronic submittals shall be submitted by email to the following address:

DOR.ShopDrawings@nebraska.gov

b. Attachments shall be limited to 25 MB of data per email. Larger files shall be separated and sent in multiple emails.

c. Electronic working drawings will only be accepted from the Prime Contractor.

8. Any reference to hard copy shop drawings in the contract shall be considered void.

**PLANS AND PROPOSALS
(A-43-0117)**

Paragraphs 3. and 4. of Subsection 111.01 in the Standard Specifications are void and superseded by the following:

Plans and Proposals are available for purchase on the NDOR Storefront website.

**LIABILITY INSURANCE
(A-55-0414)**

Subsection 107.13 in the Standard Specifications is void and superseded by the following:

107.13 – Liability Insurance

Prior to execution of the contract, the Contractor shall obtain insurance coverage to fully protect it from loss associated with the work, and have at a minimum the insurance described below:

1. General Liability:
Limits of at least:
 - \$ 1,000,000 per Occurrence
 - \$ 2,000,000 General Aggregate
 - \$ 2,000,000 Completed Operations Aggregate
 - \$ 1,000,000 Personal and Advertising Injury
- a. Contractor shall be responsible for the payment of any deductibles.
- b. Coverage shall be provided by a standard form Commercial General Liability Policy (CG0001 or equivalent) covering bodily injury, property damage including loss of use, and personal injury.
- c. The General Aggregate shall apply on a Per Project Basis.
- d. The State of Nebraska, Department of Roads, shall be named as an Additional Insured on a primary and non-contributory basis including completed operations for three (3) years after final acceptance and payment.
- e. Contractor agrees to waive its rights of recovery against the State of Nebraska, Department of Roads. Waiver of Subrogation in favor of the State of Nebraska, Department of Roads shall be added to the policy.
- f. Contractual liability coverage shall be on a broad form basis and shall not be amended by any limiting endorsements.

- g. If work is being performed near a railroad track, the 50' railroad right-of-way exclusion must be deleted.
 - h. Products and completed operations coverage in the amount provided above shall be maintained for the duration of the work, and shall be further maintained for a minimum period of three years after final acceptance and payment.
 - i. Coverage shall be included for demolition of any building or structure, collapse, explosion, blasting, excavation and damage to property below surface of ground (XCU coverage).
 - j. Policy shall not contain a total or absolute pollution exclusion. Coverage shall be provided for pollution exposures arising from products and completed operations as per standard CG0001 Pollution Exclusion or equivalent. If the standard pollution exclusion as provided by CG0001 has been amended, coverage must be substituted with a separate Pollution Liability policy of \$1.0 million per occurrence and \$2.0 million aggregate. If coverage is provided by a "claims made" form, coverage will be maintained for three years after project completion. Any applicable deductible is the responsibility of the Contractor.
2. Automobile Liability:
Limits of at least:
\$ 1,000,000 CSL per Accident
- a. Coverage shall apply to all Owned, Hired, and Non-Owned Autos.
 - b. If work is being performed near a railroad track, the 50-foot railroad right-of-way exclusion must be deleted.
 - c. Contractor agrees to waive its rights of recovery against the State of Nebraska, Department of Roads. Waiver of Subrogation in favor of the State of Nebraska, Department of Roads, shall be added to the policy.
 - d. Automobile liability coverage shall be obtained from an insurance carrier who is licensed with the Nebraska Department of Insurance.
3. Workers' Compensation:
Limit: Statutory coverage for the State where the project is located.
Employer's Liability limits: \$500,000 Each Accident
\$500,000 Disease – Per Person
\$500,000 Disease – Policy Limit
- a. Contractor agrees to waive its rights of recovery against the State of Nebraska, Department of Roads. Waiver of Subrogation in favor of the State of Nebraska, Department of Roads shall be added to the policy.
 - b. Workers' compensation coverage shall be obtained from an insurance carrier who is licensed with the Nebraska Department of Insurance.

- c. Where applicable, the Longshore and Harborworkers Compensation Act endorsement shall be attached to the policy.
- 4. Umbrella/Excess:
Limits of at least:
\$1,000,000 per Occurrence
 - a. Policy shall provide liability coverage in excess of the specified Employers Liability, Commercial General Liability and Automobile Liability.
 - b. The State of Nebraska, Department of Roads, shall be an "Additional Insured."
 - c. Contractor agrees to waive its rights of recovery against the State of Nebraska, Department of Roads. Waiver of subrogation in favor of the State of Nebraska, Department of Roads shall be provided.
- 5. Pollution Liability:
 - a. When "hazardous wastes" or contaminated or polluted materials must be handled and/or moved, the Contractor shall obtain Pollution Liability Coverage with minimum limits of \$1,000,000 per occurrence and \$2,000,000 aggregate.
 - b. If, during the course of construction, hazardous wastes, contaminated or polluted material are discovered on the project, the Contractor shall immediately cease any operation that may disturb these materials, and shall immediately notify the Engineer of all facts related to the discovery of these materials.
 - c. Unforeseen work related to the discovery of hazardous, contaminated or polluted materials on the project, and the extra cost, if any, of pollution liability coverage will be handled as "extra work."
- 6. Additional Requirements:
 - a. The Contractor shall provide and carry any additional insurance required by the Special Provisions.
 - b. Except as otherwise provided herein, all insurance shall be kept in full force and effect until after the State releases the Contractor from all obligations under the contract.
 - c. (1) If any of the work is sublet, equivalent insurance shall be provided by or on behalf of the subcontractor or subcontractors (at any tier) to cover all operations.
(2) Approved trucking subcontractors (at any tier) who are being utilized only for the purpose of hauling materials shall be exempt from the requirements of Paragraphs 1, 4, and 5.

- (3) (i) When a Contractor or subcontractor chooses to employ a trucker by carrying the driver on his or her payroll and entering into a lease agreement for the truck, the owner-operator of the truck shall be required to comply with the Automobile Liability provisions of Paragraph 2.
 - (ii) Furthermore, it shall be the duty of the Prime Contractor to ensure that the owner-operator of the truck has such insurance in effect. The Prime Contractor shall maintain evidence that any truckers so utilized (at any tier) are insured to the minimum limits specified and be able to furnish documentation of the same on demand.
 - (iii) Failure to ensure that insurance coverage exists and failure to maintain evidence thereof shall be considered a breach of the contract.
- d. Any insurance policy shall be written by an insurance company with a Best's Insurance Guide Rating of A – VII or better.
- e. Prior to execution of the contract, Contractor shall provide the State of Nebraska, Department of Roads, evidence of such insurance coverage in effect in the form of an Accord (or equivalent) certificate of insurance executed by a licensed representative of the participating insurer(s). Certificates of insurance shall show the Nebraska Department of Roads as the certificate holders.
- f. For so long as insurance coverage is required under this agreement, the Contractor shall have a duty to notify the Department when the Contractor knows, or has reason to believe, that any insurance coverage required under this agreement will lapse, or may be cancelled or terminated. The Contractor must forward any pertinent notice of cancellation or termination to the Department at the address listed below by mail (return receipt requested), hand-delivery, or facsimile transmission within 2 business days of receipt by Contractor of any such notice from an insurance carrier. Notice shall be sent to:
 - Nebraska Department of Roads
 - Construction Division --- Insurance Section
 - 1500 Highway 2, P.O. Box 94759
 - Lincoln, NE 68509-4759
 - Facsimile No. 402-479-4854
- g. Failure of the owner or any other party to review, approve, and/or reject a certificate of insurance in whole or in part does not waive the requirements of this agreement.
- h. The limits of coverage set forth in this document are suggested minimum limits of coverage. The suggested limits of coverage shall not be construed to be a limitation of the liability on the part of the Contractor or any of its subcontractors/tier subcontractors. The carrying of insurance described shall in no way be interpreted as relieving the Contractor,

subcontractor, or tier subcontractors of any responsibility or liability under the contract.

- i. If there is a discrepancy of coverage between this document and any other insurance specification for this project, the greater limit or coverage requirement shall prevail.

CONSTRUCTION DETAILS

TEMPORARY WATER POLLUTION CONTROL (B-3-1014)

Section 204 in the Standard Specifications is void.

CONSTRUCTION STORMWATER MANAGEMENT CONTROL (B-3-1014)

A. General

1. This Section defines some best management practices (BMPs) for erosion and sediment control measures and construction practices the Contractor shall use to prevent soil erosion and avoid water pollution.
2.
 - a. The Department and the Contractor are co-permittees of the NPDES Construction Storm Water General Permit.
 - b. The Contractor shall comply with all conditions required by the current NPDES Construction Storm Water General Permit.
3. The Contractor shall exercise every reasonable precaution throughout the life of the contract to prevent silting of the waters of the state, the project site, and adjacent property. Construction of drainage facilities, as well as performance of other contract work which will contribute to the control of siltation, shall be carried out in conjunction with earthwork operations or as soon thereafter as is practicable.
4.
 - a. The Contractor shall take sufficient precautions to prevent pollution of the waters of the state, the project site, and adjacent property from construction debris, petroleum products, chemicals, or other harmful materials.

The Contractor shall conduct and schedule the operations to avoid interference with any protected species.
 - b. The Contractor shall comply with all applicable statutes relating to pollution of the waters of the state and fish and game regulations.

5. All construction debris shall be disposed in a manner that it cannot enter any waterway. Excavation shall be deposited as to protect the waters of the state from siltation.
6. All erosion and sediment control measures shall be properly installed and maintained by the Contractor until all permanent drainage facilities have been constructed, and all slopes are sufficiently vegetated to be an effective erosion deterrent; or until tentative acceptance of the work.
7. All erosion and sedimentation resulting from the Contractor's operations and the weather conditions must be corrected by the Contractor.

LIMITATION OF OPERATIONS (B-3-1014)

A. General

1. The maximum exposed surface area for the Contractor's operations in excavation, borrow, and embankment is 18 acres (72,800 m²) plus an equal area of clearing and grubbing/large tree removal. A written request for an increase in the maximum exposed surface area may be approved by the Engineer. This approval will be based on the soil, moisture, seasonal conditions, the Contractor's operation, or other conditions.
2. The Engineer shall have the authority to reduce the maximum exposed surface area when any of the following conditions warrant:
 - a. Soil and moisture conditions are such that erosion is probable.
 - b. Seasonal conditions may force extended delays.
 - c. Proximity to the waters of the state requires more stringent controls.
 - d. Equipment and personnel available on the job is not sufficient to properly maintain erosion and dust control measures.
 - e. Any other environmental condition in the area that may exist which would be affected by erosion from the project.
3. Construction operations in rivers, streams, wetlands, and impoundments shall be restricted to those areas specifically shown in the contract. Rivers, streams, wetlands, and impoundments shall be promptly cleared of all false work, piling, debris, or other obstructions placed therein or caused by the construction operations.
4. Fording and operation of construction equipment within streams and wetlands will not be allowed, unless explicitly allowed in the contract. Streams are defined as any area between the high banks, regardless of the flow conditions.

CONSTRUCTION METHODS (B-3-1014)

A. General

1. The Contractor shall conduct all construction activities and install temporary erosion control measures, as necessary, to control sediment and avoid soil erosion during construction.
2. The Contractor shall incorporate all permanent erosion control features into the project at the earliest practicable time.
3. Construction stormwater management control measures for Contractor obtained work areas located outside the right-of-way, such as borrow site operations, haul roads, plant sites, staging sites, waste sites, equipment storage sites, etc. are the sole responsibility of the Contractor. All construction stormwater management control measures for these areas are at the Contractor's expense. The Contractor is responsible for securing all required permits for use of these sites.
4. The construction stormwater management procedures contained herein shall be coordinated with any permanent erosion control measures specified elsewhere in the contract to the extent practical to assure economical, effective, and continuous erosion and sediment control throughout the construction period.
5. The Contractor shall be responsible to limit erosion and prevent siltation into the waters of the state during the construction period, as well as during the times that work may be suspended.
6.
 - a. All erosion and sediment control items shall be installed by personnel who are knowledgeable in the principles and practice of various BMP installations.
 - b. The installation of all erosion and sediment control items shall be done under the direct supervision of the Contractor's employee who has successfully completed training provided by the Department and has been certified as an Erosion and Sediment Control Inspector (Inspector). The Contractor's Inspector shall be present at each site during installation to direct and inspect all erosion and sediment control BMP installations.
 - i. The NDOR Erosion and Sediment Control Inspector Certification is obtained by completing an Erosion and Sediment Control Inspector Training Course provided by the Nebraska Department of Roads and passing the examination that accompanies the training.
 - c. The Contractor shall notify the Engineer of all employees, who have been certified as Inspectors, who will be on the project to direct and inspect all erosion and sediment control BMP installations.
 - d. No payment will be made for any erosion and sediment control item unless a Contractor's Inspector was present to directly supervise and inspect the work.

- e. No payment will be made for any erosion and sediment control item that is not properly installed. All erosion and sediment control items shall be installed as per the contract.

**ENVIRONMENTAL COMMITMENT DOCUMENT
(B-3-1014)**

A. Environmental Commitment Document

- 1. a. An Environmental Commitment Document will be created by the Department to identify all project specific environmental commitments and will be included in the Contract.
- b. The Department will provide information for the following, when applicable:
 - i. Storm Water Pollution Prevention Plan (SWPPP)
 - ii. U.S. Army Corps of Engineers (USACE) Section 404 Permit
 - iii. Nebraska Department of Environmental Quality 401 Water Quality Certification
 - iv. State Title 117 Waters (USACE Non-Jurisdictional)
 - v. Floodplain Permit
 - vi. Historic Clearance
 - vii. Endangered Species Act Clearance
 - viii. Nebraska Nongame and Endangered Species Conservation Act Clearance
 - ix. National Environmental Policy Act Compliance
 - x. NPDES Construction Stormwater Permit (within Right-of-Way limits, only)
 - xi. Conservation Measures
 - xii. Migratory Bird Treaty Act
 - xiii. Bald and Golden Eagle Protection Act Compliance
 - xiv. Other pertinent issues
- c. The Contractor shall provide information for the following, when applicable:
 - i. Temporary Erosion Control Plan
 - ii. Spill Prevention and Control Plan
 - iii. Migratory Bird Treaty Act Compliance Plan
 - iv. Name and telephone number of the Contractor's representative responsible for the Environmental Commitments

- v. Name and telephone number of the employees that are NDOR-Certified Erosion and Sediment Control Inspectors
- vi. Critical Path Construction Schedule
- vii. Other items as defined elsewhere in the contract

**STORM WATER POLLUTION PREVENTION PLAN (SWPPP)
(B-3-1014)**

A. General

1. A SWPPP is required for projects that construction activities will cause a land disturbance of one (1) acre or more. The Department will prepare the SWPPP for the areas within the Right-of-Way, temporary easements and permanent easements.
2. For projects not requiring a SWPPP, the Contractor shall comply with the requirements of Environmental Commitment Document, Paragraph 1.b. of this Special Provision, as applicable.
3. Contractor obtained work areas, located on private property, are not included in the NDOR Project SWPPP.

B. Temporary Erosion Control Plan

1. The Contractor shall prepare and submit the Temporary Erosion Control Plan prior to the start of any work. The Contractor shall not begin work until the Temporary Erosion Control Plan has been submitted to the Engineer and appropriate erosion control measures are in place. Payment for any work on the contract will be withheld if erosion control measures are not in place or properly maintained.
2. The Temporary Erosion Control Plan will be reviewed at project progress meetings. All active Contractors shall have their Inspectors present and work in cooperation to determine any necessary changes. Necessary changes will be documented on the Temporary Erosion Control Plan by the Engineer.
3. Payment for preparing the Temporary Erosion Control Plan, inspections and meeting reviews are subsidiary to items that direct payment is made.

C. Spill Prevention and Control Plan

1. All project activities shall be addressed in the Spill Prevention and Control Plan. The Contractor shall prepare and submit the plan to the Engineer and install all appropriate spill prevention and control measures prior to the start of any work.
2. The Spill Prevention and Control Plan shall clearly state measures to prevent, contain, document and clean up a spill. It shall state measures for disposal of the contaminated material, disposal documentation and incident review to train personnel to prevent spills from reoccurring.

3. Spill Prevention and Control Plans are applicable to construction sites where hazardous materials are stored, used and/or generated onsite. Hazardous materials include, but not limited to: hazardous wastes, pesticides, paints, cleaners, petroleum products, fertilizers, solvents and porta-potty wastes.
4. Direct payment will not be made for the Spill Prevention and Control Plan.

D. Migratory Bird Treaty Act Compliance Plan

1. The Contractor shall not begin work until a Migratory Bird Treaty Act Compliance Plan has been submitted to the Engineer and appropriate nesting migratory bird avoidance measures are in place.
2. a. The Contractor shall clearly state the necessary measures they intend to use to avoid a "Take" of nesting migratory birds in the Migratory Bird Treaty Act Compliance Plan. Measures may include but are not limited to:
 - i. Clearing and grubbing prior to April 1st or after September 1st
 - ii. Tree removal prior to April 1st or after September 1st
 - iii. Clearing empty nests on structures prior to April 1st
 - iv. Maintaining clear structures until commencement and throughout the duration of work on structures
 - v. Netting structures to prevent nesting
 - vi. Commitment to perform surveys according to protocol
 - vii. Hire a biologist to survey areas to be disturbed prior to commencement of work during the nesting season
 - viii. Submittal of required bird survey reports
 - ix. Training of Contractor Personnel to insure compliance
3. a. The Migratory Bird Treaty Act Compliance Plan is applicable to the entire project site to avoid the "Take" of migratory birds protected under the Migratory Bird Treaty Act.
b. "Take" is defined as: pursuit, hunt, shoot, wound, kill, trap, capture, collect, or attempt to pursue, hunt, shoot, wound, kill, trap, capture, or collect.
4. The Migratory Bird Treaty Act Compliance Plan shall adhere to the NDOR's Avian Protection Plan located at:

<http://www.transportation.nebraska.gov/environment/guides/avian-protection-plan.pdf>

Direct payment will not be made for the Migratory Bird Treaty Act Compliance Plan.

E. SWPPP Inspection

1. The Contractor shall accompany the Engineer on inspections in accordance with the NPDES Construction Storm Water General Permit.
2. The SWPPP will be maintained and updated by the Engineer as work progresses and site conditions change to accurately describe the BMPs that are currently in place.
3. The Contractor's participation in SWPPP inspections, maintenance and updates shall begin on the first day construction activities cause land disturbance and end on the date of project completion as evidenced as the completion date in the District Engineer's Letter of Tentative Acceptance.
4.
 - a. The Contractor's Inspector shall be responsible for ensuring that all BMPs are installed in accordance with the contract or the manufacturers' recommendations. The Contractor's Inspector shall be capable of reading and interpreting these documents.
 - b. The Contractor's Inspector shall be familiar with product and structural BMPs. The Contractor's Inspector shall inspect, assess, and supervise the maintenance of erosion and sediment control BMPs to ensure compliance with the NPDES Construction Storm Water General Permit while preserving BMP functionality.
5. Payment for project inspection is subsidiary to items that direct payment is made.

**ENVIRONMENTAL COMMITMENT ENFORCEMENT
(B-3-1215)**

A. General

1. This specification establishes payment and disincentive assessment for the Contractor's performance in complying with Contract Environmental Commitments.
2. Deficiencies are described but not limited to:
 - a. Failure to install pollution prevention control BMPs as work progresses or as described in the SWPPP.
 - b. Failure to maintain existing pollution prevention control BMPs.
 - c. Failure to remove non-functioning pollution prevention control BMPs.
 - d. Failure to comply with USACE Section 404 Permit requirements.
 - e. Failure to comply with NPDES Construction Storm Water General Permit requirements.

- f. Failure to comply with all applicable statutes relating to pollution of the waters of the state.
- g. Exceeding the maximum exposed surface area for excavation of 18 Acres without written request for permission and written approval.
- h. Failure to comply with wildlife species specific conservation conditions.
- i. Failure to comply with the Contract.
- j. Failure to comply with the Engineers directives.

B. SWPPP Deficiency Notification

- 1. The Engineer will document and direct the Contractor to correct deficiencies.
- 2.
 - a. The Contractor shall commence correcting deficiencies, provide adequate equipment and personnel, and diligently pursue correcting deficiencies without cessation until all deficiencies have been corrected.
 - b. The count of Working Days and/or Calendar Days will continue during the time period that corrective work is being performed.
 - c. Delays to the project as a result of the Contractor conducting corrective actions for the Contract Environmental Commitments will not constitute a valid reason for an extension of the contract time allowance.
- 3. Deficiencies shall be corrected within seven (7) calendar days of notification or within an approved extension. When deficiencies are not corrected within seven (7) calendar days or within an approved extension, the Engineer will make a disincentive assessment to the contract as stated herein.
- 4.
 - a. If soil, weather, or other conditions prevent the Contractor from completing the corrective actions within seven (7) calendar days, the Contractor shall notify the Engineer in writing. The Contractor's letter shall state the reasons preventing corrective action within the time allowed. The Contractor shall propose a written Corrective Action Plan within 48 hours. Corrective work shall continue while the Corrective Action Plan is developed. The Contractor's Corrective Action Plan must contain a course of action and a time frame for completion. If the reasons and the Corrective Action Plan are acceptable, the Engineer may extend the time in which to complete the corrective work.
 - b. The Contractor will be allowed to proceed with the plan as proposed without incurring a disincentive assessment. If all corrective work is completed within the time allowance shown in the Notification or within an approved extension, a disincentive assessment will not be imposed upon the Contractor.
 - c. Storm events or soil and weather conditions occurring on other projects, which interfere with a Contractor completing corrective actions on the

project within seven (7) calendar days, will not be justification for a time extension to complete the corrective work.

5. If all corrective work identified in the Notification has not been completed at the end of the seventh (7th) calendar day after the Initial Notice Date or within an approved extension, a Shut-Down Notice will be issued on the eighth (8th) calendar day after the Initial Notice Date or on the calendar day following the last day of an approved extension.
6. All operations shall cease as of the date and time cited in the Shut-Down Notice. The Contractor shall work, exclusively, on the deficiencies until all have been corrected or as directed by the Engineer. Upon issuance of the Shut-Down Notice, a disincentive of \$500.00 per deficiency per calendar day will be assessed thru the day the corrective work is completed, inclusive.
7. The Engineer may require the Contractor to provide a written Procedures Plan that describes the process to prevent reoccurrence of deficiencies. The written Procedures Plan shall be provided within two (2) calendar days of the request. Failure to correct all deficiencies and provide a Procedures Plan may result in payments being withheld until such time that procedures are outlined.
 - a. Payment for preparing a written Procedures Plan is subsidiary to items that direct payment is made.

C. Storm Event Restoration – Incentive and Disincentive

1. The Department will pay “Storm Event Restoration - Incentive” when the Contractor completes the restoration work to eliminate the pollution prevention control deficiencies within seven (7) calendar days of Notification or within an approved extension. Multiple deficiencies may be included in one notification. If the restoration work has not been completed within seven (7) calendar days after the Initial Notice or within an approved extension, payment for the item of “Storm Event Restoration - Incentive” will not be made.
2. A storm event is defined as a storm exceeding 0.50 inch of rain in a 24 hour period.
3. The Department will notify the Contractor of pollution prevention control deficiencies.
4.
 - a. Payment for the item of “Storm Event Restoration - Incentive” may not be made when the Contractor is notified to correct pollution prevention devices not installed in accordance with the contract or the manufacturer’s recommended installation instructions.
5. If the restoration work is not completed within seven (7) calendar days or within an approved extension, a disincentive assessment of \$500.00 per deficiency per calendar day will be assessed. The disincentive assessment will begin on the eighth (8th) calendar day after the issuance of the Initial Notice Date or on the calendar day following the last day of an approved extension(s) and continue through the day that the restoration work is completed, inclusive.

D. Method of Measurement

1. a. “Storm Event Restoration – Incentive” will be measured by the each upon completion of restoration of all deficiencies included in a notification within the allowed time and only one payment per notification is allowed when multiple deficiencies are included on the notification.
- b. If deficiencies from multiple notifications are restored during the same restoration operation, only one (1) incentive is eligible for payment.
- c. If multiple notifications are the result of successive storm events and deficiencies are transferred to ensuing notifications, incentive payment is only eligible for the latest notification.
2. “Storm Event Restoration – Disincentive” will be measured by the calendar day in accordance with Paragraph C.5. above.

E. Basis of Payment

- | | |
|--|-----------------|
| 1. Pay Item | Pay Unit |
| Storm Event Restoration – Incentive | Each |
| Storm Event Restoration – Disincentive | Calendar Day |
2. All equipment, materials, etc. used in the restoration work will be paid for in accordance with Division 800 of the Standard Specifications.
 3. Payment is full compensation for all other incidentals required to complete the restoration work included in the notification within the allowed time.

F. Environmental Commitments – Contractor Compliance

1. To provide payment for all plans, inspections, surveys, reports, travel, qualified inspection person’s, carrion removal, and any other subsidiary activities for the work of implementing threatened and endangered species commitments, temporary erosion control or any other environmental commitments prescribed in the contract.
2. Multiple visits to the project may be required to comply with environmental commitments prescribed in the contract.

G. Method of Measurement

1. No measurement is required.

H. Basis of Payment

- | | |
|---|-----------------|
| 1. Pay Item | Pay Unit |
| Environmental Commitments – Contractor Compliance | Lump Sum |

2. Partial payments will be made as follows:
 - a. The Department will pay 50 percent of the total amount bid for the item Environmental Commitments – Contractor Compliance within seven (7) calendar days after the Notice to Proceed Date.
 - b. Upon completion of 50 percent of the Original Contract Amount, the Department will pay 30 percent of the amount bid for the item Environmental Commitments – Contractor Compliance.
 - c. Upon completion of 75 percent of the Original Contract Amount, the Department will pay the remaining 20 percent of the amount bid for the item Environmental Commitments – Contractor Compliance.
 - d. Failure to comply with any or all of the contract requirements, included for payment under the item of Environmental Commitments – Contractor Compliance, will preclude all payment for the item, including any previous payment.
3. Payment is full compensation for all work prescribed in the contract.

I. Immediate Action Deficiencies

1. Deficiencies that pose an imminent threat to the environment are considered an emergency situation. These deficiencies will be identified in the Immediate Action Deficiencies Section of the Environmental Commitment Deficiency Notification Form. The corrective work for Immediate Action Deficiencies shall begin immediately and continue without cessation until completed.
2. The Engineer will issue a shut-down notice. All work on the contract shall cease until the corrective work has been completed. The Engineer may allow the Contractor to continue working in areas unaffected by the Immediate Action Deficiency, provided corrective actions are being actively performed on the deficiency.
3. Immediate Action Deficiencies are not eligible for an incentive payment.
4. The Contractor will be assessed a disincentive assessment of \$1,000.00 per deficiency per calendar day for failure to begin corrective actions or failing to continue to completion as directed by the Engineer or by the regulatory agency with jurisdiction.
5. Examples of Immediate Action Deficiencies include but are not limited to:
 - a. Threatened & Endangered Species habitat protection deficiencies
 - b. USACE Section 404 Permit Noncompliance
 - c. Petroleum Spills/Tank Leakage
 - d. Hazardous Material Spills

J. Rights Reserved

1. The Department reserves the right to initiate and perform corrective action on any deficiencies which result from the Contractors' actions, inactions, or for failure to comply with the NPDES Construction Stormwater General Permit, USACE Section 404 Permit, or any other applicable permit.
2. The Contractor shall be liable to the Department for any and all costs incurred by the Department for corrective actions taken by the Department.
3. It is expressly understood that the provisions of this specification shall not relieve the Contractor of their responsibilities nor shall it relieve the Surety of its obligation for and concerning any just claim.
4. The Contractor shall indemnify and save harmless the Department and all of its representatives from any and all actions or claims brought because of the Contractor's actions, inactions, or for failure to comply with the NPDES Construction Storm Water General Permit, USACE Section 404 Permit, or any other applicable permit.

**TYPE B HIGH INTENSITY WARNING LIGHTS
(D-6-0307)**

All references in the plans to Type B High Intensity Warning Lights shall be considered void. The plans will not be revised to reflect this change.

**TEMPORARY TRAFFIC CONTROL DEVICES
(Type II Barricades, Reflectorized Drums, 42" (1070 mm) Reflective Cones, and
Vertical Panels)
(D-6-1112)**

Paragraph 2.d. of Subsection 422.03 in the Standard Specifications is void and superseded by the following:

- d. (1) Reflectorized drums used for traffic warning or channelization shall be constructed of lightweight, flexible, and deformable materials, be a minimum of 36 inches (900 mm) in height, and have a minimum width of 18 inches (450 mm), regardless of orientation. The predominant color of the drum shall be orange.
- (2) Steel drums shall not be used.

- (3) The markings on drums shall be horizontal, shall be circumferential, and shall display four 6-inch (150 mm) wide bands of retroreflective sheeting, alternating fluorescent orange - white – fluorescent orange - white. The fluorescent orange sheeting shall meet the luminance requirements of the following table.

FHWA Luminance Factor

Sheeting Type	Luminance Factor Y_T		
	Min	Max	Fluorescence Luminance Factor Limit, Y_F
Fluorescent Orange	25	None	15

- e. When approved by the Engineer or shown in the plans, 42" (1070 mm) reflective cones may be used in lieu of Type II Barricades or Reflectorized Drums. 42" (1070 mm) reflective cones shall include a 30-pound (14 kg) rubber base and display four 6-inch (150 mm) wide bands of retroreflective sheeting, alternating fluorescent orange - white - fluorescent orange - white. 42" (1070 mm) reflective cones shall not be used for lane-closure tapers or shifts.
- f. Rubber base-mounted 36-inch vertical panels shall not be used for channelization when the speed limit exceeds 40 miles per hour.

Paragraph 2.b. of Subsection 422.04 of the Standard Specifications is void and superseded by the following:

- b. (i) Type II Barricades, Reflectorized Drums, and 42" (1070 mm) Reflective Cones shall be counted as "Barricades, Type II" and measured for payment by the number of calendar days each is in place and positioned as shown in the plans or as directed by the Engineer.
- (ii) Vertical Panels shall be measured for payment as permanent "Sign Days" (by the each) by the number of calendar days each vertical panel unit is in place and positioned as shown in the plans or as directed by the Engineer.

Paragraph 2.c. of Subsection 422.04 of the Standard Specifications is amended to include Reflectorized Drums.

Paragraphs 3. and 4. of Subsection 422.05 of the Standard Specifications are void and superseded by the following:

3. a. The pay item "Barricade, Type II" is used to pay for three items ("Barricades, Type II", "42" (1070 mm) Reflectorized Cones", and "Reflectorized Drums").
- b. "Barricades, Type II", which includes "42" (1070 mm) Reflectorized Cones", and "Reflectorized Drums", is paid for as an "established" contract unit price item. The established unit price is identified on the "Schedule of Items" shown in the Proposal.
4. Payment for vertical panels includes all posts, brackets, or hardware necessary to install and maintain the vertical panel units.

WORK ZONE TRAFFIC CONTROL SIGNS (D-6-1212)

The Department has adopted the FHWA 2009 Manual of Uniform Traffic Control (MUTCD) and the 2011 Nebraska Supplement to the MUTCD as the official guidance for work zone traffic control signs. Many work zone traffic control signs have been revised, redesigned, or replaced in the 2009 MUTCD (and 2011 Nebraska Supplement). Accordingly, all work zone signs shall comply with the following:

- 1 - All signs, regardless of age, shall meet the design standards of the 2009 MUTCD (and 2011 Nebraska Supplement).

TEMPORARY PAVEMENT MARKING (D-10-0811)

Paragraph 4.f. of Subsection 422.01 in the Standard Specifications is void.

Paragraph 6.a.(2) of Subsection 422.03 is void and superseded by the following:

- (2) When the markings are no longer needed, the Contractor shall remove them. If removing markings from the final wearing surface, the removal process shall not mar or damage the surface. Removed markings shall no longer be visible on the final wearing surface.

Paragraph 6. of Subsection 422.03 in the Standard Specifications is amended to include the following:

This work shall consist of installing and removing reflectorized temporary pavement lines of the color, width and line configuration shown in the plans or as designated by the Engineer.

Temporary paint markings will be used on this project. The use of Type I tape will not be permitted and Type II tape may be used for short durations only, as directed by the Engineer. Temporary paint stripes shall be a minimum 4" (100 mm) wide, 10' (3 m) long with a 30-foot (9 m) gap or a minimum 4" (100 mm) wide solid line as shown on the plans.

Temporary pavement marking which is no longer applicable shall be removed as directed by the Engineer.

Paragraph 12.a. of Subsection 422.04 is void and superseded by the following:

- a. "Pavement Marking Removal" and "Temporary Pavement Marking Removal" shall be measured by the linear foot (meter) along the centerline of the traveled roadway for each line removed.

Subsection 422.04 is amended to include the following:

21. The use of paint for Temporary Pavement Marking shall be measured per linear foot (meter) for the item "Temporary Pavement Marking, Type Paint".
22. Temporary pavement marking tape Type II shall be measured per linear foot (meter) for the item "Temporary Pavement Marking, Type II".
23. Initial surface preparation requiring sand or shot blasting shall be measured per linear foot (meter) for the item "Temporary Pavement Marking, Surface Preparation". Surface preparation for repainting, consisting of air blasting and brushing, shall be subsidiary to other items for which payment is made.

Paragraph 1. of Subsection 422.05 is amended to include the following:

Pay Item	Pay Unit
Temporary Pavement Marking Removal	Linear Foot (LF)
Temporary Pavement Marking, Type Paint	Linear Foot (LF)
Temporary Pavement Marking, Type II	Linear Foot (LF)
Temporary Pavement Marking, Surface Preparation	Linear Foot (LF)

Paragraph 9.c. of Subsection 422.05 is void.

Paragraph 13. of Subsection 422.05 is void and superseded by the following:

13. Removal of temporary pavement markings including overlay broken/solid lines will be paid for except:
 - a. When the temporary markings are intended to be covered up by permanent markings.
 - b. When surface preparation removes the temporary markings.

Section 1069 in the Standard Specifications is amended to include the following:

1. Prior to the initial placement of the markings, temporary paint, or Type II tape the pavement upon which the markings are to be placed shall be dry, cleaned and properly prepared by sand or shot blasting, as a minimum, and to the extent recommended by the manufacturer so that all contaminants, loose debris, and other foreign material are completely removed. Surface preparation for any subsequent application shall consist of air blasting and brushing the roadway surface to remove all loose dirt, mud or other debris and to dry the surface. Each additional application of paint shall be applied over the previously painted stripes.

Prior to placing the temporary pavement markings on the prepared surface, the Contractor shall layout, spot or string line the proposed temporary marking location. The temporary markings shall be aligned in such a way as to provide a smooth and gradual transition to and from the existing markings, and throughout both straight and horizontally curved sections of the project.
2. The material used for temporary paint marking shall be a commercially available acrylic resin Type II traffic paint that dries to no pickup in 4 minutes and shall be

applied with a minimum of 6 pounds (0.7 kg) of glass beads per gallon (liter). The paint shall be applied at a minimum width of 4 inches (100 mm) and a wet thickness of approximately 15 mils (380 μ m) {approximately 16.5 gallons (39 liters) of paint per mile (kilometer) of solid line}. The equipment used to paint the line shall be a machine designed for the purpose of applying long line traffic lane markings of the type, width and thickness required, and shall be self-propelled or truck mounted and be equipped with an adjustable guide-on to assure proper placement of the line. Hand application, walk behind equipment or towing of the equipment will not be allowed.

Temporary paint lines shall be used on new or existing concrete pavement and asphaltic concrete pavement.

Any temporary painted line or segment of line, placed before December 1, which fails to adhere to the roadway surface for a minimum of 60 days under normal vehicular traffic or which appears wavy, nonuniform, thin, poorly applied, misaligned, beadless or nonreflective, shall be replaced as directed by the Engineer. For temporary painted pavement markings placed between December 1 and March 15, the minimum time requirement shall be 15 days with the same conditions applicable. No direct payment will be made for replacement within the 60 day or 15 day warranty periods.

After the minimum 60 day or 15 day warranty periods, the Contractor may be required to repaint the temporary traffic markings, as directed by the Engineer. Direct payment will be made for each additional application. However, should the additional application fail within the 60 day or 15 day warranty periods, the provisions as stated in the previous paragraph shall apply.

The Contractor must begin each additional repainting application within 72 hours after notification by the Engineer. Should the Contractor fail to begin repainting within this 72 hour period, the Engineer may use State forces or hire a private contractor to repaint the temporary traffic markings. The Contractor will be assessed any costs above the contract unit price "Temporary Pavement Marking, Type Paint" incurred by the State as a result of performing the corrective action by others, and the project will be shut down until the painting is completed.

When painting is required with air temperatures between 38° F (3° C) and 50° F (10° C), the paint shall be heated according to the manufacturer's recommendation prior to application on the dry, clean and properly prepared pavement. Any paint application made when the air temperature is below 38° F (3° C) will be paid for by the State, even if the application falls within either the 60 day or 15 day warranty periods previously described.

3. Temporary pavement marking tape Type II shall be a mixture of high quality polymeric materials and pigments, with glass beads throughout the pigmented portion of the film, and a reflective layer of high index of refraction glass beads bonded to the top surface. The film shall be precoated with a pressure-sensitive adhesive. Unless otherwise specified, the temporary pavement marking shall be 4 inches (100 mm) wide and the reflectorizing glass beads shall be incorporated to facilitate removal of the tape easily from asphalt and Portland cement concrete surfaces intact or in large pieces, at temperatures above 40° F (4° C), either

manually or with a recommended roll up device. Removal shall be accomplished without the use of heat, solvents, grinding or sandblasting.

INERTIAL BARRIER SYSTEM (D-14-0509)

Paragraph 9.b.(5) of Subsection 422.03 in the Standard Specifications is void and superseded by the following:

- (5) All inertial barriers shall have 5 to 15 percent (by volume) rock salt mixed with the filler material.

CONCRETE PROTECTION BARRIERS (D-20-0417)

Guidance for concrete protection barriers:

1. Type A: 4-loop barriers with a large opening at the bottom.
Type B: 6-loop barriers with 4 lifting slots and no slots for tie-down rods.
Type C: 6-loop barriers with 4 lifting slots and 6 slots for tie-down rods.
2. Type A barriers will not be allowed for use on NDOR projects whose contract start date is January 1, 2018 or later, regardless of requested or granted early starts that begin projects prior to that date. Type A barriers will not be allowed on interstate or freeway roadways.
3. Barriers Type B and C may be used on this project and may directly be pinned to each other in the same installation arrangement.
4. Other existing barriers meeting NCHRP 350 or MASH (Test Level 3) testing guidelines and FHWA approval may only be used with written permission (containing this project name and/or control number) from the District and Roadway Design Division.
5. If new barriers are to be fabricated for use on this project, only Type C barriers shall be fabricated.

Paragraph 5. of Subsection 422.03 in the Standard Specifications is amended to include the following:

- f. (1) Concrete protection barriers that become dislodged or moved out of alignment shall be placed back in alignment as soon as practical. If the dislodged barriers are considered to be a hazard to the traveling public by the Engineer, or the barriers encroach into the traveled lane, the barriers shall be realigned within four (4) hours of the time the Contractor is notified. For each occurrence, failure to realign the barriers within the four (4) hour time period will result in the assessment of a lump sum \$1,000 liquidated damage assessment and the

Engineer may proceed to correct the adverse condition(s) in a manner that is deemed appropriate. The Contractor will also be assessed the cost incurred when the action is performed by others. This assessment has not been provided for elsewhere in the contract and shall be considered in addition to other liquidated damage assessments which are a part of the contract.

Paragraph 5.a. of Subsection 422.03 in the Standard Specifications is void and superseded by the following:

- a. (1) Concrete protection barriers shall be furnished by the Department and installed by the Contractor at the locations shown in the plans or designated by the Engineer for the pay item "Install Concrete Protection Barrier."
- (2) The Contractor shall furnished and install concrete protection barriers at the locations shown in the plans or designated by the Engineer for the pay item "Concrete Protection Barrier." The movement of concrete protection barriers to new locations on the project will be paid for as "Concrete Protection Barrier."
- (3) The repositioning of concrete protection barriers at the same location as directed by the Project Manager or as shown in the plans after the initial installation is included in and defines the pay item "Relocate Concrete Protection Barrier."

Guidance for the use of NDOR Concrete Protection Barriers:

The Contractor, at his/her option, may use NDOR owned concrete protection barriers from NDOR stockpiles in Districts 1 and 2 at no charge to the Contractor. The Contractor is responsible for determining to his/her satisfaction the number, type, and condition of the available concrete protection barriers at the various stockpile sites.

The available District 1 stockpile sites are as follows:

NW 27th Street south of the Lincoln Municipal Airport
The Greenwood I-80 Maintenance Yard
262nd Street near Ashland
Other various locations

The available District 2 stockpile sites are as follows:

3911 So. 29th Street
Near 26th & F Street in South Omaha
On N-36 east of N-133

Regardless of the original source of the barriers (NDOR, private, etc.) the barrier will be considered as supplied by the Contractor, and will be subject to the specifications for, and paid under the item "Concrete Protection Barrier."

It will be the Contractor's responsibility to remove the barriers in a neat and orderly fashion and to return the barriers to their original location and restack them neatly as directed by the Engineer.

For any barriers damaged beyond further use, the Contractor shall be charged \$600 per damaged barrier.

RELOCATE INERTIAL BARRIER SYSTEM

Paragraph 19. b. of Subsection 422.04 in the Standard Specifications is void and superseded by the following:

- b. "Relocate Inertial Barrier System" is the pay item for moving the inertial barrier system to a new location after initial installation and operation.

Paragraph 1. of Subsection 422.05 is amended to include the following:

1.	Pay Item	Pay Unit
	Relocate Inertial Barrier System	Each (ea)

**COLD WEATHER ASPHALTIC CONCRETE PLACEMENT
(E-8-1214)**

Table 501.02 in the Standard Specifications is void and superseded by the following:

Table 501.02

Cold Weather Asphaltic Concrete Placement	
<u>Lift Thickness</u>	<u>Minimum Surface Temperatures*</u>
Less than 2 inches (50 mm)	<u>45°F (7°C)</u>
2 to 3 inches (50 mm to 75 mm)	<u>37°F (3°C)</u>
Greater than 3 inches (75 mm)	<u>35°F (2°C)</u>

*32°F (0°C) for all lift thicknesses when a Warm Mix Additive is used in accordance with the contract.

**ASPHALTIC CONCRETE
(E-8-0217)**

Paragraph 2.a.5.(ii) of Subsection 503.03 is void and superseded by the following:

During storage, the PG Binder temperature shall be maintained in accordance with binder supplier recommendations. All plants shall be equipped with a circulating system for PG Binder which is designed to assure proper and continuous circulation during the operating period. Storage tanks shall have sufficient capacity to provide for continuous operation. The tanks shall be situated and constructed to allow the volume of the PG Binder to be safely and accurately determined at any time.

Paragraph 2.a. of Subsection 503.04 is void and superseded by the following:

2. Asphalt Mix Control Strip:

a. At the Contractor's option, the control strip may be waived. The decision to omit the control strip must be communicated to the Engineer prior to the start of production. When the control strip is waived:

- (1) The moving average of four air voids values for the first three asphaltic concrete sublots is not valid and a pay factor of 1.0 shall be applied.
- (2) The first three asphaltic concrete sublots shall be subject to the following removal criteria and removal shall be at no cost to the Department.

Sublot	Removal Criteria
1-1	V_{a1-1} less than 1.5 or greater than 7.0
1-2	$(V_{a1-1} + V_{a1-2}) \div 2$ less than 1.67 or greater than 6.67
1-3	$(V_{a1-1} + V_{a1-2} + V_{a1-3}) \div 3$ less than 1.83 or greater than 6.33

Where: V_{a1-1} = the single test air voids for Sublot 1-1
 V_{a1-2} = the single test air voids for Sublot 1-2
 V_{a1-3} = the single test air voids for Sublot 1-3

- b. On the first production day, a 600 ton (544 Mg) control strip shall be placed and approved before full production begins. The Contractor shall construct the control strip using the approved asphalt mix design with laydown and compaction procedures that are representative for the project.
- c. The Contractor shall take at least 3 control strip mixture samples and record the test results for the mixture properties. The Contractor will also record compaction density values and rolling pattern information. This data will be for information only and shared with the Engineer.

Table 503.02 is void and superseded by the following:

Table 503.02

Control Strip Sampling			
Sample No.	Ton (Mg)	Air Voids for SPH	Air Voids for SPR
1	0 to 200 (0-180)	2.5 to 6.0	1.5 to 5.0
2	201 to 400 (181-363)	2.5 to 6.0	1.5 to 5.0
3	401 to 600 (364-544)	2.5 to 6.0	1.5 to 5.0

Paragraph 2.b.(2) of Subsection 503.04 is void and superseded by the following:

- (2) Marshall or Gyratory air voids of each sample shall be calculated using the maximum specific gravity of that sample.

Paragraph 2.b.(4) of Subsection 503.04 is void and superseded by the following:

The control strip will be accepted at 100% pay if all of the following test results are met. If any of the following test results are not met, the control strip will be subject to removal.

- (i) The Dust to Binder ratio is between 0.70 and 1.70.
- (ii) CAA is no more than 5% lower than the minimum specified shown on Table 1028.02 using blended cold feed material or ignition oven test results. FAA is no more than 0.5% lower than the minimum specified using blended cold feed material or no more than 1.0% lower than the minimum specified using ignition oven test results shown on Table 1028.03.
- (iii) Air voids are between 2.5% to 6.0% for SPH and between 1.5% to 5.0% for SPR.

Paragraph 2.h. of Subsection 503.04 is void.

Paragraph 2.j. of Subsection 503.04 is void and superseded by the following:

- j. When a control strip is constructed, the Contractor will use the three individual air void tests within the control strip and apply those individual values to the individual air void test result of the first subplot of Lot 1 to calculate the initial moving average of four and resulting pay factor for the initial subplot.

Paragraphs 5.a.(1) and 5.a.(3) of Subsection 503.04 are void and superseded by the following:

- a. (1) The actual mixing temperature shall be selected by the Contractor, in accordance with binder supplier recommendations, to provide adequate aggregate coating and mixture compaction at laydown.
- a. (3) Never shall the selection of the mixing temperature be such that drainage of the PG Binder from the aggregate will exceed contract specifications.

Paragraphs 10.a. and 10.b. of Subsection 503.04 are void.

Paragraphs 2.a. and 2.b.(1) of Subsection 503.06 are void.

Paragraph 2.b. (2) of Subsection 503.06 is void and superseded by the following;

- (2) For each subplot of Asphaltic Concrete Type SPR, SPS and SPH, the asphaltic concrete unit price is a product of all applicable pay factors for the item "Asphaltic Concrete, Type ____". Included in a subplot, following approval of the control strip(s), may be any roadway Asphaltic Concrete Type SPR, SPS and SPH which is produced, sampled and tested and approved by the Engineer for use as Patching, State Maintenance Patching, and Asphalt for Intersections and Driveways on project shall be eligible for inclusion in subplot(s) tonnage pay factor determination using the roadway Asphaltic Concrete Type _____ unit price. When a control strip is not constructed, the pay factor for the running average of four air voids shall be fixed at 1.0 for the first three asphaltic concrete sublots.

Paragraphs 5.a., 5.b., and 5.c. of Subsection 503.06 are void and superseded by the following:

- 5. a. When asphaltic concrete in any lot or portion of a lot is rejected and removed from the road, payment will not be made for the asphaltic concrete or for the PG Binder contained in the rejected material. The determination of the quantity of PG Binder for which payment will not be made will be based on the percent of PG Binder used in the rejected material.
- b. The order of precedence to determine the PG Binder quantity is:
 - (1) Actual lot tests.
 - (2) The average of the day's run.
 - (3) The job-mix formula.

Paragraph 12. of Subsection 503.06 void.

**TACK COAT
(E-8-1214)**

Subsection 504.02 in the Standard Specifications is amended to include the following:

Table 504.01

CFS-1, FS-1 Emulsified Asphalt Requirements	
Tests on emulsion:	Specification
Viscosity, Saybolt Furol, T 59, 25°C (77°F), sec.	20 – 100
Sieve Test, % Retained, maximum (note 1)	0.10
Residue by Distillation, %, minimum	57.0
Storage Stability, %, maximum (note 1)	1.0
Tests on distillation residue:	
Penetration, dmm.	40 - 175
Ductility, 25°C (77°F), cm., minimum	40
Solubility in Trichloroethylene, %, minimum	97.5
Note 1: See note "b" of AASHTO M 208 Shall be formulated as either a cationic or anionic, fast-setting emulsion that is suitable for tack coat dilution, and to have an accelerated breaking time in cooler temperature applications.	

Subsection 504.03, Paragraph 3.b. is void and superseded by the following:

- b. Emulsified asphalt shall be diluted in the distributor with potable water at a rate of one part water to one part emulsified asphalt.

Subsection 504.03, Paragraph 3.c. is void and superseded by the following:

- c. The rate of application shall be adequate to bond the new bituminous layer to the existing surface. This shall be from 0.10 to 0.20 Gal/SY (0.45 to 0.90 L/m²) when applied to existing or milled surfaces, and from 0.05 to 0.10 Gal/SY (0.23 to 0.45 L/m²) when applied to freshly laid asphaltic concrete.

Paragraph 2. of Subsection 504.05 is void and superseded by the following:

- 2. Any amount of tack coat emulsified asphalt which is outside the specified property ranges of Table 504.02, shall be paid for at the contract unit price multiplied by the pay factor determined in Table 504.02. If the resultant Pay Factor for the material indicates rejection as an option, the Engineer will determine if the non-compliant material will be removed.

Table 504.02

Tolerances and Pay Factors		
Specified Property	Tolerance	Pay Factor
AASHTO T 59, Prior to Dilution, Residue after Distillation	≥ 56.0%	1.00
	54.0% - 55.9%	0.85
	52.0% - 53.9%	0.70
	< 52.0%	0.40 or Reject
<p>Pay Factors for Tests for ALL other Properties Specified*</p> <p>1.00 for deviation of ± less than or equal to 10%</p> <p>0.75 for a deviation of ± greater than 10% to less than or equal to 25%</p> <p>0.40 or Reject for deviation of ± greater than 25%</p> <p>* When the specification requirement is stated as a percentage, the test result deviation from the specification will be divided by the specification value. The resulting deviation percentage is then applied to the listed criteria.</p> <p>Note: When more than one specified property exceeds specification tolerances, the single largest Pay Factor Reduction will be the one applied.</p>		

Paragraph 3. of Subsection 504.05 is void and superseded by the following:

- 3. When disputes arise in test results, the Department will select an independent laboratory for referee testing on the remainder of the sample. The identity of the independent laboratory will not be revealed until the selected laboratory has completed the referee testing.
 - a. Only the Contractor can initiate dispute resolution, and request referee testing.
 - b. If the independent lab's tests indicate failing results and pay deductions equal to or greater than the Department's, the Contractor will reimburse the Department for the cost of testing. If the independent lab's tests

indicate that the material meets specifications or is at a pay deduction less than the Department's, the Department will assume the cost of testing. When the independent lab's tests indicate a pay deduction, the lesser of the Department's and the independent lab's deductions will be applied.

Paragraph 4. of Subsection 504.05 is void and superseded by the following:

4. Water used to dilute emulsified asphalt is subsidiary to "Tack Coat" and is included in the solution that is placed and measured for payment.

Subsection 504.05 is amended to include the following:

5. Payment is full compensation for all work prescribed in this Section.

BITUMINOUS PAVEMENT PATCHING (E-8-1212)

Paragraphs 1, 2 and 3 of Subsection 516.05 in the Standard Specifications are void and superseded by the following:

1. a. Bituminous Pavement Patching of flexible pavement and the repair or replacement of any subgrade material authorized by the Engineer will be measured by one of the methods described in Paragraph 1.b. based upon the depth of the patch.
 - b.(1) For patches 16-inches (40cm) deep or less, determined at the time of patching, the patching will be measured by the ton (megagram) of "Asphaltic Concrete for Patching, Type ____" required to complete the patch and repair any faulty subgrade. No equipment rental will be paid for this work, and all equipment used to complete the work shall be subsidiary to the item, "Asphaltic Concrete for Patching, Type ____."
 - (2) For patches more than 16 inches (40cm) deep, determined at the time of patching, the patching will be measured by the ton (megagram) of "Asphaltic Concrete for Patching, Type ____" required to complete the patch and repair any faulty subgrade. Additionally, the hours of equipment rental required to complete the patching and repair in that portion of the patch deeper than 16-inches will be measured by the hour of equipment rental in accordance with Section 919. Only approved equipment needed to patch and excavate the failure is to be rented, and only the time utilized to perform the work in the region deeper than 16-inches (40 cm) is to be measured. Excluded is any equipment needed to haul asphalt to the site.

- 2. a. Bituminous Pavement Patching of concrete pavement and the repair or replacement of any subgrade material authorized by the Engineer will be measured by the square yard (square meter) of completed and accepted work regardless of depth. Additionally, the asphaltic concrete used to complete the patch will be measured for payment and included with the roadway tonnage.
- b. Bituminous Pavement Patching of concrete pavement is divided into 3 types (see Table 516.02). The types are based on the size of the individual patches constructed in a single lane. If a damaged area spans 2 or more lanes, then the continuous patch will be counted as multiple patches -- 1 patch per lane.

Table 516.02

Asphalt Patch Sizes in Rigid Pavement	
Type	Size
A	5 SY (5 m ²) or less
B	Greater than 5 SY to 15 SY (5 m ² to 12.5 m ²)
C	Greater than 15 SY (12.5 m ²)

- 3. “Asphaltic Concrete, Type _____,” “Asphaltic Concrete for Patching, Type _____,” “Asphalt Cement _____,” and “Hydrated Lime for Asphalt Mixtures” used in either the patching of flexible pavement or concrete pavement will be measured for payment by the ton (megagram) in accordance with Subsection 503.05.

**DROP-OFF/COLD-MILLED TAPERED EDGE
(E-8-0515)**

Paragraph 7. of Subsection 107.07 is void and superseded by the following.

- 7. a. The Contractor shall conduct all operations to minimize any drop-offs (abrupt changes in roadway elevation) exposed to traffic.
 - b.(1) Unless otherwise specified in the Contract, drop-offs greater than 2 inches tall at the shoulder edge that are adjacent to the traveled way shall be protected by a wedge of compacted stable material capable of carrying traffic (the wedge being 1 vertical to 3 horizontal or flatter). An edgeline warning stripe shall be placed on the traffic side of the drop-off.
 - (2) The Engineer shall authorize other methods, such as concrete barriers or Type II barricades, to protect drop-offs when conditions do not allow a wedge of compacted, stable material.
 - (3) Unless otherwise ordered by the Engineer, drop-offs up to 2 inches (50 mm) may remain exposed with appropriate warning signs alerting motorists to the condition.
- c. Open trenches which span all or part of the traveled way and/or auxiliary lanes shall be no wider than 18 inches (450 mm) and must have a steel-plate cover placed and anchored over them. The plate shall have sufficient strength so as to only allow a maximum vertical deflection of 1/2 inch (12.5 mm). A wedge of suitable material shall create a smooth transition between the pavement and the steel plate. Warning signs shall be used to alert motorists to the presence of the steel plates.

Paragraphs 3.b. and 3.c. of Subsection 510.04 are void and superseded by the following.

3. b. The Contractor shall not leave a milled vertical edge greater than 1-inch tall between lanes overnight. One of the following options shall be performed if the milling will result in a vertical grade separation greater than 1 inch (25 mm) between lanes:
 - (1) Milling shall be performed in all adjacent traffic lanes on the same day so that at the end of each day, no drop off of over 1 inch (25 mm) remains.
 - (2) The milling shall create a tapered edge between the traffic lanes. The tapered edge shall have a slope from 3 [H]: 1 [V] to 4 [H]: 1 [V], not measured more than one foot in width nor extend into the lane more than one foot. Temporary pavement marking shall be placed at the top and contiguous with the tapered edge.
- c. If the Contractor fails to complete the above options, the Contractor shall provide – at no cost to the Department – additional traffic control necessary to maintain traffic on the milled lane (or lanes) as directed by the Engineer. This additional traffic control may require the use of a pilot car, flaggers, lighted flagger station, etc.
- d. Transitions between milled and unmilled in the direction of travel surfaces will be feathered either by milling or with wedges of bituminous material (maximum slope 1 vertical to 12 horizontal).

OPTIONAL NOTCHED WEDGE JOINT (E-8-1013)

Description

The Contractor has the option of constructing a notched wedge joint. If the Contractor chooses to construct this joint, it shall be built as shown on the plans and to the following requirements:

Paragraph 5.e. of Subsection 503.04 is void if a notched wedge joint is constructed between the adjacent traffic lanes.

This work shall consist of constructing a notched wedge longitudinal joint between adjacent passes of asphaltic concrete lifts over 1" on pavement that will be open to traffic and contains uneven lanes. The notched wedge joint shall consist of a vertical notch $\frac{1}{2}$ the thickness of the asphalt lift, and an 8" to 12" uniform taper extending into the adjoining lane (see plan typical).

Equipment

1. The notched wedge joint device shall be a manufactured strike-off device attached to the asphalt paver screed and able to produce the required shape and configuration after compaction, as detailed in the plan typical.
2. The device shall be self-adjusting, spring-loaded, and able to generate a smooth, uniform surface and slope without disrupting the smoothness of the paving mat.

3. The device shall be capable of applying vertical loads by pressure or ballasting methods.
4. The device may or may not have capability of vibration.

Construction Method

1. The notched wedge joint device shall be heated prior to the beginning of laydown either manually or as part of the notched wedge joint device.
2. The notched wedge joint shall be constructed in one pass of the paver. A constant head of asphaltic concrete shall be supplied in front of the notched wedge to provide pre-compaction of the notched wedge joint.
3. The taper of the notched wedge joint will be a minimum of 8” and a maximum of 12”.
4. The notched wedge joint shall be used at any longitudinal joint locations situated between two driving lanes. The Contractor also has the option to utilize the notched wedge joint at other longitudinal joint locations.
5. A tack coat shall be applied to the full face of the in-place notched wedge joint, prior to the placement of full lane tack coat application.

Method of Measurement

The construction of a notched wedge joint will not be measured and paid for but will be subsidiary to the associated asphaltic concrete.

MILLING FOR ASPHALTIC CONCRETE INLAY

Subsection 510 of the Standard Specifications is amended to include Milling for Asphaltic Concrete Inlays. The existing bituminous surfacing shall be milled as shown in the plans.

The remaining salvaged bituminous material produced from the cols milling operation shall become the property of the Contractor and removed from the project.

Subsection 510.05 is amended to include the following:

5. Milling for Asphaltic Concrete Inlays will be measured for payment by the each.

Amend Subsection 510.06 of the Standard Specifications to include the following:

Basis of Payment

1.	Pay Item	Pay Unit
	Milling for Asphaltic Concrete Inlay	Each

ASPHALTIC CONCRETE PLACEMENT

The 2 inch Asphaltic Concrete Type SLX overlay shall be placed in one 2 inch lift.

CONCRETE CONSTRUCTION (G-5-1015)

Section 704 in the Standard Specifications is amended to include the following:

All concrete rails on bridges and approach slabs shall be cast-in-place. Slip-forming will not be permitted for concrete rails on bridges and approach slabs.

Paragraph 8. of Subsection 704.03 is amended to provide that forms for 42 inch bridge rails shall be made of steel. Wood forms that are commercially manufactured to the specific shape of the 42 inch rail shall be permitted. Forms shall be capable of producing a uniform surface, texture and appearance equal to that obtained by using steel panels in good condition.

The fourth subparagraph of Paragraph 8.j. of Subsection 704.03 is void and superseded by the following:

Steel stay-in-place form material shall conform to the requirements of ASTM A 653/A 653M Coating Designation G165/Z500.

Paragraphs 8.a., b. and c. of Subsection 704.05 are void and superseded by the following:

8. Payment Deductions:
 - a. The 28-day compressive strength is determined by the average strength of all cylinders made on a specific day to determine the 28-day compressive strength of all of a group's class of concrete poured that day. Concrete with a 28-day compressive strength not meeting the design compressive strength is subject to removal.
 - b. If the 28-day compressive strength is less than the design compressive strength, cores may be taken, at the discretion of the Engineer, within 45 days after the concrete was poured. The average of the cores will be used to determine the compressive strength.
 - c. If either the 28-day compressive strength or the average core strength is less than the design strength and the Engineer determines that the concrete is acceptable for use, the concrete is subject to a payment deduction. The pay deduction is shown below:

$$\frac{2 \times (\text{Design Compressive Strength} - 28\text{-day Compressive Strength})}{\text{Design Compressive Strength}} = \text{Percent Reduction}$$

Or

$$\frac{2 \times (\text{Design Compressive Strength} - \text{Average Core Compressive Strength})}{\text{Design Compressive Strength}} = \text{Percent Reduction}$$

**CONCRETE BRIDGE FLOORS
(10-DAY WET CURE)
(G-5-0916)**

The following Special Provision applies to concrete decks and approaches on girder and slab bridges for new bridges and complete deck replacements. Bridge deck widenings, partial deck replacements, and deck and joint repairs shall be cured in accordance with Section 706 of the specifications. Approaches that are not part of a new bridge or complete deck replacement shall be cured in accordance with Section 706 of the specifications.

Paragraph 8.i of Subsection 704.03 in the Standard Specifications is amended to include the following:

- 8.i.(4) Reinforcing steel and form work for bridge curbs and bridge rails shall not be placed until after the 10-day wet curing.

Paragraph 14 of Subsection 704.03 in the Standard Specifications is void and superseded by the following:

- 14. Bridge Deck Curing in Cold Weather
 - a. The following requirements shall govern the placement of bridge deck concrete when the temperature will be less than 40°F during the 10-day wet curing period.
 - (1) The temperature of the concrete shall not be less than 50°F immediately after being placed.
 - (2) The Contractor shall furnish heating equipment and/or enclose and protect the structure in such a way that the concrete shall be maintained at a temperature between 50°F and 100°F for the first 72 hours after the concrete has been placed, and at a temperature of between 40°F and 100°F for the next 168 hours.
 - (3) After 240 hours of curing is complete, the concrete temperature shall not decrease at a rate faster than 5°F/hour.
 - b. The Contractor shall assume all risk connected with the placing of concrete during freezing weather, and permission given by the Engineer to place concrete during such time will not relieve the Contractor of the responsibility for satisfactory results. Any concrete showing damage from freezing shall be rejected.

Paragraph 5 of Subsection 706.03 in the Standard Specifications is void and superseded by the following:

- 5. No work shall be performed on the bridge deck, including forming and placing reinforcement for concrete curbs or railing until the concrete deck has cured for 10 days. Only equipment necessary for forming and pouring the bridge rail shall be allowed on the deck during the 7 days of white pigment curing.

Paragraphs 8, 9, and 10 of Subsection 706.03 in the Standard Specifications are void and superseded by the following:

8. a. Finishing

- (1) Immediately following the finishing machine, the Contractor shall give the bridge floor surface a drag finish with wet burlap, carpet or a soft bristled broom. The drag finish shall create a uniform, fine-grained finish on the sealed concrete surface.

b. Grooving

- (1) Transverse tining in plastic concrete of bridge decks (and approaches on new bridges and bridge deck replacements) will not be allowed unless otherwise stated in the contract documents.
- (2) The Contractor shall cut longitudinal grooves into hardened concrete surfaces using a mechanical cutting device. The Contractor shall perform longitudinal grooving after surface correction grinding.
- (3) The longitudinal grooves shall be:
 - (i) 1/8 inch \pm 1/64 inch wide,
 - (ii) 1/8 inch to 1/4 inch (3 mm to 6 mm) deep, and
 - (iii) Uniformly spaced at 3/4 inch intervals measured center to center of groove.
- (4) Longitudinal grooving shall include both bridge and paving approaches. Grooving shall terminate approximately 6 inches (150 mm) from bridge expansion joints.
- (5) Longitudinal grooving on the bridge deck and approach sections shall be discontinued 3 feet from the bridge curb, rail, raised medians, or barriers unless otherwise indicated on the plans.
- (6) For phased bridge and bridge approach construction:
 - (i) The Contractor may cut longitudinal grooves in the hardened concrete at the end of each phase of construction or wait until all phases have been completed. If the Contractor elects to delay cutting of the longitudinal grooves until completion of all phases, apply an interim broom finish on the concrete deck and bridge approach during placement for all phases opened to traffic.
 - (ii) The Contractor shall finish all longitudinal grooving for all phases within 30 calendar days following completion of the last phase of the bridge.
 - (iii) The interim broom finish will not be allowed as a surface texture when opened to traffic over a winter season. If the interim broom

texture is present and the Contractor is not in a position to finish all phases of the bridge, the Contractor shall cut longitudinal grooving into the hardened concrete in order to establish an acceptable driving surface texture for the winter season.

- (7) Grooves shall be constructed using multi-blade saw cutting equipment, fitted with diamond-tipped circular saw blades.

Before grooving operations, two approved gauges to verify groove depth shall be supplied. The gauges shall be accompanied by the manufacturer's instructions for their use.

During grooving operations, the groove dimensions will be checked at random. If the minimum groove depth has not been achieved, grooving operations shall stop and the necessary adjustments shall be made.

- (8) Sidewalks and top of curbs shall not be grooved and shall receive a final finish with a fine – bristle broom.

9. Curing

- a. For this Specification, the bridge deck is defined as the concrete deck and pavement cast between the bridge grade beams. Approaches outside the grade beams are excluded.

- b. The Contractor shall cure the concrete deck with wet burlap for at least 240 hours. Burlap with Polyethylene backing will not be allowed on decks unless allowed by the Engineer.

- (1) The Contractor shall place uniformly saturated wet burlap on the concrete no later than 20 minutes after the finishing machine passes.
- (2) The burlap shall be thoroughly wetted prior to placing it on the concrete. The burlap shall be kept continuously wet by means of a sprinkling or wetting system for the 10 days.
- (3) The wet burlap shall be secured or weighed down so that it remains in contact with the concrete surface.
- (4) After 96 hours, the Contractor may place white opaque polyethylene film over the wet burlap to reduce the amount of water needed.

- c. After the 10 day wet cure, the Contractor shall apply an approved white pigment curing compound within 45 minutes of removing the wet burlap.

- (1) The total rate of combined applications shall be a minimum of 1 Gal/150 SF of surface area.
- (2) The Contractor shall cure the deck with the white pigment curing membrane for an additional 7 days. The Contractor may work on

the bridge concrete rail during the 7 days provided caution is used to limit damage to the membrane.

- (3) Curing compound shall not be applied to construction joints or reinforcing steel.
 - d. The Contractor must provide a list of equipment, equipment certification, and the number of personnel that will be dedicated to the curing operation at least 24 hours before the actual casting date.
 - e. The Contractor shall be responsible for the repair of all visible cracks more than 3 inches (75 mm) in length that develop on the bridge deck up to the time the project is accepted at no additional cost to the Department.
 - f. Cracks shall be repaired with an approved bridge deck crack sealant (methacrylate). Crack sealants shall be installed in accordance with the manufacturer's recommendations.
 - g. Concrete Bridge curbs and rails shall be cured in accordance with Subsection 704.03.
10. Grinding
- a. The grinding and grooving shall not be done until after the 17 days of curing is complete.
 - b. Bridge decks shall be ground for smoothness in accordance with Section 733.
- (1) For bridge decks and approaches that are not covered by Section 733:
 - i. The Contractor shall test the cured concrete for surface irregularities with either a 10 foot straightedge placed or operated parallel to the centerline of the roadway or some other device for measuring deviations from a plane. Variations greater than 1/8th inch shall be plainly marked for removal, except that for decks which are to receive a subsequent overlay course greater than 1 inch thick, where ¼ inch variations are allowed.
 - ii. The Contractor shall grind or cut irregularities that exceed the above limits. Bush hammering or other impact methods are not allowed.

Paragraph 15 of Subsection 706.03 in the Standard Specifications is void and superseded by the following:

- 15. Time for Opening Bridge Floor to Traffic
 - a. The Contractor shall not open the bridge floor to traffic until approval has been given by the Engineer. The Engineer may open the bridge when

the concrete has reached a minimum age of 17 days and has developed a compressive strength of at least 3500 psi.

- b. Construction equipment will not be allowed on the deck until after the 10 day wet curing period. Vehicles needed for construction activities and weighing less than 4.0 kips, and comparable materials and equipment loads, shall be allowed on any span only after the last placed deck concrete has attained a compressive strength of at least 2.4 ksi. Loads in excess of the above shall not be carried on bridge decks until the deck concrete has reached 80% of the minimum compressive strength prescribed elsewhere in these Special Provisions and after the 10 days wet curing period.

Paragraph 1 of Subsection 706.05 in the Standard Specifications is amended to include the following:

1.	Pay Item Bridge Deck Grooving	Pay Unit Square Yards (SY)
----	---	--------------------------------------

**BRIDGE DECK REPAIR AND BRIDGE APPROACH REPAIR
(G-34-0616)**

Bridge deck repair and bridge approach repair are treated similarly in this provision, except where a distinction is made.

**CONCRETE BRIDGE DECK/APPROACH REPAIR
WITH CLASS 47BD 4000 CONCRETE**

Description

- 1. The work shall include removing unsound concrete, disposing of the old concrete, preparation of the repair area, and furnishing, placing, finishing, and curing the concrete for repairs to bridge decks and/or approaches.

Material Requirements

- 1. Materials shall conform to the requirements in Table A.

Table A

Material Requirements	
Applicable Materials	Section
Portland Cement Concrete	1002
Curing Materials	1010, 1011
Water for Concrete	1005
Adhesive	1018
Joint Sealing Filler	1014

- 2. The 47BD concrete may use Class F coarse aggregate shown in Table 1033.03A

Equipment

1. Surface preparation equipment shall be of the following types:
 - a. Concrete saws capable of sawing to a specified depth.
 - b. Sandblasting equipment able to remove rust and concrete from exposed reinforcing bars. The equipment shall also be able to remove loose and fractured particles from the prepared concrete surface.
 - c. Power-driven hand tools will be allowed with the following restrictions:
 - (1) Jackhammers greater than the nominal 60 lb (27 kg) class shall not be used.
 - (2) Jackhammers or chipping tools shall not be operated at an angle greater than 45 degrees measured from the deck surface.
 - (3) Chipping hammers greater than the 30 lb (13.5 kg) class shall not be used to remove concrete from around reinforcing bars.
2. Vibrating screeds, either mechanical or hand operated shall be used to finish the concrete.

Construction Methods

1. General Requirements:
 - a. No loads other than construction equipment shall be allowed on any portion of the concrete bridge deck or approach which has undergone preparation and removal of the old concrete surface. No construction load will be allowed which exceeds either an 8,000 lb (3625 kg) wheel load or a 16,000 lb (7250 kg) axle load. Any combination of axles closer than 4 feet (1.2 m) center-to-center will be considered to be one axle.
 - b. The Contractor shall take all necessary precautions to prevent damage to persons or property beneath the structure.
2. Concrete Removal Requirements:
 - a. All unsound concrete shall be removed from the concrete bridge deck or approach. When no overlay is indicated on the plan, the Contractor shall use a diamond blade to cut around the perimeter of the repair area to a depth of one inch. All repairs shall be cut so the edges are either parallel or perpendicular to the traveled way. When an overlay is indicated on the plan, saw-cutting is not necessary and edges shall be left irregular.
 - b. The Contractor shall remove, scarify or chip the concrete deck or approach to a minimum depth of two inches in any area requiring repair until all unsound concrete is removed. Where scarifying equipment cannot be used, hand chipping will be required.

- (1) Care shall be exercised to prevent cutting or otherwise damaging any exposed reinforcing bars. Repairs to damaged reinforcing steel shall be performed by the Contractor as directed by the Engineer at no expense to the Department. Additional concrete removal and replacement necessary to repair damaged reinforcing steel shall be at no expense to the Department.
- (2) Any damaged epoxy coating of existing reinforcing steel shall be repaired according to Subsection 1021.03.

c. Defective concrete shall be removed in the following manner:

- (1) Where machine scarifying is employed to remove concrete, extreme care shall be used to avoid cutting reinforcing bars. Any damage caused by the Contractor shall be repaired by the Contractor as directed by the Engineer at no additional cost to the Department.
- (2) When existing reinforcing steel is encountered that is broken or has a section loss greater than 20%, the Contractor shall lap splice the existing bar with a bar of matching size. Lap splices shall be as given in the following table:

Bar #	Non-epoxy Length (in.)	Epoxy Length (in.)
4	15	18
5	20	24
6	26	31
7	33	39
8	45	54
9	59	71
10	74	89
11	95	139

The bar used to splice, shall lap, by the length given above, with a portion of the existing bar of which 80% or more of the full section is present, on either side of a break or deteriorated or damaged segment.

- (3) At points where removal of unsound concrete is adjacent to reinforcing bars or the removal of unsound concrete leaves over 2/3 of the bar diameter exposed, the removal shall be continued so that at least 3/4 inch clearance surrounds the bar allowing new concrete to bond to the entire periphery of the exposed bar.
- (4) Wherever removal of unsound concrete extends to the top of the bottom layer of steel, the remaining thickness shall be removed to the full depth of the bridge deck or approach.
- (5) When concrete removal goes lower than three inches from the bottom of the bridge deck or approach, the remaining concrete, in that location, shall be removed to full depth.

- (6) Any removals shall be carefully done to prevent damage to the bottom of the deck or approach and to leave removal boundaries which will allow complete filling with plastic concrete.

3. Preparation of the Surface:

- a. All debris and rubble resulting from bridge deck or approach removal shall be thoroughly swept up and disposed of. The Contractor shall sandblast all exposed reinforcing bars, all prepared concrete surfaces, and the portion of the bridge curb and all surfaces of steel roadway joints that will be in contact with the concrete. The remaining concrete surface and reinforcing bars shall be cleaned with compressed air, vacuum, brushes or other methods as necessary to produce a surface free of particles, dust, liquids or other contaminants.
- b. In cases where the placement of the concrete is delayed beyond 24 hours after the sandblasting has been completed, the formation of incidental rust on the rebars due to humidity or rain shall not be cause for re-sandblasting.

4. Forming:

- a. Forms shall be provided in areas where the removal goes through the entire depth of the bridge deck. Forms for small areas (1 square yard or less) may be wired to the reinforcing bars for support. Forms for larger areas shall be supported by blocking from the beams.
- b. Forms shall be provided as required to re-establish edges of approaches that have been removed. Voids discovered under approaches shall be filled with flowable fill concrete.

5. Placing Concrete:

- a. The Engineer shall inspect and be satisfied that all removal and preparation has been done in compliance with this provision.
- b. The clean dry vertical and horizontal faces of the repair shall be coated with Grade 2 Epoxy Adhesive from the NDR Approved Products List just before placing the new concrete.
 - (1) The epoxy adhesive shall be applied to the vertical sides of the repair with a brush.
 - (2) The epoxy application rate shall be limited so the epoxy adhesive does not become dry before it is covered with the new concrete.
- c. The Contractor shall furnish and place Class 47BD 4000 psi concrete for the deck or approach repair. The concrete shall be handled and consolidated so there will be no separation of the aggregate and the mortar.
- d. An internal vibrator shall be used to consolidate the concrete. Excessive vibration shall be avoided.

- e. A vibrating screed shall be used on repairs 5 feet or wider to finish the concrete to the final elevation.
 - f. The surface shall be floated with a magnesium bull float. The surface shall be hand tined parallel to the existing tining in the deck or approach. If the deck or approach is to be overlaid prior to opening to traffic, no tining is required.
6. Sealing Joints:
- a. All transverse and longitudinal joints surrounding the repair shall be sealed and the work considered subsidiary to the pay item "Bridge Deck Repair" or "Bridge Approach Repair".
 - b. Sealing is not required if the repairs will be overlaid with asphalt or concrete.
7. Curing:
- a. The Contractor shall apply curing compound to all concrete deck or approach repairs.
 - b. The application rate shall be 1 Gal/200 SF
8. Smoothness:
- a. The elevation of deck or approach repairs shall be corrected in a manner that eliminates swales or bumps. Swales and bumps are defined as having 1/8 inch or greater deviation using an approved 10 foot straightedge. Corrective actions shall be completed by diamond grinding or replacement. The condition of the adjacent pavement shall be considered when evaluating the 1/8 inch deviation requirement.

Method of Measurement

- 1. "Concrete Bridge Deck Repair" shall be measured for payment by the square yard of deck repaired, as determined by field measurements.
- 2. "Bridge Approach Repair" shall be measured for payment by the square yard of approach repaired, as determined by field measurements.

Basis of Payment

- | | Pay Item | Pay Unit |
|----|---|------------------|
| 1. | Concrete Bridge Deck Repair | Square Yard (SY) |
| 2. | Bridge Approach Repair | Square Yard (SY) |
| 3. | Areas of repair that, at the direction of the Engineer, extend through the full thickness of the deck or approach shall be measured and paid for at an additional 1.5x the price for "Concrete Bridge Deck Repair" or "Bridge Approach Repair". | |
| 4. | Payment for above pay items shall be full compensation for the completion of the work and for providing all materiel described in the contract documents. | |

**PREFORMED WATERPROOFING MEMBRANE TYPE 1
(G-44-1216)**

000.01 -- Description of Work

1. This work shall consist of preparation of the deck or approach surfaces, providing and installing a roll type waterproofing membrane. A required degree of smoothness is specified. This smoothness is to be attained by finishing new concrete or removing rough surfaces of some existing concrete. Roughness removal work shall be subsidiary to the Pay Item, "Prefomed Waterproofing Membrane, Type 1". Bridges with subsidiary roughness removal work have been pre-inspected by NDOR and found to require roughness removal on less than 15% of the area to be covered by Waterproofing Membrane.

000.02 -- Material Requirements

1. The Prefomed Waterproofing Membrane shall be a preformed composite material composed of rubberized or modified-bitumen asphalt and heat resistant fabric reinforcement.
 - a. The waterproofing membrane shall meet physical requirements as specified in Table 1.
2. The Wick Drain shall be a composite material and shall meet the requirements specified in Table 2.

**Table 1
Physical Requirements of Prefomed Waterproofing Membrane**

Property	Test Method	Rubberized Asphalt Type	Modified Bitumen Type
Minimum Total Thickness of membrane (mils)	ASTM D3767	65	70
Minimum Width (in)	not stated	36.00	36.00
Minimum Tensile Strength (lb/in)	ASTM D882-12	50	40
Minimum Percent Elongation at break (%)	ASTM D882	15	10
Minimum Softening Point, (°F)	ASTM D36	165	210
Pliability	ASTM D146	No cracks	No cracks

Table 2
Physical Requirements of Wick Drain

Fabric Properties	Value	Test Method
Material	Polypropylene	
Minimum Grab Tensile Strength (lb)	130	ASTM D-4632
Minimum Puncture Strength (lb)	41	ASTM D-4833
Minimum Trapezoidal Tear (lb)	60	ASTM D-4533
Minimum Elongation (%)	50	ASTM D-4632
EOS (AOS) (sieve size)	70	ASTM D-4751
Minimum Permittivity (1/sec)	0.8	ASTM D-4491
Minimum Flow Rate (gpm/sqft)	60	ASTM D-4491
Minimum UV Stability (%)	70	ASTM D-4355
Core Properties	Value	Test Method
Material	Polypropylene	
Minimum Tensile Strength (lb)	225	ASTM D-4595
Product Properties	Value	Test Method
Minimum Discharge Capacity (gpm)	1.6	ASTM D-4716
Roll width (in)	3 to 4.5	
Maximum total thickness (in)	0.5	

3. Products on the Approved Products List under “Preformed Waterproofing Membrane, Type 1” may be used without additional approval. Other products meeting the requirements of Table 1 may be submitted to the Engineer for approval.
 - a. NDOR may verify the membrane thickness from random samples obtained from membrane delivered to the site prior to placement on the bridge.
4. Products on the Approved Products List under “Wick Drains for Asphalt Overlays on Bridges” may be used without additional approval. Other products meeting the requirements of Table 2 may be submitted to the Engineer for approval.
5. Primer for use with the rubberized asphalt membrane shall be a neoprene-based material, and the primer for use with the modified-bitumen asphalt membrane shall be resin-or-solvent-based material. Primers shall be of a type recommended by the Manufacturer.
6. The mastic for use with rubberized asphalt membrane shall be rubberized asphalt cold-applied joint sealant. The mastic for use with modified-bitumen asphalt membrane shall be a blend of bituminous and synthetic resins.
7. A Materials Certification Letter shall be submitted by the Wick Drain Manufacturer to the Engineer before product delivery.
8. Manufacturer’s installation instructions for waterproofing membrane shall be provided to the Engineer in advance of any work on the bridge.

000.03 -- Construction Methods

1. Storage

- a. All materials shall be shipped and stored in a dry shaded area between 35°F to 90°F and according to the manufacturer's recommendations.

2. Preparation of the Surface to be covered by Waterproofing Membrane

- a. Newly placed concrete shall be drag finished with wet burlap. The burlap finish shall create a uniform, fine-grained finish on the sealed concrete surface. No tining, grooving, brooming, or other texturing shall be used. Burlap finish may be omitted on newly placed concrete that will not be exposed to traffic.
- b. New concrete to be covered by waterproofing membrane shall be cured with saturated wet burlap for 72 hours or a tack coat or bituminous based compound approved by the Engineer. White-pigmented curing compound shall not be allowed on surfaces to be covered by waterproofing membrane.
- c. Portland cement concrete to be covered by waterproofing membrane shall cure for a minimum of 12 days before applying the waterproofing membrane.
- d. The Engineer shall be contacted for guidance if ponding of water is observed on the concrete bridge deck before membrane is placed.
- e. Smoothness Requirement:

The surfaces to be covered by Preformed Waterproofing Membrane shall have a concrete surface profile (CSP) of 6 or smoother as per the International Concrete Repair Institute (ICRI) and no protrusions or irregularities shall exceed an amplitude of 3/16 inch within a lateral distance of 1 inch. Tining deeper than 1/8-inch shall not be accepted. No more than 1/4 inch of bridge concrete may be removed. Concrete surfaces that do not meet the above smoothness requirement shall be prepared to receive the membrane by mechanical methods approved by the Engineer. Concrete roughness removal in excess of 15% of the area to be covered by Waterproofing Membrane shall be paid for as "Extra Work". Decks that were originally constructed to a parabolic cross slope may require the use of smaller equipment to avoid excessive concrete removal near the centerline of the bridge. Use of a leveling course is not allowed except as shown in the plans.

- f. All honeycombed areas and surface cavities and cracks wider than 1/16" shall be cleaned and filled with approved patching materials. Instead of patching, surface cavities may be ground to form a smooth transition across the deck surface if approved by the Engineer.

3. Cleaning of the Surface to be covered by Waterproofing Membrane

- a. Surfaces shall be free of sand, clay, dust, salt deposits, bituminous or asphaltic residue, grease, oil, pavement markings and other deleterious materials before application of primer or adhesive. Tack coats or bituminous curing compounds shall be allowed to remain in place.

- (1) Any portion of the deck surface not corrected for smoothness per paragraph 2.e., including 3 inches up the curb face shall be thoroughly cleaned by abrasive blasting, and then blown clean with compressed air which is free of oil and water immediately before application of the primer or adhesive.
 - b. From the time the bridge deck is cleaned for the primer or adhesive coat until the placement of the asphaltic concrete overlay, the only traffic permitted on the area being treated shall be the necessary workers and equipment to perform the work required.
- 4. Weather and Moisture Conditions
 - a. Neither the Membrane, nor Primer or Adhesive shall be applied in wet weather or at ambient or surface temperatures of 32 °F or below. Special attention shall be given to assure that there is no moisture present at the interface between the membrane and deck and bridge curb. Membrane application shall occur only when the weather and atmospheric conditions are favorable for a drying period of at least four hours after completion of the application.
 - (1) The Contractor shall verify that surfaces to which primer or adhesive will be applied are sufficiently dry by the following method. No condensation shall be found by taping an 18 inch by 18 inch plastic sheet tightly to the surface of the concrete per ASTM D4263. The plastic sheet test shall be performed only when surface temperatures and ambient conditions are within the established parameters for application of the overlay system. In the event of rain, the concrete shall be allowed to air dry for a minimum of 24 hours before performing the plastic sheet test. This test shall be performed by the Contractor and observed by the Engineer. The Department will allow a 1 hour test duration instead of the 16 hours specified in ASTM D4263.
 - b. Membrane shall not be applied if weather will not permit placement of the asphaltic concrete overlay on top of the membrane before rain.
- 5. Priming of the Surface to be covered by Waterproofing Membrane
 - a. Areas of the deck that will later be covered by expansion devices other than Asphalt Plug Joints may be masked prior to application of the primer or adhesive to facilitate membrane removal.
 - b. Use of an asphalt leveling course is not allowed.
 - c. Primer or adhesive shall be spray applied or applied with a squeegee or deep nap roller that is resistant to breakdown.
 - d. Allow primer or adhesive to dry until tack free. Treated areas shall be covered by membrane within 8 hours or as specified by the product manufacturer.
 - e. Care shall be taken to avoid defacing adjacent surfaces with primer, adhesive or other materials.

- f. Primer or adhesive shall be used on concrete or existing asphalt surfaces at the rate specified by the manufacturer.

6. Membrane Placement

- a. A 1/2 to 3/4 inch (13 to 20 mm) fillet of mastic shall be placed between any vertical face and the bridge deck or approach surface before placement of the membrane to prevent a void area where the membrane turns up the vertical face.
- b. An extra 9 to 12 inch (225 to 305 mm) wide strip of preformed membrane shall be placed before the normal membrane coverage at all joints, areas around drains, all membrane junctions with curbs, end dams, protrusions, construction joints, cracks greater than .10 inch (2.5 mm), and at all inside corners.
- c. Membrane shall be applied from low point to high point in both longitudinal and transverse directions and overlapped in shingle fashion.
- d. Overlap and seal all seams and edges in accordance with product manufacturer's specification.
- e. Stagger adjacent end-of-roll overlaps by a minimum of 6 feet.
- f. All membrane rolls shall be placed manually and not by means of a tractor or automated fabric placer. Hand carts are allowed.
- g. The membrane shall be installed straight and wrinkle free with no curled or uplifted edges.
- h. Once placed, the membrane should be immediately hand rolled onto the surface to assure positive adhesion.
- i. The lips of drain openings and edges of open joints, deck slab, and other openings at deck level shall be completely sealed by extending the full waterproofing membrane over the lip or edge.
- j. Edge of membrane shall extend up the face of closed bridge rail and curbs to 1/2 inch below the height of the overlay surface. Mastic shall be tooled to extend upward along the base of closed bridge rail or curb to a height 1/2 inch higher than the final overlay surface. At open rails terminate membrane at face of rail. Seal all flat seams and outside edge terminations of the membrane with mastic.
- k. Any tears shall be patched with additional membrane, and edges of patches sealed with mastic. Before the overlay, all membrane repairs shall be inspected before covering.
- l. Wick Drains shall be placed at the face of low-side curbs extending longitudinally to terminate at deck drains or ends of closed bridge rail. Wick drains shall be placed as shown on the plans on a thin layer of tacky mastic on top of waterproofing membrane.

7. Asphalt Overlay
 - a. Only rubber tired or rubber-tracked paving equipment shall be driven on the membrane.
 - b. Asphaltic concrete overlay shall be placed within 3 days of waterproofing membrane application.
 - c. A minimum of 2 inches compacted overlay thickness is required.
 - d. The temperature of the asphaltic concrete during placement shall be between 265 and 300°F.
 - e. The use of a pickup machine and the dumping of asphaltic concrete directly on the membrane are not allowed unless a placement program is submitted for approval by the Engineer that minimizes heating of the membrane prior to spreading.
 - f. Rollers shall be operated in static mode unless permitted by the Engineer.
 - g. A vibratory plate compactor shall be on site and used in areas that cannot be roller-compacted such as near the face of bridge rails.
 - h. Tack coat shall be applied to the membrane surface to bond the asphaltic concrete to the membrane. The rate of application shall not be less than 0.1 gal/SY. Application rate will be verified during construction.

000.04 -- Method of Measurement

1. The unit of payment for the Preformed Waterproofing Membrane, Type 1 is the square Yard.
 - a. The area receiving the membrane system will not be measured directly, but will be plan dimension of the surface receiving the treatment.

000.05 -- Basis of Payment

	Pay Item	Pay Unit
1.	Preformed Waterproofing Membrane, Type 1	Square Yard (SY)
2.	Concrete roughness removal in excess of 15% of the area to be covered by Waterproofing Membrane shall be paid for as "Extra Work".	
3.	Payment is full compensation for all work prescribed in this Section.	

PERFORMANCE GRADED BINDER

The Performance Graded Binder to be used on this project shall be PG Binder 58V-34 for SLX supplied by a Certified Supplier.

**SECTION 1029 - PERFORMANCE GRADED BINDER
(J-6-0117)**

Section 503 in the Standard Specifications is amended to include Performance Graded Binders.

Subsection 1029.01 in the Standard Specifications is void and superseded by the following:

1029.01 -- Description

1. Performance Graded (PG) binder shall conform to the requirements of AASHTO M332 Table 1. PG binder shall also conform to the Department PG+ specifications (Table 1029.01) when classified as a modified binder.
 - a. The test of Direct Tension, AASHTO M332 Table 1, is omitted.
 - b. The test of $J_{nr\text{diff}}$, AASHTO M332 Table 1, is omitted.
2. The Performance Graded Binder shall be supplied by a supplier that is certified by the Department.
 - a. A supplier may request certification by contacting the Nebraska Department of Roads, Materials and Research Division, Flexible Pavement Engineer.
 - b. A certified supplier must furnish a quality control program to the Department Bituminous Laboratory for review and approval. The program shall follow, at a minimum, the guidelines of AASHTO R26 with references to AASHTO M320 to include AASHTO M332.
 - c. A certified supplier must be a participant in one or more of the following PG Binder Groups:
 - (1) AASHTO Materials Reference Laboratory (AMRL)
 - (2) Western Cooperative Testing Group (WCTG)
 - (3) Combined States Binder Group (CSBG)
 - (4) A PG Binder round robin Group approved by the Department.
 - d. A certified supplier must maintain, meet and follow the requirements of the group or groups in which they participate, to maintain certification by the Department. In addition, active participation is required to maintain certification by the Department. Active participation will include submitting of round robin sample results.
 - (1) For suppliers that desire to provide product while approved PG Binder Group membership is pending, a temporary certification may be issued for a period of up to one year. Split sample testing will be required prior to receiving a temporary certification. Split sample testing will be done on all grades of binder that the supplier intends to supply during the temporary certification period. The supplier will have up to one year to

become certified by participating in and following the requirements of one or more of the approved PG Binder Groups, and to meet all other conditions for certification.

- e. A certified supplier may be asked to supply to the Department: past round robin results, laboratory inspection reports, reasons for and investigative reports on outlying results, quality control testing results, technician training and/or proficiency testing reports.
- f. A certified supplier will agree to inspection of their plant or terminal without notice anytime during production or supplying of material to the Department. The inspection may also include the supplier's laboratory.
- g. If desired, a certified supplier can voluntarily submit samples of PG binder proposed for use to the Materials and Research Bituminous Laboratory for courtesy testing prior to Asphalt production. The test results will be for Information-Only.
- h. Certification will be withdrawn from a supplier when one or more of the following conditions exist:
 - (1) Inability to consistently supply material meeting specifications as outlined herein.
 - (2) Failure to maintain an acceptable quality control program.
 - (3) The failure to meet one or more of the conditions of being a certified supplier as outlined, but not limited to only these conditions.
- i. Notification of decertification of a supplier will be submitted in writing by the Department. The notification will include the reason(s) why decertification occurred. PG Binders from a decertified source will not be accepted for use on Department projects.
- j. If a supplier has lost certification and seeks to be recertified, the following steps are required:
 - (1) Supplier shall fulfill the requirements outlined above for gaining Certified Supplier status. This may include the submittal of material samples to ensure specifications compliance before recertification approval.
 - (2) Supplier shall submit documentation to the Flexible Pavement Engineer explaining the cause(s) of decertification outlined in the notification, and the actions that are being taken to correct the problem(s) identified by the Department.

Subsection 1029.02 in the Standard Specifications is void and superseded by the following:

1029.02 -- Material Characteristics

1. Modified Performance Grade binders shall meet the following specifications:
 - a. All specified binders with a grade temperature spread of 92°C or greater, shall be defined as modified.
 - b. The PG Binder shall meet the Multiple Stress Creep Recovery (MSCR) specifications of the following Table:

**Table 1029.01
PG+ Specifications**

AASHTO T350 MSCR Average % Recovery @ 3.2 kPa for modified PG binders	
AASHTO M332 Performance Grade	Test Temperature of 58°C
58S - 34	---
58H - 34	30 Min.
58V - 34	55 Min.
58E - 34	75 Min.

- c. The binder shall incorporate a blend of base asphalt and the use of the elastomer modifiers styrene-butadiene (SB), styrene-butadiene-styrene (SBS), or styrene-butadiene-rubber (SBR).
 - (1) Polyphosphoric Acid (PPA) may be used as an additional modifier to elastomer modifiers and shall not exceed 0.50% maximum PPA addition (by weight of binder). The total phosphorous content of the PPA-modified PG Binder shall not exceed 1900 ppm. The total phosphorous content shall be determined as per ASTM D1091, ASTM D6443, or ASTM D6481.
 - (i) To determine specifications compliance, the Department requires a sample of the base asphalt binder, a sample of the PPA, and supplier-prepared varying PPA percentage modified binder samples. These samples shall be sent to the NDR Bituminous Laboratory prior to project Asphalt production.
 - (2) Crumb rubber may be used as an additional modifier to elastomer modifiers. If crumb rubber is used:
 - (i) Paragraph 5.4 (solubility) of AASHTO M332 is then void.
 - (ii) Paragraph 5.5 (micron requirement) of AASHTO M332 is then void.

- d. The composite material shall be thoroughly mixed at the asphalt refinery or terminal prior to (for tank storage) or as (in-line blending) being loaded into the transport vehicle.
 - (1) The modified binder shall be heat and storage stable and shall not separate when handled and stored as per the supplier's recommendations.
 - (2) The composite material shall be homogenous, and shall not demonstrate evidence of localized gelation or over-crosslinking of polymers. The composite material shall not otherwise contain any other non-homogenous conglomerations.
2. Unmodified Performance Grade Binders are defined as specified binders with a grade temperature spread of less than 92°C.

Subsection 1029.03 in the Standard Specifications is void and superseded by the following:

1029.03 -- Procedures

1. A Material Certification shall be submitted to the Engineer prior to construction or when switching suppliers, stating the type of any modifier(s) being used. The Material Certification must also state that the material has not been air blown or oxidized.
 - a. If the PG Grade modification process of the PG Binder includes the use of PPA (Polyphosphoric Acid) and/or crumb rubber, then the Material Certification must also state the type of all modifiers used in the formulation. If PPA is used, the Material Certification must state the % PPA in the binder, and also state and confirm the total phosphorous content of the PPA modified binder.
2. The Contractor shall receive from the supplier, instructions on the proper storage and handling of each grade and shipment of PG Binder.
3. Substitution of a PG Binder, which exceeds the upper and/or lower grade designations from what is specified, requires advance notification to, and approval by, the Engineer. The substitution of the PG Binder shall also be identified in the sample identification submittals.
4. PG Binder Lots and their respective samples are defined as follows:
 - a. Each 200 tons of liquid PG Binder grade incorporated into the production of Asphalt, or final portion thereof, will be a binder lot.
 - b. A binder lot will include only one PG Binder grade, or will include a blend of grades as defined in paragraph 5.

- c. A binder lot will include only one supplier of the PG Binder.
 - (1) If a Contractor needs to switch binder suppliers during the production of a binder lot, it is the Contractor's responsibility to ensure both the compatibility and the specifications compliance of the mixture of the respective binder products. The supplier designation of the lot will be listed as "mixed suppliers" if the binder lot sample was taken after this occurs.
 - d. The Engineer must be notified and approve of the intent to blend binder grades, or to switch binder suppliers, prior to either occurrence.
 - e. All binders shall be sampled at the rate of at least one sample per binder lot.
 - (1) The sample shall consist of a two-quart (half gallon) can and shall be taken by the Contractor's Certified Sampling Technician, with confirmation by Department personnel. The sample shall be taken at the plant from the line between the storage tank and the mixer, or from the tank supplying material to the line, at a location from which material sampled is representative of the material in the line to the mixer. The sampling process shall follow procedures of the NDR Materials Sampling Guide.
 - (2) When the tested PG Binder is in compliance, the binder lot will be accepted and the sample will be discarded. If the tested PG Binder does not comply, then the pay factor of the PG Binder lot represented by the sample shall be adjusted according to Table 1029.02, and Table 1029.03 (if modified).
 - (3) When a total PG Binder grade type on a project is less than 200 tons, a minimum of one PG Binder lot sample is required. If the PG Binder does not comply with test specifications, then the pay factor of the PG Binder lot shall be adjusted according to Table 1029.02, and Table 1029.03 (if modified).
5. Blending of differing PG Binder grades at the hot mix plant site will be allowed only with prior approval, and with the following restrictions:
- a. The resultant blend of grades will meet PG+ (if modified binder), and/or AASHTO M332 specifications when tested as $\pm 3^{\circ}$ C of the specified PG Binder grade.
 - b. The sample of the blended material will be considered as a lot sample, and it will be taken during initial production following the blending of the binders.
 - c. The lot sample of the blended material shall have a pay factor applied as per Table 1029.02, and Table 1029.03 (if modified), when not meeting specifications.
 - d. The blended sample's identification form shall note the blending conditions and provide a statement that the sample is a blend of grades.
 - e. The next lot sample, following the sample representing the blend, will be tested as the specified binder grade for the asphalt mixture being produced and shall meet AASHTO M332 and PG+ (if modified), specifications.

- f. For modified PG Binders, only blending of the same type of elastomer modifiers listed in 1029.02 Paragraph 1.c. will be allowed.
- 6. The Nebraska Department of Roads, Materials and Research Bituminous Laboratory, will do selective testing on each Binder Lot. When any test result shows a lot sample not meeting specifications, that lot sample and any adjacent previous, and any adjacent following lot sample received will be tested for complete specifications compliance. Adjacent lot sample testing will then continue in this manner until tested samples meet all specifications, or there are no more lot samples remaining to be tested.

7. All lot samples as tested are subject to the Pay Factors listed in Table 1029.02, and also Table 1029.03 if modified, below:

Table 1029.02
Tests of AASHTO M332 Pay Factor Table ¹

Test and Specification	Test Results	Pay Factor
Original Binder Dynamic Shear, $G^*/\sin \delta$, kPa Min. 1.00	> 0.99	1.00
	0.97 - 0.99	0.95
	0.94 - 0.96	0.90
	0.91 - 0.93	0.85
	< 0.91	0.70 or Reject
Rolling Thin Film Oven Residue, Standard Traffic "S", MSCR $J_{nr3.2}$ Max. 4.5 kPa ⁻¹	<4.6	1.00
	4.6	.95
	4.7	.90
	4.8	.85
	>4.8	.70 or Reject
Rolling Thin Film Oven Residue, Heavy Traffic "H", MSCR $J_{nr3.2}$ Max. 2.0 kPa ⁻¹	<2.1	1.00
	2.1	.95
	2.2	.90
	2.3	.85
	>2.3	.70 or Reject
Rolling Thin Film Oven Residue, Very Heavy Traffic "V", MSCR $J_{nr3.2}$ Max. 1.0 kPa ⁻¹	<1.1	1.00
	1.1	.95
	1.2	.90
	1.3	.85
	>1.3	.70 or Reject
Rolling Thin Film Oven Residue, Very Heavy Traffic "E", MSCR $J_{nr3.2}$ Max. 0.5 kPa ⁻¹	<0.6	1.00
	0.6	.95
	0.7	.90
	0.8	.85
	>0.8	.70 or Reject
Pressure Aging Vessel Residue Dynamic Shear, "S", $G^* \sin \delta$, kPa Max. 5000	< 5001	1.00
	5001 - 5200	0.95
	5201 - 5400	0.90
	5401 - 5600	0.85
	> 5600	0.70 or Reject
Pressure Aging Vessel Residue Dynamic Shear, "H", "V", "E", $G^* \sin \delta$, kPa Max. 6000	< 6001	1.00
	6001 – 6050	.95
	6051 – 6100	.90
	6101 – 6150	.85
	>6150	.70 or Reject

Test and Specification (cont'd)	Test Results	Pay Factor
Pressure Aging Vessel Residue BBR m-Value Min. 0.300	>0.350	1.05
	0.300 – 0.350	1.00
	0.295 – 0.299	0.95
	0.290 – 0.294	0.90
	0.285 – 0.289	0.85
	<0.285	0.70 or Reject
Pressure Aging Vessel Residue BBR Creep Stiffness, mPa Max. 300	< 200	1.05
	200 - 300	1.00
	301 - 310	0.95
	311 - 320	0.90
	321 - 330	0.85
	> 330	0.70 or Reject

**Table 1029.03
PG + Pay Factor Table ¹**

AASHTO T350 Multiple Stress Creep Recovery (MSCR) @ 58°C Test and Specifications	Test Results	Pay Factor
AASHTO M332 Performance Grade 58H-34 Average % Recovery @ 3.2 kPa Min. 30%	> 29	1.00
	29	0.95
	28	0.90
	27	0.85
	< 27	0.70 or Reject
AASHTO M332 Performance Grade 58V-34 Average % Recovery @ 3.2 kPa Min. 55%	> 54	1.00
	54	0.95
	53	0.90
	52	0.85
	< 52	0.70 or Reject
AASHTO M332 Performance Grade 58E-34 Average % Recovery @ 3.2 kPa Min. 75%	> 74	1.00
	74	0.95
	73	0.90
	72	0.85
	< 72	0.70 or Reject

¹ If a lot sample has more than one test that results in a reduced pay factor (less than 1.00) from either or both of the above Pay Factor Tables, the single largest pay factor reduction will be the one used in determining the lot pay factor. If a lot sample passes all testing (1.00 or greater), and one or more test pay factors are 1.05, the pay factor of 1.05 will be the one used in determining the lot pay factor.

8. When all lot samples have been received and tested, a final pay factor of all the PG Binder per Asphalt type will be calculated and applied as follows:

- a. The final pay factor is the average of all lot sample pay factors. The final pay factor cannot exceed 1.000.

Example Calculations:

4 Binder Lots Asphalt: $\frac{0.95 + 1.05 + 1.00 + 0.85}{4} = 0.962$ Final Pay Factor

3 Binder Lots Asphalt: $\frac{0.95 + 1.05 + 1.05}{3} = 1.017 =$ Final Pay Factor of 1.000

- b. The final pay factor will be applied to the contract unit price of asphalt binder.
- c. The Engineer will determine if lots that have a test pay factor of 0.70 or Reject will be removed. If 0.70 or Reject material is left in place, a price factor of 0.70 will be the determined lot pay factor. The final pay factor will be applied to the contract unit price of asphalt binder.
 - (1) Removal and replacement will be at no additional cost to the Department.
 - (2) If any lot was removed, a new lot pay factor will be determined by testing of the replacement material.

9. When the testing of a PG binder lot sample shows test results that are outside of specification limits, the initial process of resolving the sample failure will include the following actions, as appropriate:

- a. The Department Bituminous Laboratory may conduct retesting of the remaining portion of the sample as determined necessary to confirm the original test result(s).
- b. The Department Bituminous Laboratory will notify the Department project personnel, who will in turn notify the Contractor. All parties will arrange to investigate all aspects of the testing, loading, handling and delivery of the material in question. The Contractor and Department project personnel shall report their findings to the Bituminous Laboratory.
- c. The Department Bituminous Laboratory will collect and compile all information provided.
- d. The Department Bituminous Laboratory will issue a standard report of tests for all samples tested, to include any resulting final pay factor deductions or removals. A copy of the report of tests will be distributed to the District and the Construction Division. The District will then provide a copy to the Contractor. PG Binder Supplier requests for a copy of this report will be directed to the Contractor.

10. If the Contractor wishes to dispute any results after testing and investigations have been completed on any failing lot sample(s) that subjected the final pay factor from paragraph 8 to less than 1.000, the Department will select an independent laboratory for referee testing to take place on the remaining portion of the sample(s).
 - a. Only the Contractor can initiate dispute resolution, and request referee testing. The request must be made, in writing, to the Department Construction Division within 30 days of awareness of final pay factor determination. Otherwise dispute resolution is forfeited.
 - b. The identity of the independent laboratory will not be revealed until the selected laboratory has completed the referee testing, and the Department Bituminous Laboratory has submitted a final report of the results.
 - c. If the independent lab's tests indicate failing results and pay deductions equal to or greater than the Department's, the Contractor will reimburse the Department for the cost of testing. If the independent lab's tests indicate that the material meets specification, or is at a pay deduction less than the Department's, the Department will assume the cost of testing. When the independent lab's tests indicate a pay deduction, the lesser of the Department's and the independent lab's deductions will be applied.

Subsection 503.05 in the Standard Specifications is amended to include the following:

503.05 -- Method of Measurement

PG Binder shall be measured in accordance with Subsection 503.05, Paragraph 3, in the Standard Specifications. References to the term asphalt cement are superseded with the term PG Binder.

Subsection 503.06 in the Standard Specifications is amended to include the following:

503.06 -- Basis of Payment

Subsection 503.06 in the Standard Specifications is amended to provide that PG Binder, accepted by the Engineer for use in asphaltic concrete, will be paid for at the contract unit price per ton (Megagram) for the item "Performance Graded Binder _____", less any deductions as prescribed in the pay factor tables.

**SECTION 1028 - SUPERPAVE ASPHALTIC CONCRETE
(J-7-1116)**

Section 1028 in the Standard Specifications is void and superseded by the following:

1028.01 -- Description

1. a. Superpave Asphaltic Concrete is a Contractor-designed mix.
- b. The Contractor shall be required to define properties using a gyratory compactor that has met the Superpave evaluation test procedures, during mix design and production.
2. Job Mix Formula
 - a. Before production of asphaltic concrete, the Contractor shall submit, in writing, a tentative Job Mix Formula (JMF) on the NDOR Mix Design Submittal Form for verification to the Department.
 - b. The JMF shall be determined from a mix design for each mixture. A volumetric mixture design in accordance with AASHTO R 35 as modified within this specification will be required. However, the mixture for the Superpave specimens and maximum specific gravity mixture shall be aged for two hours at compaction temperature. The mixture shall be prepared using the following:
 - (1) Mixture Conditioning of Hot Mix Asphalt (HMA), AASHTO R 30.
 - (2) Method for Preparing and Determining the Density of Hot Mix Asphalt Specimens by Means of the SHRP Gyratory Compactor, AASHTO T 312.
 - c. The JMF shall identify:
 - (1) The virgin mineral aggregates and pit locations
 - (2) Recycled Asphalt Pavement (RAP) and source locations
 - (3) Hydrated lime
 - (4) Mineral filler
 - (5) The percent passing value for each specified sieve for the individual and blended materials
 - d. (1) The Contractor shall submit one uncoated, proportioned 22 lb. (10,000 gram) sample of the blended mineral aggregates for consensus properties and specific gravity testing, for all mix types except SPS. Once verified, the Contractor may begin plant production and QC testing with the QA/QC program.

- (2) The Contractor has the option of submitting the following; 2 proportioned 22 lb. (10,000 gram) samples of the blended mineral aggregates (which are precoated with hydrated lime, if lime is used) and two one-quart (liter) samples of the proposed PG Binder to be used in the mixture to the Department Materials and Research Central Laboratory at least 15 NDR working days before production of asphaltic concrete. If submitted these samples will be used to verify the Contractor's Superpave mix design test results and mix properties.
- (3) Submitted with these samples shall be a copy of the Contractor's results for all Superpave mix design tests.
- (4) Mix design shall include at a minimum:
 - (i) The bulk specific gravity (G_{sb}), which shall be 2.585, for data purposes and as information only, for all mixes.
 - (ii) The target binder content. The binder content will be determined by ignition oven results. A correction factor of 0.3% will be added to the ignition oven results for mixes containing hydrated lime, and an adjustment factor of 0.1% will be added to the ignition oven results for mixes containing WMA.
 - (iii) The supplier and grade of PG Binder.
 - (iv) The maximum specific gravity of the combined mixture (Rice).
 - (v) The bulk specific gravity (G_{mb}) and air voids at N initial (N_{ini}), N design (N_{des}) and N maximum (N_{max}) of the gyratory compacted specimens.
 - (vi) Voids in the Mineral Aggregate (VMA) and Voids Filled with Asphalt (VFA) at N_{des} .
 - (vii) Fine Aggregate Angularity (FAA) and specific gravity, Coarse Aggregate Angularity (CAA), Flat and Elongated Particles and Sand Equivalent of the aggregate blend.
 - (viii) Location description and/or legal descriptions and producers of materials used in the mix.
 - (ix) Dust to Binder Ratio.
 - (x) JMF compaction temperatures from NDOR Gyratory Temperature Table (See Table 1028.11).
 - (xi) The hydrated lime content.

3. Quality Control Program:
 - a. The Contractor shall establish, provide, and maintain an effective Quality Control (QC) Program. The QC Program shall detail the methods and procedures that will be taken to assure that all materials and completed construction conforms to all contract requirements.
 - b. Although guidelines are established and certain minimum requirements are specified herein and elsewhere in the contract, the Contractor shall assume full responsibility for placing a pavement course that meets the target field values.
 - c. The Contractor shall establish a necessary level of control that will:
 - (1) Adequately provide for the production of acceptable quality materials.
 - (2) Provide sufficient information to assure both the Contractor and the Engineer that the specification requirements can be met.
 - d.
 - (1) The Contractor shall develop and submit a copy of their QC Program to the Department. A copy of the QC Program shall be kept on file in the QC lab trailer. This Program shall be updated as needed and submitted annually for review.
 - (2) The Contractor shall not begin any construction or production of materials without an approved QC Program.
 - e. The QC Program shall address, as a minimum, the following items:
 - (1) QC organization chart.
 - (2) Inspection requirements.
 - (i) Equipment.
 - (ii) Asphalt concrete production.
 - (iii) Asphalt concrete placement.
 - (3) QC testing plan.
 - (4) Documentation of QC activities.
 - (5) Requirements for corrective action when QC or acceptance criteria are not met.
 - (6) Any additional elements deemed necessary.
 - (7) A list, with the name and manufacturers model number, for all test equipment used during laboratory testing.

- (8) A description of maintenance and calibration procedures, including the frequency that the procedures are performed.
- f. The QC organization chart shall consist of the following personnel:
- (1) A Program Administrator:
 - (i) The Program Administrator shall be a full-time employee of the Contractor or a Subcontractor (Consultant) hired by the Contractor.
 - (ii) The Program Administrator shall have a minimum of 5 years' experience in highway construction.
 - (iii) The Program Administrator need not be on the job site at all times but shall have full authority to institute any and all actions necessary for the successful implementation of the QC Program.
 - (iv) The Program Administrator's qualifications and training shall be described in the QC Program.
 - (2) Quality Control Technicians:
 - (i) The quality control technicians shall report directly to the Program Administrator and shall perform all sampling and quality control tests as required by the contract.
 - (ii) The QC technicians shall be certified every 5 years by the Department Materials and Research Division.
 - (iii) Certification at an equivalent level by a state or nationally recognized organization may be acceptable.
 - (iv) The QC technician's credentials and training records shall be submitted to the Department.
 - (v) The Contractor may have a non-certified technician working under the direct supervision of a certified technician for no more than one construction season.
- g. (1) Inspections shall be performed daily to ensure continuing compliance with contract requirements until completion of the work.
- (2) QC test results and periodic inspections shall be used to ensure the mix quality and to adjust and control mix proportioning.

4. Contractor's Lab Equipment:
- a. The Contractor shall calibrate and correlate the testing equipment according to the procedures prescribed for the individual tests and conduct tests in conformance with specified testing procedures.
 - b. The Contractor shall have the following equipment (or approved equal) at or near the project location:
 - (1) A gyratory compactor and molds meeting AASHTO criteria.
 - (2) An Asphalt Content Ignition Oven meeting AASHTO criteria.
 - (3) Rice equipment specified in AASHTO T 209, procedure 9.5.1, Weighing in Water. The thermometer being used to measure water temperature will be as specified in T 209.
 - (4) FAA equipment specified in AASHTO T 304.
 - (5) To test density of compacted asphaltic concrete, a minimum 6000 gm balance, 0.1 gm resolution, with under body connect and water container large enough to conveniently place specimen in the basket and completely submerge the basket and specimen without touching the sides or bottom is required.
 - (6) QC Laboratory which contain the following:
 - Air conditioner.
 - Dedicated phone.
 - FAX machine or email.
 - Photocopy machine.
 - Sample storage.
 - Work table.
 - Bulletin board.
 - Running water.
 - Desk and chair.
 - Separate power supply.
 - Incidental spoons, trowels, pans, pails.
 - (7) Diamond saw for cutting cores.
 - (8) Diamond core drill minimum 3 inch (75 mm).
 - (9) Oven, 347°F (175°C) minimum, sensitive plus 5°F (plus 2°C).
 - (10) USA Standard Series Sieves for coarse and fine aggregate with appropriate shakers [12 inch (300 mm) recommended].

- (11) Personal Computer capable of running the latest version of Department Superpave software, creating an electronic copy of the data, and printing to a Color Printer.

5. QC Testing Plan:

- a. The testing plan shall provide that the samples be collected in accordance with the Department statistically based procedure of random sampling.
- b. The Contractor may add any tests necessary to adequately control production.
- c. All QC test results shall be reported on the latest version of the Department's provided Superpave software by the Contractor with a copy provided to the Engineer within 1 week after the tests are complete. Daily review by the Engineer shall be allowed. At the completion of the asphalt production, the Contractor shall submit to the Department a final copy of the Superpave test results on electronic recording media (CD, e-mail, flash drive, etc.).
- d. Corrective Action Requirements:
 - (1) The Contractor shall establish and utilize QC charts for individual QC tests. The requirements for corrective action shall be linked to the control charts.
 - (2) The Contractor's QC Program shall detail how the results of QC inspections and tests will be used to determine the need for corrective action.
 - (3)
 - (i) A clear set of rules to determine when a process is out of control and the type of correction to be taken to regain process control will be provided.
 - (ii) As a minimum, the plan shall address the corrective actions that will be taken when measurements of the following items or conditions relating to the mixture approach the specification limits:
 - (I) Plant produced mix gradations at laydown (See gradation tolerances).
 - (II) Binder content.
 - (III) Air voids.
 - (IV) VMA (mix design only).
 - (V) VFA (mix design only).

- (VI) FAA AASHTO T 304.
CAA ASTM D 5821.
- (VII) Dust to Binder Ratio.
- (VIII) Density.
- (IX) Contaminates.
- (iii) Corrective actions that will be taken when the following conditions occur:
 - (I) Rutting.
 - (II) Segregation.
 - (III) Surface voids.
 - (IV) Tearing.
 - (V) Irregular surface.
 - (VI) Low Density.

1028.02 -- Material Characteristics

1. The type of PG Binder will be shown in the contract.
2. Recycled Asphalt Pavement:
 - a. The Contractor may submit to the State a proposal to supplement the virgin aggregates of the asphaltic concrete mix with a Contractor's specified percentage of Recycled Asphalt Pavement (RAP). The Contractor is responsible for investigating and maintaining the quality and verifying the quantity of the RAP material.
 - b. In recycled asphaltic concrete mixtures, the allowable percent of RAP will be as shown in Table 1028.01.

Table 1028.01

Asphaltic Concrete Type	Percent, RAP	
	Minimum	Maximum
SPS	0	65
SPR	0	55
SPH	0	35

3. Aggregates:
 - a. Aggregates for use in superpave asphaltic concrete shall be tested on an individual basis.

- b. With the exception of Asphaltic Concrete Type SPS the blended mineral aggregate shall not contain more than 80% limestone on the final surface lift of asphaltic concrete.
- c. Asphaltic Concrete Type SPR may contain a total maximum of 10% of the virgin material that is composed of natural, uncrushed aggregate by manmade methods commonly known as but not limited to: 47B gravel, 2A gravel, gravel surfacing, sluice sand, blow sand, waste sand, fill sand, road gravel, roofing gravel, hot mix sand or gravel, coarse sand, fine sand, plaster sand, masonry sand, pit run sand or gravel. For clarification on any proposed gravel, contact the Department Flexible Pavements Engineer.
- d. Chat or coal sand will not be allowed in any mix.
- e. Crushed rock material for use in asphaltic concrete, 1/4 inch (6.35 mm) and smaller, screenings and manufactured sand shall have a Sodium Sulfate loss of not more than 12% by mass at the end of 5 cycles. Sampling size and frequency shall adhere to the current Department Materials Sampling Guide.
- f. Quartzite and granite shall conform to the requirements of Subsection 1033.02, Paragraph 4, a.(8). Sampling size and frequency shall adhere to the current Department Materials Sampling Guide.
- g. Crushed rock (Limestone) and Dolomite shall conform to the requirements of Paragraph 4.a. (4), (5) and (6). of Subsection 1033.02 of the Standard Specifications. Sampling size and frequency shall adhere to the current Department Materials Sampling Guide.
- h. Soundness tests shall not be required for fine sand.
- i. Once the satisfactory quality of aggregates from a source has been established, sufficient additional soundness tests will be performed to insure the continued satisfactory quality of the material, as determined by the Materials Sampling Guide
- j. Aggregate consensus properties may be performed on material prior to the application of hydrated lime.

- k. The coarse aggregate angularity value of the blended aggregate material shall meet or exceed the minimum values for the appropriate asphaltic concrete type as shown in Table 1028.02. If the coarse portion of the blend is all ledge rock the CAA tests may be waived.

**Table 1028.02
Coarse Aggregate Angularity
(ASTM D 5821)**

Asphaltic Concrete Type	CAA (minimum)
SPS	--
SPR	83
SPH	95/90*

* Denotes two faced crushed requirements

- l. The fine aggregate angularity value of the blended aggregate material shall meet or exceed the minimum values for the appropriate asphaltic concrete type as shown in Table 1028.03.
- m. The specific gravity for calculation of the Fine Aggregate Angularity (FAA) shall be determined on a washed combined aggregate sample of the material passing the No. 8 (2.36 mm) sieve and retained on the No. 100 (150 µm) sieve. The Contractor will determine the specific gravity to be used in the calculation of FAA mixture design value(s) and, if verified by the Department Aggregate Laboratory, this same value can be used throughout production. The verification value determined by the Department Aggregate Laboratory will be on a combined aggregate sample supplied by the Contractor that is representative of the material proposed or being used during production. The specific gravity to be used throughout production to calculate FAA values will be the Contractor's verified value or the Department determined value (whenever verification is not made) and will be noted on the Mix Design. Changes in aggregate percentages during production may require determination of a revised specific gravity for FAA.

**Table 1028.03
Fine Aggregate Angularity
(AASHTO T304 Method A)**

Asphaltic Concrete Type	FAA (minimum)
SPS	--
SPR	43.0
SPH	45.0

- n. The coarse aggregate shall not contain flat and elongated particles exceeding the maximum value for the appropriate asphaltic concrete type category shown in these provisions according to Table 1028.04.

**Table 1028.04
Flat and Elongated Particles*
(ASTM D 4791)**

Asphaltic Concrete Type	Percent, Maximum
SPS	25
SPR	10
SPH	10

*Criterion based on a 5:1 maximum to minimum ratio.

- o. The sand equivalent of the blended aggregate material from the fine and coarse aggregates shall meet or exceed the minimum values for the appropriate asphaltic concrete type shown in these provisions according to Table 1028.05.

**Table 1028.05
Sand Equivalent Criteria
(AASHTO T 176)**

Asphaltic Concrete Type	Sand Equivalent, Minimum
SPS	30
SPR	45
SPH	45

- p. Dust to binder ratio is the ratio of the percentage by weight of aggregate finer than the No. 200 (75 μ m) sieve to the asphalt content expressed as a percent by weight of total mix. The dust to binder ratio shall be within 0.70 and 1.70.
- q. The blended aggregate shall conform to the gradation requirements specified in Table 1028.06 and Table 1028.07 for the appropriate nominal size.

Table 1028.06
Gradation Control Points for 0.75 Inch (19 mm) and 0.5 Inch (12.5 mm) Nominal Size

English Sieve (Metric)	0.75 Inch (19 mm) Control Points (percent passing)		0.5 Inch (12.5 mm) Control Points (percent passing)	
	Minimum	Maximum	Minimum	Maximum
1 inch (25 mm)	100.0			
3/4 inch (19 mm)	90.0	100.0	100.0	
1/2 inch (12.5 mm)		90.0	90.0	100.0
3/8 inch (9.5 mm)				90.0
No. 8 (2.36 mm)	23.0	49.0	28.0	58.0
No. 16 (1.18 mm)				
No. 30 (600 μ m)				
No. 50 (300 μ m)				
No. 200 (75 μ m)	2.0	8.0	2.0	10.0

Table 1028.07
Gradation Control Points for 0.375 Inch (9.5 mm) Nominal Size and SPR

English Sieve (Metric)	0.375 Inch (9.5 mm) Control Points (percent passing)		SPR Control Points (percent passing)		SPR (Fine) Control Points (percent passing)	
	Minimum	Maximum	Minimum	Maximum	Minimum	Maximum
3/4 inch (19 mm)			98.0	100.0		
1/2 inch (12.5 mm)	100.0					
3/8 inch (9.5 mm)	90.0	100.0	81.0	89.0	81.0	96.0
No. 4 (4.75 mm)		90.0				
No. 8 (2.36 mm)	32.0	67.0	46.0	56.0	46.0	56.0
No. 16 (1.18 mm)						
No. 30 (600 μ m)						
No. 50 (300 μ m)			12.0	21.0	12.0	21.0
No. 200 (75 μ m)	2.0	10.0	4.0	9.0	4.0	9.0

- r. The combined mineral aggregate for Asphaltic Concrete, Type SPS, shall be an aggregate or a combination of aggregates, and mineral filler if needed, that conforms to the gradation requirements specified in Table 1028.08.

**Table 1028.08
Gradation Control Points for Type SPS**

English Sieve (Metric)	Control Points (percent passing)	
	Minimum	Maximum
1 inch (25 mm)	100.0	
¾ inch (19 mm)	94.0	100.0
½ inch (12.5 mm)	81.0	100.0
No. 4 (4.75 mm)	70.0	90.0
No. 8 (2.36 mm)	42.0	70.0
No. 16 (1.18 mm)	29.0	43.0
No. 30 (600 µm)	19.0	34.0
No. 50 (300 µm)	11.0	20.0
No. 200 (75 µm)	2.0	10.0

- s. Mineral filler shall consist of pulverized soil, pulverized crushed rock, broken stone, gravel, sand-gravel, sand or a mixture of these materials that conforms to the requirements in Table 1028.09.

**Table 1028.09
Mineral Filler for Type SPS**

	Min.	Max.
Total Percent Passing the No. 50 (300 µm) Sieve	95	100
Total Percent Passing the No. 200 (75 µm) Sieve	80	100
Plasticity Index (material passing the No. 200 (75 µm) Sieve, except soil)	0	3
Plasticity Index for Soil	0	6

1028.03 -- Acceptance Requirements

1. Mix Criteria:
 - a. The target value for the air voids of the SPH Asphaltic Concrete shall be 4% ($\pm 1\%$) at the Ndes number of gyrations. For Type SPS Asphaltic Concrete the air voids at Ndes shall be a minimum of 1.5% with a maximum of 5.0%. For Type SPR Asphaltic Concrete the air voids shall be 3% ($\pm 1\%$) at the Ndes number of gyrations.
 - b. The design criteria for each mixture shall be determined from Tables 1028.10, 1028.11, and 1028.12.

**Table 1028.10
Gyratory Compaction Effort
(Average Design High Air Temperature <39 degrees C)**

Asphaltic Concrete Type	Nini	Ndes	Nmax
SPS	6	40	62
SPR	7	65	100
SPH	8	95	150

**Table 1028.11
Gyratory Compaction Temperatures**

Mix Type	% RAP	Compaction Temp °F
SPS	0-25	270 ± 5
	26-65	280 ± 5
SPR	0-35	280 ± 5
	36-55	290 ± 5
SPH	0-35	300 ± 5

**Table 1028.12
Minimum Binder Content**

Mix Type (Metric)	Minimum Binder Content, Percent
SPS	4.8
SPR	5.0
3/8 inch (9.5 mm)	5.5
1/2 inch (12.5 mm)	5.1
3/4 inch (19 mm)	5.0

- c. During production of Lot #1 and randomly selected lots thereafter, the Contractor shall provide to the Department 6 properly prepared gyratory samples for AASHTO T 283 testing for all mixtures except Asphaltic Concrete Type SPS. Superpave mixtures shall contain 1.25% hydrated lime as specified in the Special Provision "Hydrated Lime for Asphaltic Mixtures". Each Superpave mixture shall be tested for moisture sensitivity in accordance with AASHTO T 283. The 6 inch (150 mm) specimens shall be compacted in accordance with AASHTO T 312 to 7% ($\pm 0.5\%$) air voids at 95 mm in height and evaluated to determine the Tensile Strength Ratio (TSR).
 - d. During production of Lot #1, the Contractor shall provide to the Department two 75mm gyratory puck samples at 4.0% voids ($\pm 0.5\%$) for APA testing for all mixtures except Asphaltic Concrete Type SPS.
2. The Contractor shall make Mix adjustments when:
 - a. The mix does not meet the current approved JMF or any other requirements of the contract.
 - b. Surface voids create a surface or texture that does not meet the criteria of Sections 502 and 503 in these Standard Specifications.
 - c. Rutting occurs.
 3. The Contractor shall inform the Engineer when changes in mixture properties or materials used occur for any reason. Changes such as, but not limited to, types or sources of aggregates or changes in grades, sources, properties or

modification procedures (if modified) of PG Binders. The Department may require a new job mix formula, mix design and moisture sensitivity test. The new proposed job mix formula shall be in accordance with the requirements as stated above.

4. Mix adjustments at the plant are authorized within the limits shown in Table 1028.13 as follows:
 - a. The adjustment must produce a mix with the percent air voids and all other properties as stated in these specifications.
 - b. All adjustments must be reported to the Engineer.
 - c. The adjustment values in Table 1028.13 will be the tolerances allowed for adjustments from the Department verified mix design "Combined Gradation" target values which resulted from production or mix design adjustments, but cannot deviate from Superpave gradation criteria. Mix adjustments for individual aggregates, including RAP, greater than 25% of the original verified mix design proportion or greater than 5% change in the original verified mix design percentage, whichever is greater, may require the Contractor to submit a new mix design, as determined by the Engineer. The Contractor is responsible for requesting new mix design targets as they approach these tolerances, failure to do so may result in a suspension of operations until a new mix design is approved.

Table 1028.13

Aggregate Adjustments	
Sieve Size	Adjustments
1 inch (25 mm), 3/4 inch (19 mm), 1/2 inch (12.5 mm), 3/8 inch (9.5 mm), No. 4 (4.75 mm)	± 6%
No. 8 (2.36 mm), No. 16 (1.18 mm), No. 30 (600 µm), No. 50 (300 µm)	± 5%
No. 200 (75 µm)	± 2%

5. Sampling and Testing:
 - a. The Contractor shall take samples at frequencies identified by the Engineer, according to the Department statistically based procedure. The samples shall be approximately 75 lbs. (34 kg) and split according to AASHTO T-248 to create a companion sample. This sample splitting can be either at: 1) the sampling location, with the Department taking custody of their sample at that time or 2) after being transported to the test facility in an insulated container, with the Department taking custody of their sample at that time as determined by the Engineer. The details of sampling, location, splitting etc. shall be determined at the pre-construction conference.
 - b. All samples transported to the test facility and companion samples within the Lot shall be identified by attaching or faxing the lab calculation sheet from the latest version of the superpave software, stored, and retained by the Contractor until the Department has completed the verification testing

process. Transporting of all samples will be under the observation of Department.

- c.
 - (1) The sample shall be taken from the roadway, behind the paver before compaction or from the windrow. For SPS mixes, the Contractor has the option to obtain the samples directly at the plant.
 - (2) At least one QC sample shall be tested for every 1,000 tons of plant produced mix.
 - (i) If, at the completion of the project, the final lot consists of less than 5,000 tons of asphaltic concrete, 1 sample for each 1,000 tons or fraction thereof, shall be taken and tested.
 - (3) Additional sampling and testing for the Contractor's information and quality control may be performed at the Contractor's discretion. Any additional testing will not be used in pay factor determination.
 - (4)
 - (i) When cold feed samples are being taken, the acquisition shall be timed such that the material in the sample represents, as close as possible, the same material in the sample taken behind the paver. If cold feeds are sampled and tested by Contractor, a split of that sample must be submitted with the hot mix subplot sample. The Contractor will be notified what subplot (a minimum of 1 subplot per lot) sample must be tested for FAA and CAA from the blended cold feed material according to the Department random sampling schedule. All other FAA and CAA subplot samples may be taken from the randomly selected portion of the blended cold feed material or obtained from the random samples taken behind the paver. Samples shall be taken under the observation of Department and split according to AASHTO T-248, with the Department taking custody of their sample at that time.
 - (ii) For projects using RAP material the FAA shall be established as follows: a RAP sample will be processed through an ignition oven and then combined with the proportioned amount of virgin aggregate defined by the mix design and then proceeding with FAA and CAA testing.
- d. The sample shall be compacted immediately while still hot (additional heating may be required to raise the temperature of the sample to compaction temperature).
- e. Each production sample shall be tested as follows:
 - (1) Bulk Specific Gravity (Gmb) shall be determined for each specimen in accordance with AASHTO T 166 Bulk Specific Gravity of Compacted Bituminous Mixtures Using Saturated

Surface Dry Specimens. One specimen shall be compacted for each production sample.

- (2) One Theoretical Maximum Specific Gravity (Gmm) test for each production sample of uncompacted mixture shall be determined in accordance with AASTHO T 209 procedure 9.5.1. Weight in water - Maximum Specific Gravity of Bituminous Paving Mixtures.
- (3)
 - (i) The Blended Aggregate Bulk Specific Gravity (Gsb) shall be 2.585 for information only for all mixes.
 - (ii) FAA - AASHTO T 304 Method A. The pour time of the test sample into the funnel shall be completed in 5±1 seconds.
 - (iii) CAA - ASTM 5821. For SPR mixes, CAA testing and results are only required on the cold feed verification test for the lot.
- (4) The laboratory air voids shall be determined in accordance with the following:

Table 1028.14

$\text{Gmb}(\text{corr})@Nany = \text{Gmb}(\text{meas})@Nmax \times (\text{height}@Nmax \div \text{height}@Nany)$ $\%Gmm(\text{corr})@Nany = 100 \times (\text{Gmb}(\text{corr})@Nany \div \text{Gmm}(\text{meas}))$ $\% \text{ Air Voids}@Nany = 100 - \%Gmm(\text{corr})@Nany$ $\text{VMA}@Ndes = 100 - (\text{Gmb}(\text{corr})@Ndes \times Ps \div \text{Gsb})$ $\text{VFA}@Ndes = 100 \times ((\text{VMA}@Ndes - \% \text{ Air Voids}@Ndes) \div \text{VMA}@Ndes)$ $\text{Measured} = (\text{meas})$ $\text{Corrected} = (\text{corr})$
--

- (5)
 - (i) The percent of PG Binder shall be determined for each QC test. The percent of PG Binder will be computed by ignition oven results. A correction factor of 0.3% will be added to the ignition oven results for mixes containing hydrated lime.
 - (ii) The gradations shall be determined for each QC test using AASHTO T 30.
- (6) Except as noted in this Subsection, all sampling and testing shall be done as prescribed in the Department Materials Sampling Guide and Standard Method of Tests.

f. Testing Documentation:

- (1) All test results and calculations shall be recorded and documented on data sheets using the latest version of Department provided "Superpave" software. A copy containing complete project documentation will be provided to the Department at the completion of asphalt production.

g. Superpave Software:

- (1) QC charts from the software shall be made available for review by the Engineer at any time.
- (2) As a minimum, the following values shall be reported on Department provided software:
 - (i) Laboratory Gyratory density.
 - (ii) Ignition oven or cold feed aggregate gradations for all Superpave sieves will be reported.
 - (iii) PG Binder content shall be plotted to the nearest 0.01% by ignition oven results in accordance with AASHTO T 308.
 - (iv) The theoretical maximum specific gravity (Rice) to the nearest 0.001% will be reported.
 - (v) Laboratory Gyratory air voids at Ndes shall be plotted to nearest 0.1%. Laboratory Gyratory air voids, at Nini, Ndes and Nmax shall be reported to nearest 0.1%.
 - (vi) FAA and CAA of the asphaltic concrete for both cold feed and ignition oven samples will be reported to the nearest 0.1% for FAA and 1% for CAA. A minimum of one subplot FAA and CAA cold feed sample per lot will be tested and recorded on Department provided software.
 - (vii) VMA content shall be plotted to nearest 0.1% and VFA shall be reported to the nearest 0.1%.
 - (viii) Dust to Binder ratio to the nearest 0.01 will be reported.

6. Verification Sampling and Testing:

- a. The Department will select and test at random one of the subplot samples within a Lot for verification and report results.
- b. The results of Contractor QC testing will be verified by the Department's verification tests. Any samples outside of the tolerances in Table 1028.15 and 1028.16 will result in an Independent Assurance (IA) review of testing and may result in the Department test results being applied.

- (1) On any given Lot, if the results of Air Void verification testing and its companion QC testing are within 1.0% air voids, the Air Void verification for the entire Lot is complete and the Contractor test results will be used to determine the pay factors. If the Air Void verification test results and the companion QC test results are outside the above tolerance, the results from the verification test will be used to determine the pay factor for that subplot. Any or all of the remaining four Department subplot samples may be tested and the Department subplot test results may be applied to the respective sublots and the resulting pay factors will apply.
 - (2) On any given Lot, if the results of the FAA verification testing and its companion QC testing are within 0.5 percent, the FAA verification for the entire Lot is complete and the Contractor test results will be used to determine the pay factor. If the FAA verification test results and the companion QC test results are outside the above tolerance, the results from the verification test will be used to determine the pay factor for that subplot. Any or all of the remaining four Department subplot samples may be tested and the Department subplot test results may be applied to the respective sublots and the resulting pay factors will apply.
- c. When verification tests are within testing tolerance but results show a consistent pattern of deviation from the QC results, the Engineer may cease production and/or request additional verification testing or initiate a complete IA review.

**Table 1028.15
Asphaltic Concrete Testing Tolerances**

Test	Tolerance
Asphalt Content by Ignition Oven	0.5%
Gyratory Density	0.020
Maximum Specific Gravity	0.015
Bulk Dry Specific Gravity (Gsb)	0.020
FAA	0.5%
CAA	10%
Field Core Density	0.020
Air Voids	1.0%

**Table 1028.16
Blended Aggregate Gradation
Testing Tolerances**

Sieve Size	Tolerance
3/4 inch (19 mm), 1/2 inch (12.5 mm), 3/8 inch (9.5 mm), No. 4 (12.5 mm), No. 8 (2.36 mm)	5%
No. 16 (1.18 mm), No. 30 (600 µm), No. 50 (300 µm)	4%
No. 200 (75 µm)	2%

- d. Independent Assurance (IA) Review of Testing:
 - (1) The Contractor shall allow the Department personnel access to their laboratory to conduct IA review of technician testing procedures and apparatus. Any deficiencies discovered in testing procedures will be reported by the department and corrected by the Contractor.
 - (2) During IA review, the Department personnel and the Contractor will split a sample for the purpose of IA testing. The samples selected will be tested in the Department Branch Laboratory. Any IA test results found to be outside of defined testing tolerances above will be reported. The Contractor shall verify the testing apparatus and make corrections if the apparatus is out of tolerance.
 - (3) See Section 28 of the Materials Sample Guide for more information on IA testing.
- e. If the project personnel and the Contractor cannot reach agreement on the accuracy of the test results, the Department will be asked to resolve the dispute, which will be final. It is the Contractor's responsibility to obtain a large enough sample size for any referee testing (a total sample size of 6000 grams, to be retained by the Department after splitting, is recommended for FAA testing). All dispute resolutions will be in accordance with the Quality Assurance Program requirements in the NDOR Materials Sampling Guide.

7. Production Tolerances, Acceptance, and Pay Factors

**Table 1028.17
Production Tolerances***

<i>Test</i>	<i>Allowable Deviation from Specification</i>
<i>Dust to Asphalt Ratio</i>	None
<i>Coarse Aggregate Angularity</i>	- 5% below Min.
<i>Fine Aggregate Angularity for SPR Only</i>	- 0.2% below Min. for cold feed - 0.5% below Min. for ignition oven
<i>Fine Aggregate Angularity for all other mixes</i>	- 0.5% below Min. for cold feed - 1.0% below Min. for ignition oven
Minimum Binder Content	None

* These tolerances are applied to the mix design specification values, not the submitted mix design targets.

- a. The Contractor shall notify the Engineer whenever a test result approaches the Specification limits.
- b. When any single test result for FAA testing falls outside the allowable production tolerances in Table 1028.17, the material represented by this test will be accepted with a 20% penalty or rejected, as determined by the

Engineer. For all other tests, when any single test result, on the same mix property, from two consecutive QC samples fall outside the allowable production tolerances in Table 1028.17, the material represented by these tests will be accepted with a 20% penalty or rejected, as determined by the Engineer.

- c. The Contractor shall assume the responsibility to cease operations when specifications are not being met.
- d. Acceptance and pay factors for Asphaltic Concrete Type SPS will be based on compacted in place average density and joint density.
- e. For each subplot of Asphaltic Concrete Type SPS, SPR and SPH, the asphaltic concrete unit price is a product of all applicable pay factors for the item "Asphaltic Concrete, Type _____". Included in a subplot, following approval of the control strips, may be any roadway Asphaltic Concrete Type SPS, SPR or SPH which is produced and approved by the Engineer and including material used for Patching, State Maintenance Patching, and Asphalt for Intersections and Driveways on project shall be eligible for inclusion in subplot(s) tonnage pay factor determination using the roadway Asphaltic Concrete Type _____ unit price. When a control strip is not constructed, the pay factor for the running average of four air voids shall be fixed at 1.0 for the first three asphaltic concrete sublots.
 - (1) When there is a production tolerance pay factor penalty as stated in Paragraph 7.b. subsection 1028.03 this penalty percentage will be entered in the Superpave Asphalt Pay Factor Summary under production specifications for each subplot affected. These individual pay factors will then be multiplied by each other to determine a total pay factor for each subplot.
- f. The pay factors for the single test air voids and moving average of four air voids pay factors will be determined in accordance with Table 1028.18.

Table 1028.18
Acceptance Schedule
Air Voids - N_{des}

Air voids test results for Asphaltic Concrete Type SPR	Air voids test results for SPH Asphaltic Concrete	Pay Factor	
		Moving average of four	Single test
Less than 0.5%	Less than 1.5%	50% or Reject	50% or Reject
0.5% to 0.9%	1.5% to 1.9%	50% or Reject	50%
1.0% to 1.4%	2.0% to 2.4%	50% or Reject	95%
1.5% to 1.9%	2.5% to 2.9%	90%	95%
2.0% to 2.4%	3.0% to 3.4%	100%	100%
2.5% to 3.5%	3.5% to 4.5%	102%	104%
3.6% to 4.0%	4.6% to 5.0%	100%	100%
4.1% to 4.5%	5.1% to 5.5%	95%	95%
4.6% to 5.0%	5.6% to 6.0%	90%	95%
5.1% to 5.5%	6.1% to 6.5%	50% or Reject	90%
5.6% to 6.0%	6.6% to 7.0%	50% or Reject	50%
6.1% and over	7.1% and over	50% or Reject	50% or Reject

8. Asphalt Concrete Density Samples:
- a. The Contractor shall perform density tests under direct observation of Department personnel. The Contractor shall establish the method of testing in the preconstruction conference and shall test in accordance with the AASHTO T 166, NDR T 587, or as otherwise described in these Special Provisions. The Contractor shall insure that the proper adjustment bias and/or correction factors are used and accessible to Department personnel along with all other inputs when NDR T 587 is selected. All correlation factors and test results shall be generated and reported on the Department Density spreadsheet. When AASHTO T 166 is being used, the Department will observe the Contractor taking, transporting, and testing the cores. The Department will take immediate custody of the cores at the completion of the testing. All disputed values determined using NDR T 587 will be resolved using AASHTO T 166.

- b. The Contractor shall determine the density of samples by comparing the specific gravity of the core sample to the Maximum Specific Gravity (Rice) as follows:

$$\% \text{ Density} = \frac{\text{Specific Gravity of Core}}{\text{Maximum Mix Specific Gravity (Rice)}} \times 100$$

where:

$$\text{Sp. Gr. of Core} = \frac{\text{Wt. of Core in Air}}{\text{Wt. of SSD Core} - \text{Wt. of Core in Water}}$$

$$\text{Maximum Mix Specific Gravity (Rice)} = \frac{\text{Wt. of Mix in Air}}{\text{Wt. of Mix in Air} - \text{Wt. of Mix in Water}}$$

Note: The individual QC test value of the Maximum Mix Specific Gravity (Rice), determined by AASHTO T 209, will be used to calculate the density of each corresponding core.

- c. The Contractor shall cut cores the first day of work following placement of the mixture. The core samples shall be a minimum of a 3 inch (75mm) diameter.
- d. Normally, 1 sample for determination of density will be taken from each subplot at locations determined by the Engineer.
- e. The average density of the lot shall be used to compute the pay factor for density. Exceptions to the sampling and testing of core samples for the determination of density are as follows:
- (1) When the nominal layer thickness is 1 inch (25 mm) or less, the sampling and testing of density for this layer will be waived.
 - (2) When the average thickness of the 5 cores for a lot is 1 inch (25 mm) or less, the testing of density samples for this lot will be waived.
 - (3) When the nominal layer thickness and the average of the original 5 cores for a lot are both more than 1 inch (25 mm), but some of the cores are less than 1 inch (25 mm) thick, additional cores shall be cut at randomly selected locations to provide 5 samples of more than 1 inch (25 mm) thickness for the determination of the pay factor for density.
- f. (1) If, at the completion of the project, the final lot consists of less than one lot of asphaltic concrete, a minimum of 3 samples, or 1 sample for each subplot or fraction thereof, whichever is greater, shall be taken and tested for density.
- (2) The test results shall be averaged and the density pay factor based on the values shown in Table 1028.19.

- (3) Should the average of less than 5 density tests indicate a pay factor less than 1.00, additional density samples to complete the set of five shall be taken at randomly selected locations and the density pay factor based on the average of the 5 tests.

Table 1028.19

Acceptance Schedule Density of Compacted Asphaltic Concrete	
Average Density (5 Samples, Percent of Voidless Density)	Pay Factor
Greater than 92.4	1.00
Greater than 91.9 to 92.4	0.95
Greater than 91.4 to 91.9	0.90
Greater than 90.9 to 91.4	0.85
Greater than 90.4 to 90.9	0.80
Greater than 89.9 to 90.4	0.70
89.9 or Less	0.40 or Reject

- g. If requested by the Contractor, check tests for all density tests in the original set, taken no later than the working day following the receipt of all test results for the lot, will be allowed in lots with a density pay factor of less than 1.00. No re-rolling will be allowed in these lots. Locations for checks tests will be provided by the Engineer from the Random Sampling Schedule. The average density obtained by the check tests shall be used to establish the density pay factor for the lot.
- h. The location of density samples are identified by the Random Sampling Schedule. When the random location is noted as zero or the lane width (i.e., zero or 12 ft. on a 12-foot lane), the core shall be cut with the outer edge of the core barrel no greater than 4 inches away (laterally) from the edge of the top of the mat for an unconfined edge or from the edge of the top of the hot mat (joint) for a confined edge. If using a nuclear gauge, the 4 inches would be measured to the edge of the gauge base. The percent density value at these edge-of-lane locations shall be adjusted upward by 2.5%, but to a value of no greater than 92.5%, and the resultant value used in determining the density pay factor. No initial value of 92.5 or greater shall be adjusted.

WARM MIX ASPHALT (J-7-1116)

The Contractor has the option to use Warm Mix Asphalt (WMA) meeting the following requirements.

1. Warm Mix Asphalt (WMA)

Warm Mix Asphalt mixtures shall follow the requirements of Superpave Asphaltic Concrete and all other applicable sections with the following exceptions:

- a. The Contractor shall request the use of a WMA additive in writing when submitting the Job Mix Formula. The requested additive shall be an approved Level I or II production product or combination thereof. The manufacturer's recommended additive rates, specifications, and all other pertinent information shall be included in the requests. All requests must be approved by the Flexible Pavements Engineer prior to their use.
- b. Level I Production
 - (1) Level I WMA additives are as follows: water injection devices.
 - (2) Hydrated Lime at 1.25% by weight of virgin aggregate is required for all mixtures.
 - (3) The allowable drop in temperature shall be a maximum of 40°F below the producer's recommended production temperature for Hot Mix Asphalt (HMA), or less as required during production to achieve proper laydown and compaction properties. Plant production temperatures shall not drop below 230°F.
- c. Level II Production
 - (1) Level II WMA additives are as follows: Advera, Evotherm 3G (M1, U1), AkzoNobel Rediset LQ-1102C, Cecabase RT 945 w/AD-here LOF 65-00, and Sasobit.
 - (2) For amine based WMA additives, 25% of the additive must be considered an amine based anti-stripping agent, unless Poly-Phosphoric Acid (PPA) is used. If PPA is used in the binder, the WMA shall be a non-amine based WMA, specifically for use and compatible with binders containing PPA. WMA additives and anti-strips shall be terminal blended by the binder supplier. For all other warm mix technologies hydrated lime shall be added at a minimum rate of 1.25% by weight of virgin aggregate, including the weight of limestone. Hydrated Lime shall not be used on Level II WMA mixtures when the WMA additive is an Amine based additive or when the Amine WMA additives are used in combination with Level I water injection. The minimum rate for amine based WMA additives shall be 0.7%. The dosage rate of anti-strip shall not exceed manufacturer's recommendations.

- (3) The drop in temperature shall be a maximum of 90°F from the producer's recommended production temperature for HMA. Plant production temperatures shall not drop below 215°F.
- d. Other WMA additives shall not be used unless otherwise approved by the Flexible Pavements Engineer.
- e. WMA additives may be used in combination by approval of the Flexible Pavements Engineer.
- f. Asphalt mixes shall be tested for TSR on the first lot of production and then on randomly selected lots thereafter.
- g. Field samples shall be heated and compacted using the following table unless otherwise approved by the Flexible Pavements Engineer.

Gyratory Compaction Temperatures

Mix Type	% Rap	Compaction Temp °F
SPS	0-25	270 + 5
	26-65	280 + 5
SPR	0-35	280 + 5
	36-55	290 + 5
SPH	0-35	300 + 5

- h. NDOR may suspend or eliminate the use of WMA on a project if any of the following conditions occur: rutting, segregation, surface voids, tearing, irregular surface, low density, raveling, stripping, or if pavement does not meet any other design criteria.
2. Warm Mix Asphalt (WMA) additives will be measured and paid for directly by the unit of each for the item "Hydrated Lime/Warm Mix Asphalt" for each ton of hot mix asphalt produced.

**ASPHALT DENSITY GAUGE
(J-7-1013)**

Description

An Asphalt Density Gauge may be used for Quality Control when determining the in-place density of asphaltic concrete.

Material Requirements

The device must be approved by the Flexible Pavements Engineer.

Testing Method

- 1. The Contractor shall establish the method of testing in the preconstruction conference. All testing shall be in accordance with AASHTO T-343 and as directed in this provision.

2. The first 3 density locations of the project shall be cored in accordance with AASHTO T166 to calibrate the asphalt density gauge. Prior to coring, the Contractor shall calibrate the device at each core location.
3. Calibration: A correction factor shall be established for the first 3 cores by calculating the difference between the average density measurement of the asphalt density gauge and the roadway core density. This correction factor shall be entered into the device and used for measuring subsequent densities. The correction factor shall be verified with another core for every 15 density readings that are to be recorded.
4. Density Reading Procedure: Place the asphalt density gauge on the asphalt mat over the area to be tested. Record the density reading, and repeat this process for a total of 5 readings, as detailed in Figure 1. An average of the 5 readings will be used as the density reading for each location. For densities taken less than 6 inches from the edge of the lift, density readings shall be taken as shown in Figure 2. The span between density reading locations in each direction shall be no greater than 12".




Figure 1: Asphalt density gauge reading pattern




Figure 2: Asphalt density gauge reading pattern less than 6" from mat edge

5. If any density measured by the asphalt density gauge is below 90%, a density core shall be cut at that location and used for density measurement for that subplot. Density readings below 90% shall not be used to calculate a correction factor. All disputed values determined using the asphalt density gauge will be resolved using AASHTO T 166.

ASPHALTIC CONCRETE LONGITUDINAL JOINT DENSITY TESTING (J-7-1013)

Description

One sample for determination of joint density will be taken randomly from each lot. This joint density sample stands independent of the required standard density per subplot used for determining the average of 5 density pay factor.

Equipment

Testing shall be conducted in accordance with the AASHTO T 166, NDR T 587, or an approved Asphalt Density Gauge. The Contractor shall insure that the proper adjustment bias and/or correction factors are used and accessible to Department personnel, along with all other inputs when NDR T 587 or the Asphalt Density Gauge is selected. All correlation factors and test results shall be generated and reported on the Department Density spreadsheets.

Testing

1. The Contractor shall establish the method of testing in the preconstruction conference.
2. One sample for determination of joint density will be taken randomly from each lot, as determined by the Engineer. The location of the edge density samples are identified by the Random Sampling Schedule.
3. The joint density core shall be cut 1 inch away (laterally) from the identified edge of the top of the mat.
4. The Contractor shall cut cores the first day of work following placement of the mixture. The core samples shall be a minimum of a 3 inch (75mm) diameter.
5. The Department will observe the Contractor taking, transporting, and testing the cores (as applicable). The Department will take immediate custody of the cores at the completion of the testing. All disputed values determined using NDR T 587 or the Asphalt Density Gauge will be resolved using AASHTO T166.

6. The Contractor shall determine the density of samples by comparing the specific gravity of the core sample to the Maximum Specific Gravity (Rice) as follows:

$$\% \text{ Density} = \frac{\text{Specific Gravity of Core}}{\text{Maximum Mix Specific Gravity Rice}} \times 100$$

where:

$$\text{Sp. Gr. of Core} = \frac{\text{Wt. of Core in Air}}{\text{Wt. of SSD Core} - \text{Wt. of Core in Water}}$$

$$\text{Maximum Mix Specific Gravity (Rice)} = \frac{\text{Wt. of Mix in Air}}{\text{Wt. of Mix in Air} - \text{Wt. of Mix in Water}}$$

Note: The individual QC test value of the Maximum Mix Specific Gravity (Rice), determined by AASHTO T 209, will be used to calculate the density of each corresponding core.

7. Exceptions to the sampling and testing of joint density core samples for the determination of density are as follows:
- a. When the nominal layer thickness is 1 inch (25 mm) or less, the sampling and testing of density for this layer will be waived.
 - b. When the average thickness for the standard lot is 1 inch (25 mm) or less, the testing of joint density samples for this lot will be waived.
8. If requested by the Contractor, a re-test for the original joint density test, taken no later than the working day following the receipt of the test result, will be allowed. Locations of re-tests will be provided by the Engineer from the Random Sampling Schedule. The density obtained by the re-test shall be used to establish the density pay factor for the lot.

Method of Measurement

All work related to the Asphaltic Concrete Longitudinal Joint Density Sample will not be measured and paid for but will be subsidiary to the associated asphaltic concrete.

Basis of Payment

1. The pay factor shall be computed according to the following table:

Joint Density Test Lot Pay Factor			
Joint Density	SPS	SPR	SPH
93.0 or greater	102%	102%	102%
92.0 to 92.9	100%	102%	102%
91.0 to 91.9	98%	100%	102%
90.0 to 90.9	98%	98%	100%
89.0 to 89.9	98%	98%	98%
88.9 or Less	98%	98%	98%

2. The pay factor will be incorporated in the production specs calculation in the Superpave Software. Any incentive or disincentive will be added or subtracted to the pay factor after any other applicable production tolerances pay factors have been incorporated. The pay factor will apply to the entire lot.

ASPHALTIC CONCRETE TYPE SLX

Asphaltic Concrete, Type SLX shall meet all of the requirements of Asphaltic Concrete, Type SPR, listed in Section 1028 and these Special Provisions, with the following exceptions:

1. Material Characteristics:

- a. The type of PG Binder used shall be PG Binder 58V-34 with 0.7% of an approved amine-based WMA additive.
- b. Reclaimed Asphalt Pavement (RAP) will be added to the mix at a minimum of 20% and a maximum of 35%. The RAP must be fractionated/processed prior to use, to a sizing such that the combined hot mix meets the required gradation. The mat cannot exhibit any visual defects or cold spots from RAP conglomeration.
- c. The mix shall contain a minimum of 20% Crushed Rock Chips (with a minimum of 45% retained on the #4 sieve and a maximum of 5% passing the #200 sieve).
- d. The Asphaltic Concrete shall have a minimum Fine Aggregate Angularity (FAA) of 43.0 on the combined aggregate blend. There is no requirement for Coarse Aggregate Angularity (CAA).
- e. Asphaltic Concrete Type SLX shall use the gradation band listed below.

Gradation Control Points for Type SLX

English Sieve (Metric)	Control Points (percent passing)	
	Minimum	Maximum
1/2 inch (12.5 mm)	98.0	100.0
3/8 inch (9.5 mm)	93.0	100.0
No. 4 (4.75 mm)	70.0	87.0
No. 8 (2.36 mm)	45.0	65.0
No. 16 (1.18 mm)	25.0	41.0
No. 30 (600 μm)	15.0	31.0
No. 50 (300 μm)	10.0	21.0
No. 100 (150 μm)	---	---
*No. 200 (75 μm)	4.0	10.0

* Dust to binder ratio is the ratio of the percentage by weight of aggregate finer than the No. 200 (75 μm) sieve to the asphalt content expressed as a percent by weight of total mix. The dust to binder ratio shall be between 0.70 and 1.70.

2. Design Criteria:

- a. The optimum binder content shall be the binder content that produces 2.0 to 4.0 percent air voids at 50 gyrations, with a minimum content of 5.3%.
- b. The Voids in the Mineral Aggregate (VMA) shall be a minimum of 16% ± 1% (mix design only).

3. Placing and Finishing:

- a. Asphaltic Concrete shall be placed only when the ambient temperature is at least 40°F (4°C) and rising.
- b. The asphaltic concrete temperature shall be 285° F (154°C) or above measured in the truck just prior to placement. Exceptions to this requirement are that the PG Binder Supplier recommended maximum temperature requirement shall not be exceeded.
- c. The Contractor will use steel wheel compactors only. Rubber tire rollers will not be allowed.

4. Asphaltic Concrete Density:

Regardless of layer thickness, Asphaltic Concrete Type SLX will be monitored for density.

An initial rolling pattern test strip shall be completed to determine the rolling pattern that will target a minimum of 92.5% density. The Contractor shall monitor the density through a combination of rolling pattern and field testing as deemed necessary by the Engineer.

Method of Measurement:

For each lot of Asphaltic Concrete Type SLX, the asphaltic concrete shall be paid by the contract unit price for the item "Asphaltic Concrete, Type SLX". The asphaltic concrete unit price is a product of all applicable pay factors excluding density and CAA.

Basis of Payment:

Paragraphs 2.a., 2.b.(1), 2.b.(2) and 2.b.(3) of Subsection 503.06 are void and superseded by the following:

Asphaltic Concrete Type SLX shall be paid per ton (Mg) for the item "Asphaltic Concrete Type SLX".

**HYDRATED LIME FOR ASPHALT MIXTURES
(J-12-0213)**

1. General

Hydrated lime will be added to all aggregates (at the Contractor's option, limestone may be excluded) used for asphalt mixtures except Asphaltic Concrete used for Temporary Surfacing, and Asphaltic Concrete Type SPS, HRB and SPL. Hydrated lime will be added to pre-moistened aggregates whether it is used directly into the mix or stockpiled for marinating purposes. The application of moisture and hydrated lime to the aggregates along with equipment calibration and procedures to prevent any "dusting" shall be documented and approved in the Contractor's Quality Control (QC) Plan.

2. Material Requirements

The lime shall meet the chemical and physical properties defined in AASHTO M 303 for Type I - High calcium-hydrated lime, or meet the requirements of ASTM 1097 for Type S Hydrated Lime.

The hydrated lime being used, whether for mix design or plant mix production, shall be stored in an enclosed container and must be used within 90 days. Stockpiles marinating shall also be used within 90 days. Lime that is stored over 90 days in a protected storage silo environment may be submitted for chemical analysis to verify that it meets the specification for use in the mix.

Water shall conform to the requirements of Section 1005.

3. Construction

Prior to the addition of hydrated lime the aggregates shall have a minimum moisture content of 3% by weight of aggregate. The surface of the aggregate shall be uniformly dampened by water.

If additional moisture is required it shall be added at the entry end of an enclosed pug mill mixer and prior to the addition of hydrated lime.

Hydrated Lime shall be added at a rate of 1.25 percent by weight of virgin aggregate, including the weight of the limestone.

4. Equipment

The addition of lime shall be plant controlled, and blended with an enclosed twin-shaft pug mill with a production capacity rating that exceeds the aggregate feed rate. It shall be capable of effective mixing in the full range of asphaltic concrete production rates.

The pug mill set up shall be located in the system at a location where the mixed material can be readily inspected on a belt prior to entry into the drum.

The pug mill shall be designed such that the mixture of aggregate and hydrated lime is moved in a near horizontal direction (within 20 degrees of horizontal) by the mixing paddles without the aid of conveyor belts for a distance of at least three feet (900 mm). Mixing devices which permit the mixture of aggregate and hydrated lime to fall through the mixing blades onto a belt or chute are not acceptable.

A positive signal system and a limit switch device shall be installed in the plant at the point of introduction of the hydrated lime. The positive signal system shall be placed between a metering device and the drum plant, and utilized during production whereby an alarm is activated; alerting the plant that the hydrated lime is not being introduced into the mixture.

The hydrated lime storage silo shall have enough capacity for continuous production. The silo shall be replenished by pneumatic delivery from road tankers at a pressure that will not create dusting. Hydrated lime will be dispensed from the silo into the pug mill by a conventional vane feeder or a load cell pod system.

The mechanism for adding moisture to the aggregate will be configured and located to insure that all virgin aggregate is uniformly coated with moisture prior to the lime application.

5. Sampling and Testing

Hydrated lime shall be certified by the supplier stating its compliance to the specifications.

A physical inventory of hydrated lime usage will be required during mix production. A daily silo inventory, noting "beginning weight", "weight added during the day's production", and "end of day weight", will be recorded and made available for review by the Engineer. When a weigh pod system is used, an accumulative accounting method shall be used to calculate and review lime addition rates throughout production. When calculations indicate a hydrated lime usage of ± 0.15 percent from the design percentage the Contractor shall assume the responsibility to cease production and recalibrate the system prior to resuming mix production. Any asphaltic concrete placed having 0.15 percent below the design percentage shall be removed and replaced at no cost.

The percent of moisture shall be determined and documented: 1) from belt samples or 2) from stockpile samples, a minimum of once per day.

6. Mixture QC and Verification Testing

During an ignition oven burn off, lime will combine with the sulfur in the binder and produce ash. Therefore, when mix containing hydrated lime is being designed and produced a correction factor to the ignition oven burn off result of +0.30% shall be used. This correction factor shall be added to the ignition oven binder content reading in order for the actual binder content to be determined.

7. Method of Measurement:

Hydrated Lime shall be measured for payment by the unit of each for each ton of hot mix asphalt used and incorporated into the project, or for State Maintenance Patching.

Water applied shall not be measured and paid for but shall be considered subsidiary to the item "Hydrated Lime/Warm Mix Asphalt".

8. Basis of Payment:

Lime, measured as provided herein and incorporated into the project, shall be paid for at the contract unit price per each for the item "Hydrated Lime/Warm Mix Asphalt". Lime measured as provided herein and used for State Maintenance Patching shall be paid for at the contract unit price per each for the item "Hydrated Lime/Warm Mix Asphalt for State Maintenance Patching". This price shall be full compensation for furnishing, delivering, hauling, storing, all labor, equipment, tools and incidentals necessary to complete the work.

HYDRATED LIME SLURRY FOR ASPHALT MIXTURES (J-12-0213)

1. **General** — The Contractor will have the option of using Hydrated Lime Slurry For Asphalt Mixtures or Hydrated Lime For Asphalt Mixtures. Hydrated lime slurry will be added to all aggregates (at the Contractor's option, limestone may be excluded) used for asphalt mixtures except Asphaltic Concrete used for Temporary Surfacing, and Asphaltic Concrete Type SPS and SPL. Hydrated lime slurry will be added to aggregates whether it is used directly into the mix or stockpiled for marinating purposes. The application of hydrated lime slurry to the aggregates along with equipment calibration and procedures shall be documented and approved in the Contractor's Quality Control (QC) Plan.
2. **Material Requirements** — The lime shall meet the chemical and physical properties defined in AASHTO M 303 for Type I - High calcium-hydrated lime, or meet the requirements of ASTM 1097 for Type S Hydrated Lime.

The dry hydrated lime being used, whether for mix design or plant mix production, shall be stored in an enclosed container and must be used within 90 days. Stockpiles marinating shall also be used within 90 days. Hydrated lime (dry or slurry) that is stored over 90 days in a protected storage silo or slurry tank may be submitted for chemical analysis to verify that it meets the specification for use in the mix.

Water shall conform to the requirements of Section 1005.

3. **Construction** — Hydrated Lime shall be added at a rate of 1.25 percent by weight of virgin aggregate, including the weight of the limestone.
4. **Equipment** — The addition of lime shall be plant controlled, and blended with an enclosed twin-shaft pug mill with a production capacity rating that exceeds the aggregate feed rate. It shall be capable of effective mixing in the full range of asphaltic concrete production rates.

The pug mill set up shall be located in the system at a location where the mixed material can be readily inspected on a belt prior to entry into the drum.

The pug mill shall be designed such that the mixture of aggregate and hydrated lime is moved in a near horizontal direction (within 20 degrees of horizontal) by the mixing paddles without the aid of conveyor belts for a distance of at least three feet (900 mm).

Mixing devices which permit the mixture of aggregate and hydrated lime to fall through the mixing blades onto a belt or chute are not acceptable.

A positive signal system and a limit switch device shall be installed in the plant at the point of introduction of the hydrated lime. The positive signal system shall be placed between a metering device and the drum plant, and utilized during production whereby an alarm is activated; alerting the plant that the hydrated lime is not being introduced into the mixture.

A minimum of two hydrated lime slurry tanks shall be used for blending and supply. Slurry shall be drawn for production from only one tank at a time. The hydrated lime slurry tanks shall have enough capacity for continuous production.

Hydrated lime slurry shall be dispensed from a slurry tank into the pug mill by a pressure regulated spray system having an electronic flow measurement system that has been

calibrated to insure the proper application rates will be provided. Certificate of Calibration for the spray bar system should be provided by the Contractor with the calibration being performed by a third party every 12 months (minimum) or at the Engineer's request.

The electronic flow measurement system shall automatically record the flow rate of the lime slurry being feed to the pug mill. The data recorder system shall be capable of recording the flow rate (in gallons per minute) at intervals of not more than 5 minutes and shall have the capability of calculating the volume of lime slurry used each day, from each slurry tank, and shall be capable of printing a summary of the daily lime slurry usage for each tank. This printout of the daily lime slurry volumes shall be presented to the NDOR representative at the end of each day's production.

- 5. Blending and Supply Hydrated Lime Slurry** — The Contractor shall determine the target hydrated lime slurry concentration (percent solids) that will be used to produce the asphalt mixture. This target concentration value shall be provided to the Engineer prior to production of the asphalt mixture and shall not be less than 30 percent. The target concentration value shall not be modified without the approval of the Engineer. It is the Contractors responsibility to control the concentration of the hydrated lime slurry.

Only valid weights of dry hydrated lime shall be added to the required quantity of water to provide uniform hydrated lime slurry having a dry solids content within ± 0.5 percent of the Contractor's target value. Water or dry hydrated lime shall not be added to a tank that is actively supplying hydrated lime slurry to the pug mill. Hydrated lime slurry shall not be drawn from a tank that is not completely blended in accordance with the manufacturer's recommendations.

The hydrated lime slurry in the active supply tank shall be agitated prior to and during production in accordance with the manufacturer's recommendations.

Dry hydrated lime shall be transferred at a pressure that will not create dusting.

- 5.1** If individual hydrated lime slurry tanks are dedicated to only blending or supply, then thoroughly mixed hydrated lime slurry may be added from the blending tank(s) to the supply tank during production, provided the concentrations are within ± 0.5 percent.
- 5.2** If the hydrated lime slurry tanks are used for both blending and supply, the tanks shall be plumbed such that hydrated lime slurry can be supplied to the pug mill from any of the blending/supply tanks without disruption of the slurry supply.
- 6. Sampling and Testing** — Hydrated lime shall be certified by the supplier stating its compliance to the specifications.

The concentration of the lime slurry shall be controlled within ± 0.5 percent of the target hydrated lime slurry concentration (percent solids). The concentration of the hydrated lime shall be determined in accordance with section 6.1. It is the Contractor's responsibility to halt production to make adjustments when the concentrations fall out of compliance.

The concentration of the lime slurry shall be determined and recorded by the Contractor immediately following blending each batch of lime slurry for the project. These records

shall include date and time of test, sample collection information, and the unit weight, temperature and concentration of slurry. These records shall be made available to the Engineer upon request.

A physical inventory of hydrated lime usage will be required during mix production. This inventory shall be used to verify the lime application rate, and for payment of the hydrated lime. The concentration of the lime slurry shall be determined and recorded by the Contractor at the beginning and at approximately the mid-point of each day's production. The hydrated lime slurry samples shall be collected from the supply line leading to the pug mill. These records shall include date and time of test, sample collection information, and the unit weight, temperature and concentration of slurry. These records shall be presented to the NDOR representative at the end of each day's production.

When calculations indicate that the application rate of "dry" hydrated lime to the aggregate is ± 0.15 percent from the design percentage the Contractor shall assume the responsibility to cease production and recalibrate the system prior to resuming mix production. Any asphaltic concrete placed having a "dry" hydrated lime application rate (applied to aggregate) of 0.15 percent below the design percentage shall be removed and replaced at no cost.

6.1 The Contractor shall determine the solids content (concentration) of the hydrated lime slurry using Table 1, Table 2 and the Slurry Worksheet. The Contractor shall provide and use the standard weight per 83.205-ml Gardner cup meeting the requirements of ASTM D 244.

After a batch of lime slurry has been produced, use the following procedures to verify that the intended percent solids have been achieved.

1. Fill a quart container 3/4 full with lime slurry. Samples can be taken from ports located at either end of the vessel. Do not use glass.
2. Weigh a dry, empty Gardner (WPG) cup and cover to the nearest 0.01 of a gram. Record this weight.
3. Shake the lime slurry sample well. Immediately fill the WPG cup.
4. Tap the WPG cup lightly on an immovable object to allow for the escape of air bubbles.
5. Slowly turn the cap of the WPG cup until it is completely seated. If the cover is pushed on quickly, lime slurry will squirt out through the hole in the center. Be sure to point the top of the WPG away from you (or others) while putting on the cap.
6. Hold the WPG cup by the top and bottom with thumb and forefinger. Be sure to cover the hole in the cap.
7. Rinse the WPG cup under running water to remove any lime from the outside of the cup.
8. Dry the outside of the cup thoroughly.
9. Weigh the dry, filled WPG cup to the nearest 0.01 of a gram. Record this weight.

10. Promptly remove the cover, insert thermometer and record the temperature.
 11. Subtract the empty cup weight (from step 2) from the filled cup weight (step 9) and record the difference.
 12. Multiply the difference by 0.1. This number is the density (lbs./gallon) of the lime slurry. Record this number.
 13. Look up the temperature correction in Table 2 and record the value.
 14. Multiply the slurry density times the temperature correction value. This is the adjusted slurry density. Record the adjusted slurry density on the slurry worksheet.
 15. Find the nearest density to that recorded above on the "Slurry Solids Chart" on Table 1, Slurry Solids Chart - 24 degrees C. The corresponding number is the percent solids (concentration) of the lime slurry sample. Record on worksheet.
7. **Mixture QC and Verification Testing** — During an ignition oven burn off, lime will combine with the sulfur in the binder and produce ash. Therefore, when mix containing hydrated lime is being designed and produced a correction factor to the ignition oven burn off result of +0.30% shall be used. This correction factor shall be added to the ignition oven binder content reading in order for the actual binder content to be determined.
8. **Method of Measurement** — Hydrated Lime shall be measured for payment by the unit of each for each ton of hot mix asphalt used and incorporated into the project, or for State Maintenance Patching.
- Water applied shall not be measured and paid for but shall be considered subsidiary to the item "Hydrated Lime/Warm Mix Asphalt".
9. **Basis of Payment** — Lime, measured as provided herein and incorporated into the project, shall be paid for at the contract unit price per each for the item "Hydrated Lime/Warm Mix Asphalt". Lime measured as provided herein and used for State Maintenance Patching shall be paid for at the contract unit price per each for the item "Hydrated Lime/Warm Mix Asphalt for State Maintenance Patching". This price shall be full compensation for furnishing, delivering, hauling, storing, all labor, equipment, tools and incidentals necessary to complete the work.

Table 1, Page 1
Slurry Solids Chart – 24°C

Density lbs./gal.	Slurry Solids %	Density lbs./gal.	Slurry Solids %	Density lbs./gal.	Slurry Solids %	Density lbs./gal.	Slurry Solids %
9.108	15.1	9.402	20.1	9.715	25.1	10.050	30.1
9.114	15.2	9.406	20.2	9.722	25.2	10.057	30.2
9.120	15.3	9.414	20.3	9.728	25.3	10.064	30.3
9.128	15.4	9.420	20.4	9.735	25.4	10.071	30.4
9.131	15.5	9.426	20.5	9.741	25.5	10.078	30.5
9.137	15.6	9.433	20.6	9.748	25.6	10.085	30.6
9.143	15.7	9.439	20.7	9.755	25.7	10.092	30.7
9.148	15.8	9.445	20.8	9.761	25.8	10.099	30.8
9.154	15.9	9.451	20.9	9.768	25.9	10.106	30.9
9.160	16.0	9.457	21.0	9.774	26.0	10.113	31.0
9.166	16.1	9.463	21.1	9.781	26.1	10.120	31.1
9.171	16.2	9.469	21.2	9.787	26.2	10.127	31.2
9.177	16.3	9.476	21.3	9.794	26.3	10.134	31.3
9.183	16.4	9.482	21.4	9.800	26.4	10.141	31.4
9.189	16.5	9.488	21.5	9.807	26.5	10.148	31.5
9.195	16.6	9.494	21.6	9.814	26.6	10.155	31.6
9.200	16.7	9.500	21.7	9.820	26.7	10.163	31.7
9.206	16.8	9.506	21.8	9.827	26.8	10.170	31.8
9.212	16.9	9.513	21.9	9.833	26.9	10.177	31.9
9.218	17.0	9.519	22.0	9.840	27.0	10.184	32.0
9.224	17.1	9.525	22.1	9.847	27.1	10.191	32.1
9.230	17.2	9.531	22.2	9.853	27.2	10.198	32.2
9.235	17.3	9.538	22.3	9.860	27.3	10.205	32.3
9.241	17.4	9.544	22.4	9.867	27.4	10.212	32.4
9.247	17.5	9.550	22.5	9.873	27.5	10.220	32.5
9.253	17.6	9.556	22.6	9.880	27.6	10.227	32.6
9.259	17.7	9.563	22.7	9.887	27.7	10.234	32.7
9.265	17.8	9.569	22.8	9.894	27.8	10.241	32.8
9.271	17.9	9.575	22.9	9.900	27.9	10.248	32.9
9.277	18.0	9.581	23.0	9.907	28.0	10.255	33.0
9.282	18.1	9.588	23.1	9.914	28.1	10.263	33.1
9.288	18.2	9.594	23.2	9.920	28.2	10.270	33.2
9.294	18.3	9.600	23.3	9.927	28.3	10.277	33.3
9.300	18.4	9.607	23.4	9.934	28.4	10.284	33.4
9.306	18.5	9.613	23.5	9.941	28.5	10.292	33.5
9.312	18.6	9.619	23.6	2.948	28.6	10.299	33.6
9.318	18.7	9.626	23.7	9.954	28.7	10.306	33.7
9.324	18.8	9.632	23.8	9.961	28.8	10.314	33.8
9.330	18.9	9.638	23.9	9.968	28.9	10.321	33.9
9.336	19.0	9.645	24.0	9.975	29.0	10.328	34.0
9.342	19.1	9.651	24.1	9.982	29.1	10.335	34.1
9.348	19.2	9.658	24.2	9.988	29.2	10.343	34.2
9.354	19.3	9.664	24.3	9.995	29.3	10.350	34.3
9.360	19.4	9.670	24.4	10.002	29.4	10.358	34.4
9.366	19.5	9.677	24.5	10.009	29.5	10.365	34.5
9.372	19.6	9.683	24.6	10.016	29.6	10.372	34.6
9.378	19.7	9.690	24.7	10.023	29.7	10.380	34.7
9.384	19.8	9.696	24.8	10.030	29.8	10.387	34.8
9.390	19.9	9.703	24.9	10.037	29.9	10.394	34.9
9.396	20.0	9.709	25.0	10.044	30.0	10.402	35.0

Table 1, Page 2
Slurry Solids Chart – 24°C

Density lbs./gal.	Slurry Solids %	Density lbs./gal.	Slurry Solids %	Density lbs./gal.	Slurry Solids %	Density lbs./gal.	Slurry Solids %
10.409	35.1	10.795	40.1	11.210	45.1	11.658	50.1
10.417	35.2	10.803	40.2	11.218	45.2	11.667	50.2
10.424	35.3	10.811	40.3	11.227	45.3	11.677	50.3
10.432	35.4	10.819	40.4	11.236	45.4	11.686	50.4
10.439	35.5	10.827	40.5	11.244	45.5	11.695	50.5
10.447	35.6	10.835	40.6	11.253	45.6	11.705	50.6
10.454	35.7	10.843	40.7	11.262	45.7	11.714	50.7
10.462	35.8	10.851	40.8	11.270	45.8	11.724	50.8
10.469	35.9	10.859	40.9	11.279	45.9	11.733	50.9
10.477	36.0	10.867	41.0	11.288	46.0	11.743	51.0
10.484	36.1	10.875	41.1	11.297	46.1	11.752	51.1
10.492	36.2	10.883	41.2	11.305	46.2	11.762	51.2
10.499	36.3	10.892	41.3	11.314	46.3	11.771	51.3
10.507	36.4	10.900	41.4	11.323	46.4	11.781	51.4
10.514	36.5	10.908	41.5	11.332	46.5	11.790	51.5
10.522	36.6	10.916	41.6	11.341	46.6	11.800	51.6
10.530	36.7	10.924	41.7	11.349	46.7	11.809	51.7
10.537	36.8	10.932	41.8	11.358	46.8	11.819	51.8
10.545	36.9	10.941	41.9	11.367	46.9	11.828	51.9
10.552	37.0	10.949	42.0	11.376	47.0	11.838	52.0
10.560	37.1	10.957	42.1	11.385	47.1	11.848	52.1
10.568	37.2	10.965	42.2	11.394	47.2	11.857	52.2
10.575	37.3	10.974	42.3	11.403	47.3	11.867	52.3
10.583	37.4	10.982	42.4	11.412	47.4	11.877	52.4
10.591	37.5	10.990	42.5	11.421	47.5	11.886	52.5
10.599	37.6	10.998	42.6	11.430	47.6	11.896	52.6
10.606	37.7	11.007	42.7	11.439	47.7	11.906	52.7
10.614	37.8	11.015	42.8	11.447	47.8	11.915	52.8
10.622	37.9	11.023	42.9	11.456	47.9	11.925	52.9
10.629	38.0	11.032	43.0	11.465	48.0	11.935	53.0
10.637	38.1	11.040	43.1	11.475	48.1	11.945	53.1
10.645	38.2	11.048	43.2	11.484	48.2	11.954	53.2
10.653	38.3	11.057	43.3	11.493	48.3	11.964	53.3
10.661	38.4	11.065	43.4	11.502	48.4	11.974	53.4
10.668	38.5	11.074	43.5	11.511	48.5	11.984	53.5
10.676	38.6	11.082	43.6	11.520	48.6	11.994	53.6
10.684	38.7	11.090	43.7	11.529	48.7	12.004	53.7
10.692	38.8	11.099	43.8	11.538	48.8	12.014	53.8
10.700	38.9	11.107	43.9	11.547	48.9	12.023	53.9
10.707	39.0	11.116	44.0	11.556	49.0	12.033	54.0
10.715	39.1	11.124	44.1	11.566	49.1	12.043	54.1
10.723	39.2	11.133	44.2	11.575	49.2	12.053	54.2
10.731	39.3	11.141	44.3	11.584	49.3	12.063	54.3
10.739	39.4	11.150	44.4	11.593	49.4	12.073	54.4
10.747	39.5	11.158	44.5	11.602	49.5	12.083	54.5
10.755	39.6	11.167	44.6	11.612	49.6	12.093	54.6
10.763	39.7	11.175	44.7	11.621	49.7	12.103	54.7
10.771	39.8	11.184	44.8	11.630	49.8	12.113	54.8
10.779	39.9	11.193	44.9	11.639	49.9	12.123	54.9
10.787	40.0	11.201	45.0	11.649	50.0	12.134	55.0

Table 2
Correction Factor to Adjust Slurry Densities for Temperature

Temp (C)	Factor	Temp (C)	Factor
20	0.99927	61	1.01176
21	0.99944	62	1.01218
22	0.99962	63	1.01262
23	0.99981	64	1.01305
24	1.00000	65	1.01349
25	1.00002	66	1.01394
26	1.00041	67	1.01439
27	1.00063	68	1.01485
28	1.00085	69	1.01531
29	1.00109	70	1.01578
30	1.00132	71	1.01626
31	1.00157	72	1.01673
32	1.00182	73	1.01722
33	1.00208	74	1.01770
34	1.00234	75	1.01820
35	1.00261	76	1.01870
36	1.00289	77	1.01920
37	1.00318	78	1.01971
38	1.00347	79	1.02022
39	1.00376	80	1.02074
40	1.00407	81	1.02126
41	1.00438	82	1.02179
42	1.00469	83	1.02232
43	1.00501	84	1.02286
44	1.00534	85	1.02341
45	1.00567	86	1.02395
46	1.00601	87	1.02451
47	1.00635	88	1.02506
48	1.00670	89	1.02563
49	1.00706	90	1.02619
50	1.00742	91	1.02677
51	1.00779	92	1.02734
52	1.00816	93	1.02793
53	1.00854	94	1.02851
54	1.00892	95	1.02911
55	1.00931	96	1.02970
56	1.00970	97	1.03031
57	1.01010	98	1.03091
58	1.01051	99	1.03152
59	1.01092	100	1.03214
60	1.01134	101	1.03276

Slurry Worksheet

Date	Time	WPG Cup Weight Full Step (9)	WPG Cup Weight Empty Step (2)	Slurry Weight (Full-Empty) Step (11)	Slurry Density (Slurry Wt. x 0.10) Step (12)	Sample Temp. °C Step (10)	Temp. Correction Factor (Table 2) Step (13)	Adjust Density (Slurry Density x Temp. Corr. Factor) Step (14)	Percent Solids (Table 1)

**PORTLAND CEMENT CONCRETE
(J-15-0216)**

Paragraph 1. of Subsection 1002.02 in the Standard Specifications is amended to include the following:

Concrete mixes will be in accordance of Table 1002.02.

Paragraph 3. of Subsection 1002.02 is void and superseded by the following:

3. Type IP, IS and IT Interground/Blended cement shall be used for all classes of concrete except for pavement repair. Type IP, IS and IT Interground/Blended cement shall meet all requirements of ASTM C 595. Pavement repair shall include Type I/II Portland Cement for Class PR1 Concrete and Type III Portland Cement shall be used in Class PR3 Concrete.

Tables 1002.02 and 1002.03 in Subsection 1002.02 are void and superseded by the following:

ENGLISH
TABLE 1002.02

Class of Concrete (1)	Base Cement Type	Total Cementitious Materials Min. lb/cy	Total Aggregate		Air Content % Min.-Max. (2)	Coarse Aggregate (%)	Water/Cement Ratio Max. (3)	Required Strength Min. psi
			Min. lb/cy	Max. lb/cy				
47B**	IP/IS/IT*	564	2850	3150	6.5 - 9.0	-	0.45	3500
47B***		564	2850	3150	6.0 - 8.5	-	0.45	3500
47BD		658	2500	3000	6.0 - 8.5	30+3	0.42	4000
47B-HE		752	2500	3000	6.0 - 8.5	30+3	0.40	3500
BX(4)		564	2850	3150	6.0 - 8.5	-	0.45	3500
47B-OL****		564	2850	3200	5.0 - 7.0	30+3	0.36	4000
PR1		I/II	752	2500	2950	6.0 - 8.5	30+3	0.36
PR3	III	799	2500	2950	6.0 - 8.5	30+3	0.45	3500
SF(5)	I/II	589	2850	3200	6.0 - 8.5	50+3	0.36	4000

- (1) Each class of concrete shall identify the minimum strength requirement, per plans and specifications. All classes of concrete shall be air-entrained and a water-reducing admixture shall be used per manufacture's recommendations.
- Class R Combined Aggregate shall use a mid-range water reducer admixture. The dosage shall be at the manufacture's recommendation and the Engineer may approve a low-range water reducer admixture.
- (2) As determined by ASTM C 138 or ASTM C 231.
FOR INFORMATION ONLY. The Contractor may develop a Quality Control Program to check the quantity of air content on any given project; such as, checking the air content behind the paver.
- (3) The Contractor is responsible to adjust the water/cement ratio so that the concrete supplied achieves the required compressive strength without exceeding the maximum water/cement ratio. The minimum water/cement ratio for any slip form concrete pavement is 0.38, unless the Contractor requests approval from the Engineer in writing to change the minimum water/cement ratio to 0.36.
- (4) For temporary surfacing, Type I/II cement is allowed.
- (5) Minimum Portland Cement shall be 564 lbs/cyds and the total Silica Fume added shall be 25 lbs/cyds.

(*) Refer to Subsection 1004.02 for material characteristics.

Lithium Nitrate may be used in place of Supplemental Cementitious Materials (SCMs), see Section 1007 of the Standard Specifications as modified in these Special Provisions.

(**) For slip form applications.

(***) For hand-pours and substructures applications.

(****) When IP using Class N pozzolan, the maximum water/cement ratio is 0.41.

Table 1002.03	
Table of Acceptable Concrete Class Substitutions	
Class Specified	Acceptable Class for Substitution
BX	47B, 47BD or 47B-HE
47B	47BD or 47B-HE

Paragraphs 5., 6., 7., 8., 9. and 10. of Subsection 1002.02 are void and superseded by the following:

5. Class PR1 and PR3 Concrete:
 - a. The calcium chloride for use in PR concrete shall be either:
 - (1) A commercially prepared solution with a concentration of approximately 32 percent by weight.
 - (2) A Contractor prepared solution made by dissolving 4.5 pounds of Grade 2 or 6.2 pounds of Grade 1 calcium chloride per gallon of water to provide a solution of approximately 32 percent by weight.
 - b. The 7.4 pounds of water in each gallon of solution shall be considered part of the total water per batch of concrete.
 - c. The calcium chloride solution shall be added, just prior to placement, at a rate of 0.375 gallons/100 pounds of cement (1.4 lb. calcium chloride per 100 lb. cement).
 - d. Class A, Flaked or Pellet Calcium Chloride shall be added at a rate not to exceed 2.0 percent of the weight of the cement for Grade 1, or 1.6 percent of the weight of the cement for Grade 2. Grade 1 Calcium Chloride purity is between 70 and 90 percent and Grade 2 Calcium Chloride is between 91 and 100 percent.
 - e. Where mixing trucks are used:
 - (1) For Class PR3 Concrete, calcium chloride shall be thoroughly mixed into the concrete before placement. The minimum mixing time is 2 minutes.
 - (2) For Class PR1 Concrete, calcium chloride shall be added first and then the concrete mixed at least 2 minutes or as required by manufacturer. Next, the Type F high range water-reducer admixture is added and the concrete is mixed an additional 5 minutes.
6. Class High Early (47B-HE) Concrete
 - a. High Early (47B-HE) concrete shall be cured as prescribed in Subsection 603.03, Paragraph 7. The Contractor shall take necessary curing measures so the required strength is achieved.

- b. High Early concrete shall achieve a compressive strength of 3,500 psi at 48 hours after placement.
 - c. The 48-hour compressive strengths shall be used to determine pay factor deductions for high early concrete in accordance with Table 603.03.
 - d. A non-calcium chloride accelerator shall be used when the ambient temperature at the time of the placement of concrete is 70°F or less.
 - e. When requested by the Contractor, the maturity method, as provided in NDR C 1074, may be used in lieu of the requirements of Subsection 603.03, Paragraphs 11.c. and d. to determine the strength of concrete pavement for the purpose of early opening to traffic and acceptance. Requests by the Contractor for use of the maturity method shall be on a project basis and shall be made in writing to the Engineer.
7. The yield of the concrete proportions shall be determined and adjusted by the Producer.
8. All Classes of Concrete with the exception of PR1 and PR3 shall have a Durability Factor not less than 70 and a mass loss not greater than five percent after 300 freeze/thaw cycles when tested in accordance with ASTM C 666. The freeze/thaw testing shall be conducted according to Procedure A.

Paragraphs 1. & 2. of Subsection 1002.03 are void and superseded by the following:

- 1. The Contractor shall identify the plant that will supply the concrete 14 days before use and be entirely responsible for its calibration, batching of concrete, aggregate and sampling of cement per NDR Sampling Guide.
 - a. The Contractor shall be responsible for the following:
 - 1) Batching concrete.
 - 2) Contractor shall sample aggregate from the conveyor belt or stockpile. Gradations from a split sample shall be tested in accordance to Section 1033 and reported to the Engineer at the frequency required by the Materials Sampling Guide.
 - i. Contractor shall retain possession of the split samples on-site at the Contractor's facility until such a time as determined by the Engineer.
 - a. At the pre-construction meeting:
 - 1) Contractor shall determine the location of testing and report the names of the technician performing the sampling and testing.
 - 2) Engineer will notify the Contractor of the retrieval of the split samples.

- ii. The Contractor shall split the sample, place the Department's split sample into a cloth bag and immediately seal the split sample with the provided security seal. The cloth sample bag shall be supplied by the Department.
 - iii. The sampling splitting and placement of the security seal of aggregate samples shall be witnessed by certified Department personnel.
 - iv. Contractor shall secure the split sample using a consecutively numbered security seal of 75 pounds breaking strength provided by the Department. The Contractor shall use the consecutively numbered security seals to identify and track each Aggregate Class. Samples that are not consecutively numbered will be investigated for custody of the sample and the Engineer may cease production until it is determined what action will be required.
 - a. The Contractor shall report the security seal tracking number with the split sample gradation.
 - b. The following training shall be required for personnel who oversee the batching of the concrete:
 - 1) Concrete Technician Personnel
 - i. Concrete Plant Technician
 - 2) Portland Cement Sampler
 - i. NDR Portland Cement Sampler
2. Portland Cement Concrete shall be supplied by certified Ready Mix Plants that are in compliance with the requirements in the *Quality Control Manual*, Section 3, -- Certification of Ready Mixed Concrete Production Facilities published by the National Ready Mixed Concrete Association. Refer to NDR Material Sampling Guide for the policy on stationary and portable plants.

Paragraph 4. of Subsection 1002.03 is void and superseded by the following:

- 4. a. Mix times shall meet the requirements of ASTM C 94. Mixing time tests shall be repeated whenever the concrete appearance indicates that mixing was inadequate.
- b. Batch plants that are transporting the concrete in non-agitating trucks, the mixing time will not be less than 60 seconds, and for agitating trucks, the mixing time will not be less than 45 seconds.

- c. The Certification of stationary and portable ready mix plants will conform to the tests that are required in the NDR Materials Sampling Guide.

Paragraph 6. of Subsection 1002.03 is void and superseded by the following:

6. Batch tickets shall be prepared as prescribed in the National Ready Mixed Concrete Association's *Quality Control Manual*. The Contractor shall keep all gradations and batch tickets until final acceptance by the Department. Projects that have less than 200 cubic yards of concrete placed will be allowed to have hand written tickets. For projects greater than 200 cubic yards, hand written tickets will be at the Engineer's discretion. The concrete batch tickets shall show batch weights, aggregate moisture (shall be tested daily and moisture probes are allowed), admixtures used, water, and mix design calculations. A copy of the batch ticket shall be given to the Engineer upon delivery of concrete.

Paragraph 8. of Subsection 1002.03 is void and superseded by the following:

8. Coarse aggregate from a dry pit shall be uniformly saturated with water before it is used. The wetting shall begin 24 hours prior to the concrete mixing to allow complete saturation.

Paragraph 13.a. of Subsection 1002.03 is void and superseded by the following:

13. a. The quantity of water shall be determined by the Contractor. The minimum quantity of water should be used which will produce required workability. Any additional water used to rinse the charging hopper and fins after the batching of concrete is allowed. This water must be estimated and recorded on the batch ticket.

Subsection 1002.04 is void and superseded by the following:

1. Class 47B Concrete Mix Design Submittal:
 - a. The Contractor shall submit the Concrete Mix Design Worksheet consisting of design mix proportions, testing of mix design from a minimum of 4 cubic yards and aggregate data for 47B class of concrete being placed on the project.
 - (1) All testing must be performed by a qualified laboratory found on the NDR's Material and Research website, under the *Nebraska Qualified Consultant & LPA Laboratories* and submitted to the Engineer.
 - (2) The Concrete Mix Design shall be submitted to the Engineer 4 weeks prior to any concrete being placed on the project.
 - (3) The Concrete Mix Design shall not be paid for directly by the Department and shall be subsidiary to items which direct payment is made.

- (4) Concrete shall not be placed on the project before the Concrete Mix Design Worksheet has been reviewed and approved by the Engineer.
- b. The Contractor shall submit the Concrete Mix Design Worksheet to the Engineer. Email submissions are preferred but will be accepted by fax or postal mail.
- (1) Contractor's Mix Design Worksheet can be found on the Materials and Research website. The submitted Mix Design Worksheet shall include the following:
 - Contractor Name
 - Project Number
 - Date
 - Location of ready mix or central mix plant
 - Date submitted
 - Signature of Contractor representative
 - (2) Material Source Information.
 - Cement Manufacturer
 - Type of Interground/Blended Cement
 - Type of Admixtures
 - Aggregate Pit and Quarry location
 - (3) Specific Gravity of each individual aggregate source.
 - (4) Sand Equivalent for dry pit sand-gravel aggregate.
 - (5) Combined Aggregate percent passing as described on Table 1033.03C.
 - (6) Contractor's Target combined aggregate gradation percent passing.
 - (i) The Contractor's required worksheet can be found on the Materials and Research website.
 - (7) Testing of Mix Design:

The mix design shall show the weights of all ingredients including Interground/Blended cements, aggregates, water, admixtures types and water cement ratio.

 - Temperature of concrete at time of sampling, ASTM C 1064.
 - The air content of plastic concrete, ASTM C 231.

- Weight per cubic foot, Yield, ASTM C 138. The relative Yield shall be a minimum of 97%.
 - Compressive strength shall be performed with a minimum of three averaged specimens at 7-day and 28-day, ASTM C 39. The minimum 28-day compressive strength shall be 3500 psi.
- (8) Traditional 47B Mix Design is defined as a 70 percent Class B Aggregate and 30 percent Class E Aggregate may be exempt from the concrete testing described in Paragraph 1.(b)(7). All other requirements shall be included in the Concrete Mix Design Report.
- c. The PCC Engineer will notify the Contractor of the mix design approval for Class 47B Concrete. Approval of the mix design does not alleviate the Contractor of the responsibility of the in-place concrete. The Contractor may adjust admixtures, water cement ratio, vibrator frequency, etc., as needed in accordance to the specifications.
- d. The Contractor shall submit a new concrete mix design worksheet meeting the above requirements when a change occurs in the source, type, or proportions of cements or aggregates; unless otherwise approved by the Engineer.
2. The quantity of water to be used shall be determined by the Contractor. It shall not be varied without the Engineer's consent.
3. If the concrete mixture is excessively wet causing segregation, excessive bleeding, excessively dry or any other undesirable condition, the concrete shall be rejected. At the option of the Engineer, slump tests may be performed to determine the consistency.
4. Concrete which has developed initial set before it is consolidated and finished shall be rejected.
5. a. If false set is encountered, the batching operation shall be stopped until the problem is resolved.
- b. Each batch must be mixed or agitated for at least 3 additional minutes after observing the false set and the concrete must be of satisfactory consistency.
6. Compressive strength tests shall be made in accordance with ASTM C 39.
7. Concrete shall be sampled as prescribed in the NDR *Materials Sampling Guide*. Samples shall be taken at the point of placement, never before the discharge from the last conveyance.

8. Aggregate Acceptance, Verification, Sampling and Testing:

- a. The aggregate will be accepted based on the Contractor's testing results except as noted below.
- b. The aggregate verification sampling and testing by the Department will be randomly selected and tested according to subplot sizes in Table 1002.05.

Table 1002.05

Aggregate Class	Lot	Sublot
E and F	3000 tons	1000 tons
A,B and C	6000 tons	2000 tons
R	6000 tons	2000 tons

- c. The results of Contractor split sample will be verified by the Department's verification tests. Any samples outside of the tolerances as specified according to the Materials Sampling Guide, Section 28 under the *Acceptable Tolerance Limits for Independent Assurance* will result in an Independent Assurance (IA) review of testing and may result in the Department test results being applied.
- d. On any given Lot, if the results of the gradation from the verification test are within Department's specification, the Contractor's results will be used for the entire lot. On any given Lot, if the gradations results from the verification test are outside Department's specification, further investigation will be initiated by the Engineer for that subplot. Any or all of the remaining Department subplot samples may be tested and the Department subplot test results may be applied to the respective subplot and the acceptance will apply.
- e. When verification tests are within testing tolerance but results show a consistent pattern of deviation from the split sample results, the Engineer will exercise one or more of the following:
 - Cease production.
 - Request additional verification testing.
 - Initiate a complete IA review.
- f. Independent Assurance (IA) Review of Testing:
 - 1) The Contractor shall allow the Department personnel access to the Contractors' laboratory to conduct IA review of the technician testing procedures and apparatus. Any deficiencies discovered in the Contractor's testing procedures will be reported to the Contractor and corrected by the Contractor.
 - 2) During the IA review, the Department personnel and the Contractor shall split a sample for the purpose of IA testing. The samples selected will be tested in the Department's Branch Laboratory. Any IA test results found to be outside of defined

testing tolerances as stated in Paragraph 8.c. of Subsection 1002.04 will be reported to the Contractor. The Contractor shall immediately correct any deficiencies found during the IA review.

- 3) If the project personnel and the Contractor cannot reach agreement on the accuracy of the test results, the Department Central Laboratory will be asked to resolve the dispute, which will be final. All dispute resolutions will be in accordance with the Quality Assurance Program requirements in the NDR's Materials Sampling Guide.

PORTLAND AND INTERGROUND/BLENDED CEMENT (J-15-0216)

Section 1004 in the Standard Specifications is void and superseded by the following:

1004.01 – Description

1. Portland cement is the binder in concrete, locking the aggregate into a solid structure. It is manufactured from Lime, Silica, and Alumina (with a small amount of plaster of Gypsum).
2. Equivalent alkali referred to herein is hereby defined as the sum of the Sodium Oxide (Na_2O) and the Potassium Oxide (K_2O) calculated as Equivalent Alkali $\text{Na}_2\text{O}_e = \text{Na}_2\text{O} + 0.658 \text{K}_2\text{O}$.
3. Interground and Blended cements consist of intimate and uniform intergrinding or blending of Portland cement clinker, Slag cement, Pozzolan and/or Limestone.

1004.02 – Material Characteristics

1. Type I, Type II, Type I/II and Type III Portland cement shall conform to the requirements in ASTM C 150 with the following additional requirements:
 - a. Portland cement shall not contain more than 0.60 percent equivalent alkali.
2. Interground and Blended Cement shall conform to the requirements in ASTM C 595 with the following additional requirements:
 - a. Interground/Blended cement (Type IP)
 - (1) For Type IP(25) shall be composed of Class F fly ash or Class N pozzolan replacement shall be $25\% \pm 2\%$.
 - (2) For Type IP(20) shall be composed of Class F fly ash or Class N pozzolan replacement shall be $20\% + 2\%$.

- b. Interground/Blended cement (Type IS)
 - (1) For Slag Cement, the maximum replacement shall be 35% +5 when incorporated into the final Interground/Blended cement.
- c. Interground/Blended cement (Type IT)
 - (1) For SCMs, Slag cement and Limestone, the maximum replacement by weight shall be 40%. The manufacturer has a production tolerance of $\pm 2\%$ from the proposed replacement.
 - (2) For Limestone cement, the replacement range shall be from 5.1% to 10.0% when incorporated into the final Interground/Blended cement.
- d. No additional SCMs, Slag cement and Limestone will be added at the batch plant.

1004.03 – Procedures

- 1. The Contractor shall provide adequate protection for the Portland and Interground/Blended cement against dampness.
 - a. Portland and Interground/Blended cement shall be hauled or stored in railroad cars, dry bulk trailers or in suitable moisture-proof buildings.
 - b. The use of tarpaulins for the protection of the Portland and Interground/Blended cement against moisture will not be allowed.
- 2. No Portland and Interground/Blended cement which has become caked or lumpy shall be used.
- 3. Portland and Interground/Blended cement which has been spilled shall not be used.
- 4. Accepted Portland and Interground/Blended cement which has been held in storage at the concrete mix plant more than 90 days shall be retested.
- 5. Portland and Interground/Blended cement coming directly from the manufacturer shall not be used until the temperature is 150°F or less.
- 6. Portland cement having false set when tested in accordance with in ASTM C 150 will not be used.

1004.04 – Acceptance Requirements

- 1. For Department projects, Portland and Interground/Blended cements must be on the NDR Approved Product List (APL).

2. The Contractor shall submit any new Portland and Interground/Blended cements to the Engineer to be approved for the APL with the following:
 - a. Material source information:
 - 1) Mill Location
 - 2) Type of Portland and Interground/Blended cements
 - 3) Grinding Period
 - 4) Associated Manufacture Product Name
 - 5) Provide source and type of each SCMs and/or Slag Cement used for final product.
 - (i) The Department will allow the use of ASTM C 1697.
 - a. When two or more SCMs and/or Slag Cement are pre-blended, the Contractor shall report chemical composition analysis of the final blend.
 - b. The final blend shall be reported as per ASTM C 1697, Paragraph 4.
 - 6) Portland cement shall conform to ASTM C 150.
 - 7) Interground/blended cements shall conform to ASTM C 595.
 - 8) Provide total cementitious materials replacement per ASTM C 595.
 - 9) Report test results per ASTM C 1567 at 28-days.
3. Alkali Silica Reaction Requirements and Testing:
 - a. Interground/Blended cement shall be tested according to the provisions of ASTM C 1567.
 - (1) The mortar bars shall be composed of Type IP, IS or IT Interground/blended cement and sand and gravel from an approved Platte River Valley-Saunders County source.
 - i. When Elkhorn River-Madison County source or an out of state aggregate source is being used on a project, the Elkhorn River or an out of state aggregate source shall be used in lieu of the Platte River Valley-Saunders County source.
 - ii. When Contractor proposes a change of aggregate source, then the new aggregate source shall be tested by ASTM C 1567.
 - (2) The mortar bars for the ASTM C 1567 shall not exceed 0.10% expansion at 28 days.

4. Portland and Interground/Blended cements will be placed on NDR's APL based on the conformance with the NDR's Acceptance Policy Portland and Interground/Blended Cements.

1004.05 - Sampling and Testing Requirements

1. All Portland and Interground/Blended cements shall be sampled and tested at the rate as described in the NDR's Materials Sampling Guide.
 - a. The Department will inform the Contractor when a sample is required.
 - b. A sample shall be taken by a Contractor's Certified Portland Cement Sampler and must be under the supervision of Department certified personnel.
 - c. The sample shall be taken at the plant from a bulk shipment of a rail car, dry bulk trailer, batch plant silo or from the line between the bulk truck and the silo. Upon sampling, the Department will take immediate custody of the sample.
2. Noncompliant material shall be tested in accordance with ASTM C 1567 and in accordance with Section 1004.04, Paragraph 3.a. (1).
 - i. The mortar bars for the ASTM C 1567 shall not exceed 0.10% expansion at 28 days.
 - ii. If the expansion is greater than 0.10% at 28 days, then the Interground/Blended cement shall be subject to removal, 40% pay and/or removal from NDR's APL in accordance with NDR's Acceptance Policy on Portland and Interground/Blended Cements.
3. Noncompliant material from the mill, terminal or project will be temporarily removed from the Approved Products List pending further investigation.
4. If the noncompliant Portland or Interground/Blended cement is removed from the Approval Products List, all shipments from the supplier will be held until the investigation of the failing samples have been completed by the NDR Materials and Research Division.

WATER FOR CONCRETE (J-15-0214)

Section 1005 in the Standard Specifications is void and superseded by the following:

1005.01 – Description

1. Water shall be free from objectionable quantities of oil, acid, alkali, salt, organic matter, or other deleterious materials and shall not be used until the source of supply has been approved.

2. Wash water from the mixer washout may be used only with the Engineer's approval. Use of wash water will be discontinued if undesirable reaction with admixtures or aggregates occurs.

1005.02 – Material Characteristics

1. Water which contains more than 0.25 percent total solids by weight shall not be used.
2. When required by the Engineer, the quality of mixing water shall be determined by NDR C 114, NDR T 290, NDR D 512, NDR C 1602, ASTM C 31, ASTM C 109, ASTM C 191, and ASTM C 1603.
3. Upon written request by the concrete producer and approval by Materials and Research, the concrete producer may utilize up to 10% wash water for batching all classes of concrete with the following conditions:
 - a. Wash water shall conform to the requirements in NDR's Material Sampling Guide under Policy for Certification of Ready Mix Plants.
 - b. Wash water must be clarified wash water that has been passed through a settling pond system.
 - c. Wash water must be scalped off of a settling basin that has been undisturbed for a minimum of 12 hours.
 - d. Wash water must be metered into each load.
 - e. Wash water quantities shall be shown on the batch ticket.

CALCIUM CHLORIDE (J-15-0214)

Section 1006 of the Standard Specifications is void and superseded by the following:

1006.01 – Description

Calcium Chloride shall be Type S (Solid) or Type L (Liquid). Calcium Chloride can be used for; but not limited to, dust control and acceleration of the set of concrete.

1006.02 – Material Characteristics

The requirements for calcium chloride shall be tested in accordance with ASTM D 98.

1006.03 – Acceptance Requirements

Acceptance shall be based on requirements contained in the NDR Materials Sampling Guide.

**SECTION 1007 -- CHEMICAL ADMIXTURES
(J-15-0214)**

Section 1007 in the Standard Specifications is void and superseded by the following:

1007.01 -- Description

1. Admixtures are materials added to Portland cement concrete to change characteristics such as workability, strength, permeability, freezing point, and curing.
2. The Department's concrete admixture types are:
 - a. Type A - Water-Reducing Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump.
 - b. Type B - Retarding Admixture - An admixture that slows the setting of concrete.
 - c. Type C - Accelerating Admixture - An admixture that speeds the setting and early strength development of concrete.
 - d. Type D - Water-Reducing and Retarding Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump and slows the setting of concrete.
 - e. Type E - Water-Reducing and Accelerating Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump and speeds the setting and early strength development of concrete.
 - f. Type F - Water-Reducing, High Range Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump by 12 percent or greater.
 - g. Type G - Water-Reducing, High Range and Retarding Admixture - An admixture that reduces the quantity of mixing water required to produce concrete of a given slump by 12 percent or greater and slows the setting of concrete.
 - h. Air-Entraining - An admixture that encapsulates air in the concrete.
 - i. Lithium Nitrate – An admixture used to control the Akali Silica Reaction (ASR) in concrete.

1007.02 -- Material Characteristics

1. Type A through G admixtures shall meet the requirements in ASTM C 494.
2. Air-entraining admixtures shall meet the requirements in ASTM C 260.
3. Use of admixtures other than those cited may be requested by the Contractor.
4. Admixtures shall not contain more than 1 percent of chlorides calculated as calcium chloride unless specified otherwise in the Specification.

5. Admixtures shall be used at the manufacturer's recommended dosage rates.
6. The air-entraining admixture characteristics shall produce concrete with satisfactory workability and total air content as prescribed in Table 1002.02.
7. a. When using the Lithium Nitrate admixture, the Contractor shall submit to the Engineer:
 - (i) A five pound sample of Portland cement that will be used on the project.
 - (ii) The Manufacturer's method for determining the recommendation for the required dose rate based on the equivalent alkali content.
 - (iii) Water content of the Lithium Nitrate admixture solution.
- b. The Engineer will report the equivalent alkali content to the Contractor. The Contractor shall use the reported equivalent alkali content to determine the required dose rate based on the manufacturer's recommendation.

1007.03 -- Procedures

1. The process for adding admixtures to a ready mix truck on the project site involves positioning the load of concrete up to the truck chute, stopping short of discharge.
 - a. The admixture is then poured over the surface of the concrete and mixed for at least 5 minutes.
 - b. No more than 1.3 gallons of water shall be used to rinse the admixture from the fins and top chute. This water must be shown on the proportioning report and shall not exceed the water cement ratio.
 - c. When Lithium Nitrate is used, the portion of the admixture that is water will be shown on the proportioning report and shall not exceed the water cement ratio.
 - d. The Contractor is responsible for the addition of the admixture.
2. a. If the air content is less than the minimum specified, addition of air-entraining admixtures is allowed.
- b. The Contractor shall take measures based on manufacturer's recommendations that are within compliance of NDR Specifications, to bring the load of concrete into NDR prescribed limits according to Table 1002.02.
- c. If the air content is then outside the limits in Table 1002.02, the load of concrete shall be rejected.

1007.04 -- Acceptance Requirements

1. a. Approved chemical admixtures are shown on the NDR Approved Products List.
- b. Admixture approval shall be based upon annual certifications and certified test results submitted to the NDR Materials and Research Division.

2. The admixture must be essentially identical in concentration, composition, and performance to the admixture tested for certification.
3. Admixtures not identified on the NDR Approved Products List may be used under the following conditions:
 - a. A certificate of compliance and certified test results must be submitted to the NDR Materials and Research Division and approval for use must be given by the NDR Materials and Research Division.

**SILICA FUME
(J-15-0307)**

Paragraph 2 of Subsection 1009.03 in the Standard Specifications is void and superseded by the following:

2. Silica fume shall be protected from temperatures in excess of 90°F (32°C).

**LIQUID MEMBRANE-FORMING COMPOUNDS FOR CURING CONCRETE
(J-15-0307)**

Subsection 1012.03 in the Standard Specifications is void and superseded by the following:

1012.03 – Acceptance Requirements

1. All curing compounds to be approved must be from the current calendar year with no carry-over from the previous years.
2. Approved compounds are on the NDR Approved Products List.
3. Products not on the NDR Approved Products List shall be sampled and tested in accordance with requirements of the NDR Materials Sampling Guide.

**BITUMINOUS LIQUID COMPOUNDS FOR CURING CONCRETE
(J-15-0515)**

Section 1013 in the Standard Specifications is void and superseded by the following:

1013.01 – Description

The compound shall consist essentially of an asphaltic base and shall be of a consistency suitable for spraying at temperatures existing at the time of construction operations. It shall form a continuous, uniform film. It shall be free of precipitated matter caused by conditions of storage or temperature. The compounds shall be relatively nontoxic.

1013.02 – Material Characteristics

- a. When tested in accordance with AASHTO T 155, the loss of water shall not be more than 0.11 lb/ft² (0.55 kg/m²) of surface area at 3 days, unless otherwise specified by the Engineer.
- b. The Contractor has the option of using bituminous tack coat. The tack coat shall conform to all requirements of Section 504.
- c. The base material shall conform to Sections 1030, 1031 and 1032.

1013.03 – Acceptance Requirements

Products shall be sampled and tested in accordance with requirements of the NDR Materials Sampling Guide.

JOINT AND CRACK SEALING FILLER (J-15-0813)

Section 1014 in the Standard Specifications is void and superseded by the following:

1014.01 – Description

Joint sealing filler shall be either a cold applied silicone product or an asphalt product (hot pour) conforming to the requirements of this Section. The type of joint filler to be used shall be as specified in the plans or special provisions. If not specified, any of the joint sealing fillers in this Section may be used.

Crack sealing filler shall be a hot pour sealer conforming to the requirements of this Section.

1014.02 -- Material Characteristics

1. NE-3405 and NE-3405LM (hot pour)
 - a. NE-3405 joint and crack sealer shall conform to the requirements of ASTM D6690, Type II. The material shall conform to the requirements of Table 1 with the following exception:
 - (i) The test of Bond, non-immersed, ASTM D5329, 3 specimens through 3 cycles shall be run at 0°F (-18°C), 100% extension.
 - b. NE-3405LM (Low Modulus) joint and crack sealer shall conform to the requirements of ASTM D6690, Type IV. The material shall conform to the requirements of Table 1.
 - c. The test of Bond, non-immersed, ASTM-D5329, will be tested on concrete blocks that will be constructed by the NDR Concrete Laboratory. The concrete blocks will be made of a 47B concrete mixture as prescribed in Section 1002 in the NDR Standard Specifications. The design is amended so that no fly ash is used in the mixture. All other specifications for Portland Cement Concrete apply.

- d. Sample conditioning, preparation and heating shall be in accordance with ASTM D 5167 with the following exceptions:
- (i) The following sentence of Section 8.1.2, “Also, if present, remove container liner by cutting it away”, is void and superseded by the following:

“Also, if present, as much of the polyethylene bag as possible, shall be removed by cutting it away. Wholly-meltable type container in contact with the sample section shall be left in place.”
 - (ii) The last sentence of Section 8.1.2 “Solid Materials” is void and superseded by the following:

The entire vertical section which has been cut, shall be placed into the pot for melting.
 - (iii) The Section of 8.2.2.1 “Solid Materials” is void.
 - (iv) The Section of 8.2.3 is void and superseded by the following:

After the solid segment is added to the melter, the material shall be allowed to minimally melt to a uniform viscous state suitable for the installation of the stirrer or paddle. The sample shall then be stirred for one full hour. The oil bath temperature shall be regulated to bring the material to the maximum heating temperature within the one hour of stirring.
 - (v) The Section of 8.2.4.1 is void and superseded by the following:

During the one full hour of stirring, check the temperature of the material at maximum 15 minute intervals using a Type K thermocouple with the calibration verified in accordance with Section 6.1.7 to ensure conformance with specified temperature requirements. Stop the mechanical stirrer when measuring temperatures. If material temperatures ever exceed the maximum heating temperature, or ever drop below the minimum application temperature after the maximum heating temperature was reached, discard the sample and re-do the heating. Maintain appropriate records of times and temperatures to verify conformance with specification requirements.
 - (vi) The Section of 8.2.4.2 is void.
- e. ASTM D 5329 shall include the following changes:
- (i) Sections 6.4 and 12.4 “Specimen Preparation” shall have the reference of “177 ml (6 oz.)” replaced with “3 oz.”

(ii) Section 6 “Cone Penetration, Non-Immersed” shall be superseded with the following exceptions:

1. Section 6.5 “Procedure” is void and superseded by the following:

Place the specimen in a water bath maintained at 77 +/- 0.2°F (25 +/- 0.1°C) for two hours immediately before testing. Remove the specimen from the bath and dry the surface by shaking gently to remove free water from the surface of the specimen. Using the apparatus described in Section 6.3, make one determination at or near the center of the specimen. Take care to ensure the cone point is placed on a point in the specimen that is representative of the material itself, and is free of dust, water, bubbles, or other foreign material.

2. Section 6.6 “Report” is void and superseded by the following:

Record the value as penetration of the specimen in dmm units.

(iii) Section 12 “Resilience” shall be superseded with the following exceptions:

1. Section 12.5 “Procedure”, void the sentence “Make determinations at three points equally spaced from each other and less than 13mm (½ inch) from the container rim” and supersede with the sentence “Make one determination at or near the center of the tin.”

2. Section 12.6 “Report” is void.

2. Silicone Joint Sealer (cold applied)

a. Silicone joint sealers may be either self-leveling or non-sag and shall meet the requirements in Table 1014.01.

Table 1014.01

Silicone Joint Sealer Requirement		
Property	Requirement	Test
As supplied:		
Specific Gravity	1.010-1.515	ASTM D792
Work Time, minimum	10 minutes	
Tack-Free, at 25°C	20-360 minutes	
Cure Time, at 25°C, maximum	14 days	
Full Adhesion, maximum	21 days	
As cured, at 25°C + 1.5		
Elongation, minimum	800%	ASTM D412
Durometer		
Non-Sag, Shore A	10-25	ASTM D2240
Self-Leveling, Shore 00, minimum	40	ASTM D2240
Joint Movement Capacity	+100% to -50%	ASTM C719
Tensile Stress, at 150% Elongation	45 psi	ASTM D412

1014.03 -- Packaging

1. NE-3405 and NE-3405LM
 - a. The joint and crack sealer can be packaged in either cardboard box of wholly-meltable type containers.
 - (i) Cardboard box containers shall be manufactured from double wall kraft board producing a minimum bursting test certification of 350 PSI (241 N/cm²) and using water-resistant adhesives. The use of metal staples or fasteners of any kind will be prohibited for closing the lids of the boxes. Tape or other like material is acceptable.
 - a. The joint and crack sealer shall be in meltable [300°F (149°C)] polyethylene bag(s).
 - (ii) Wholly-meltable type containers, and any of their components, shall be fully meltable and integrational with the joint and crack sealer by the time the manufacturer's minimum application temperature is reached.
 - a. The wholly-melted and integrated container must not adversely affect the test specifications of the joint and crack sealer.
2. Silicone Joint Sealer
 - a. Each container shall include information regarding manufacturer and product name.

1014.04 -- Acceptance Requirements

1. NE-3405 and NE-3405LM
 - a. Acceptance of the manufactured material is based on pre-approval by either on or off-site sampling. Acceptable hot pour sealant lots are listed on the NDR Approved Products List.
 - (i) NDR on-site field sampling shall be in accordance with the NDR Materials Sampling Guide.
 - (ii) Off-site (Proxy) sampling shall be in accordance with ASTM D 6690.
 1. Proxy sampling shall be overseen by an outside party approved by the NDR, preferably another DOT Agency. Proxy samples shall include a manufacturer's Certificate of Compliance. Proxy samples shall also include a dated signature of origin by the Representative that is not affiliated with the manufacturer, and can either be on the Certificate of Compliance, or separate letter.
 2. For convenience in both sampling and shipping samples, sample containers smaller than a manufacturer's usual production containers are allowed, as long as the sample is 1500 grams min.

3. Samples shall be sent to the NDR Bituminous Laboratory, or alternatively, sent to an NDR-approved independent laboratory for testing which will be at no cost to the Department. If a NDR-approved independent laboratory will be used for testing purposes, the NDR Bituminous Laboratory must be notified so that NDR concrete blocks for Bond testing can be sent to it.
2. Silicone Joint Sealer
 - a. Acceptance of applied silicone joint sealers shall be in accordance with the NDR *Materials Sampling Guide*.
 - b. Acceptable silicone joint sealer manufacturer products are listed on the NDR Approved Products List.
 - (i) For products that are not listed, approval may be based upon test results from an independent laboratory submitted to the NDR Concrete Materials Section by the manufacturer, and testing by the NDR. Approval must be made prior to product use.

EPOXY COMPOUNDS AND ADHESIVES (J-15-0308)

Section 1018 in the Standard Specifications is void and superseded by the following:

1018.01 – Description

This specification provides requirements for two-component, epoxy-resin bonding systems for use in non-load bearing applications and resin adhesives for application to Portland cement concrete.

1018.02 – Material Characteristics

1. Epoxy-resin bonding systems shall conform to the requirements of ASTM C 881. Approved systems are shown on the NDR Approved Products List.
2. The classification of Epoxy-Resin Bonding Systems is as follows:
 - a. Type I For use in non-load bearing applications for bonding hardened concrete and other material to hardened concrete.
 - Type II For use in non-load bearing applications for bonding freshly mixed concrete to hardened concrete.
 - Type III For use in bonding skid resistant materials to hardened concrete, and as a binder in epoxy mortars or epoxy concretes.

- b. Grade 1 Low viscosity.
- Grade 2 Medium viscosity.
- Grade 3 Non-sagging consistency.
- c. Class A For use below 40°F (4°C); the lowest allowable temperature to be defined by the manufacturer of the product.
- Class B For use between 40°F and 60°F (4°C and 15°C).
- Class C For use above 60°F (15°C); the highest allowable temperature to be defined by the manufacturer of the product.
- Class D For use between 40°F and 65°F (4°C and 18° C).
- Class E For use between 60°F and 80°F (15°C and 26°C).
- Class F For use between 75°F and 90°F (24°C and 32°C).

1018.03 – Procedures

1. The compounds shall be of the type and grade specified in the plans or as directed by the Engineer.
2. The class of the compounds shall be selected for use according to climatic conditions at the time of application.
3. All bonding surfaces shall be clean and free of all oil, dirt, grease, or any other materials which would prevent bonding.
4. Mixing and application shall be in strict accordance with the manufacturer's instructions.

1018.04 – Acceptance Requirements

1. Epoxy-resin bonding systems and resin adhesives approved for use are shown on the NDR Approved Products List.
2. Epoxy-resin bonding systems that are not on the NDR Approved Products List may be accepted based on a manufacturer's certificate of compliance.

**DEFORMED METAL CENTER JOINT AND METAL KEYWAY
(J-15-0307)**

Paragraph 1 a. of Subsection 1027.01 in the Standard Specifications is void and superseded by the following:

a. Metal Center Joint:

Metal center joint sections shall be manufactured from sheets no less than 18 gauge [0.05 inch (1.3 mm)] thick and shall be of the size and trapezoidal shape shown in the plans. The sections shall be punched along the centerline of the narrow face of the trapezoid to admit the tie bars required by the plans and also at intervals of not greater than 2 feet (600 mm) to receive pins that are driven vertically into the subgrade to support the metal center joint.

**AGGREGATES
(J-15-0616)**

Subsection 1033.01 is amended to include the following paragraphs and Subsection 1033.02, Paragraphs 1., 2. and 3. of the Standard Specifications are void and superseded by the following:

1033.01 – Description

This combined aggregate gradation using Class R aggregate is to optimize aggregate blends utilizing more locally available materials.

Achieving a uniform gradation for Class R may require the use of two or more different aggregates. It is the responsibility of the contractor to consider additional material characteristics; such as, but not limited to particle shape, cubicity, angularity, etc., when designing a mix.

1033.02 -- Material Characteristics

1. Sampling and Testing Procedures:

All materials shall be sampled and tested in accordance with Table 1033.01. All material source locations and quarries must be approved by the Department for prior to use.

Table 1033.01

Sampling and Testing Procedures	
Procedure	Method
Sampling	NDR T 2
Sieve Analysis	NDR T 27
Clay Lumps, Shale, and Soft Particles	NDR T 504
Abrasion	AASHTO T 96
Freeze and Thaw Soundness	NDR T 103
Specific Gravity and Absorption (course aggregate)	AASHTO T 85
Specific Gravity and Absorption (fine aggregate)	AASHTO T 84
Total Evaporable Moisture Content of Aggregates by Drying	AASHTO T 255
Plastic Fines in Graded Aggregates and Soils by Use of the Sand Equivalent Test	AASHTO T 176
Sodium Sulfate Soundness	AASHTO T 104
Calcium Carbonate	NDR C 25
Organic Impurities	AASHTO T 21
Mortar-Making Properties	AASHTO T 71
Reducing Field Samples of Aggregate to Testing Size	AASHTO T 248
Lightweight Pieces in Aggregates	NDR T 113

2. General Aggregate Properties:

- a. Aggregates shall be free from injurious quantities of dust, soft or flaky particles, loams, alkali, organic matter, paper, wood or other deleterious matter as determined by the Engineer.
- b. Dolomite as herein defined is a magnesium limestone containing calcium carbonate and magnesium carbonate in approximately a 4 to 3 ratio.
- c. The calcium carbonate content of limestone shall be at least 80 percent (computed as CaCO_3 from the value determined for CaO).
- d. Fine Sand shall have at least 95 percent of its particles pass the No. 10 (2.0 mm) sieve and no more than 25 percent pass the No. 200 (75 μm) sieve. This definition applies to sodium sulfate soundness test.
- e. Once an aggregate's soundness and abrasion quality has been determined, additional quality testing for soundness and abrasion loss will be at the Engineer's discretion.
- f. All aggregates or combine aggregates that have been washed or coming from a wet pit shall be stockpiled for a minimum of 48 hours before being introduced into concrete.

3. Portland Cement Concrete Aggregates:**a. Fine Aggregate:**

- (1) Aggregate shall be washed and composed of clean, hard, durable and uncoated particles.
- (2) Aggregates produced from wet pits by pumping must be adequately washed by means approved by the Department.
- (3) Aggregates from dry pits shall be adequately washed by means approved by the Department and have a Sand Equivalent value not less than 90 in accordance with AASTHO T 176.
 - (i) If the Sand Equivalent is less than 90, the Engineer may elect to stop aggregate production until such a time ASTM C 109 has been completed. The aggregate, when subjected to the test for mortar-making properties, shall produce a mortar having a compressive strength at the age of 7 days equal to or greater than that developed by mortar of the same proportions and consistency made of the same cement and aggregate after the aggregate has been washed to a sand equivalent greater than 90. Materials failing to produce equal or greater strength shall be unacceptable.
- (4) Aggregate for concrete shall have a soundness loss of not more than 10% by weight at the end of 5 cycles using Sodium Sulfate Soundness test AASHTO T 104.
- (5) The weight of the aggregate shall not contain more than 0.5% clay lumps.
- (6) Aggregate subjected to the colorimetric test for organic impurities which produces a color darker than the standard shall be further tested for its mortar-making properties in accordance with AASHTO T 71. The Engineer may elect to stop aggregate production until such a time AASHTO T 71 testing has been completed.
 - (i) Aggregate, when subjected to the test for mortar-making properties, shall produce a mortar having a compressive strength at the age of 7 days equal to or greater than that developed by mortar of the same proportions and consistency made of the same cement and aggregate after the aggregate has been treated in a 3% solution of sodium hydroxide. Materials failing to produce equal or greater strength shall be unacceptable, except when determined to be acceptable under the provisions of Subsection 105.03.
- (7) Aggregate shall meet the requirement in Tables 1033.02A, 1033.02B and 1033.03C.
- (8) Lightweight pieces (measured by percent by volume values) shall not exceed 3.5%. For Class R aggregate, fine aggregate is defined as any material passing a No. 4 sieve.

Table 1033.02A

AGGREGATE SPECIFICATION RANGE	Class	Percentage Max Min	Percent Passing									
			1 1/2"	1"	3/4"	1/2"	3/8"	No.4	No.10	No.20	No.30	No.200
			Class A	--	--	--	--	100	100 92	90 64	--	40 10
Class B	--	100	--	--	--	97 77	70 50	--	40 16	3 0		
Class C	--	100	--	--	--	88 44	50 24	--	20 4	3 0		

Table 1033.02B

Aggregate Classes and Uses	
Aggregate Class	Concrete Description
A	Overlay Concrete SF
B	47BD, 47B-HE, 47B-OL, PR 1 and PR 3
C	BX

b. Coarse Aggregate:

- (1) Aggregate shall consist of Limestone, Quartzite, Dolomite, Gravel and Granite composed of clean, hard, durable, and uncoated particles.
- (2) The percent of clay lumps, shale, soft particles or lightweight pieces shall not exceed the following amounts:

Clay Lumps	0.5%
Shale	1.0%
Soft Particles	3.5%
Lightweight Pieces	3.5%

- (3) Any combination of clay lumps, shale and soft particles (all percent by weight values), plus the lightweight pieces (a percent by volume value) shall not exceed 3.5%. For Class R aggregate, coarse aggregate is defined as any materials retained on a No. 4 sieve.
- (4) Aggregate for concrete shall be free of coatings that will inhibit bond and free of injurious quantities of loam, alkali, organic matter, thin or laminated pieces, chert, or other deleterious substances as determined by the Engineer.
- (5) Aggregate for concrete shall not have a soundness loss greater than 8.0% by weight at the completion of 16 cycles of alternate freezing and thawing.
- (6) Aggregates for concrete shall have a Los Angeles Abrasion loss percentage of not more than 40.
- (7) All fractions passing the No.4 sieve shall meet quality requirement of soundness loss of not more than 10% by weight at the end of 5 cycles using sodium sulfate solution.

- (8) The coarse aggregate shall be tested according to ASTM C 1260.
 - (a) The mortar bars for the ASTM C 1260 shall not exceed 0.10% expansion at 28 days.
 - (i) If the proposed coarse aggregate exceeds 0.10% expansion at 28 days, the aggregate proportions used on the project shall be tested in accordance to ASTM C 1567.
 - a. The ASTM C 1567 mortar bars shall be composed of Interground/blended cement being used on the project.
 - b. If the expansion is greater than 0.10%, the coarse aggregate shall not be used.
- (9) Aggregate shall meet the requirements in Tables 1033.03A, B, and C.

Table 1033.03A

AGGREGATE SPECIFICATION RANGE	Class	Percent	Percent Passing									
			1 1/2"	1"	3/4"	1/2"	3/8"	No.4	No.10	No.20	No.30	No.200
AGGREGATE SPECIFICATION RANGE	Class E	Max		100	90		45	12		*4		3
		Min	100	92	66	--	15	0	--	0	--	0
	Class F	Max	--	--	100	100	90	30	8		--	3
		Min			96	40	4	0				0

*If the No. 200 sieve is less than 1.5% passing the No.20 sieve could be increased to maximum of 6% passing.

Table 1033.03B

Aggregate Classes and Uses	
Aggregate Class	Concrete Description
E	47BD, 47B-HE, PR 1 and PR 3
F	47B-OL, Overlay Concrete SF

c. Combined Aggregates:

- (1) The Contractor shall design and meet the specification requirements. It is the Contractor's responsibility to provide desirable mix properties; such as, but not limited to, workability, resistance to segregation, stable air void system, good finishing properties and good consolidation properties.
- (2) The combined blended aggregate shall meet the requirement in Table 1033.03C and 1033.03D.

Table 1033.03C

*Class R - Combined Aggregate Gradation Limits (Percent Passing)								
Sieve Size	1 1/2 inch	1 inch	3/4 inch	No.4	No.10	No.30	No. 50	No.200
Max	100	100	98.0	70.0	50.0	30.0	12.0	3.0
Min	-	92.0	85.0	45.0	31.0	8.0	2.0	0

* Refer to Subsection 1002.04, Paragraph 1.b.(8) for the traditional 47B Mix Design

Table 1033.03D

Aggregate Classes and Uses	
Aggregate Class	Concrete Description
R	47B

d. Aggregate Production and Testing:

- (1) Any change greater than 3% in the original verified constituent percentage of the combined aggregates gradation will be considered non-compliant. Any change of the combined gradation targets must remain within the Combined Aggregate Gradation Limits in Table 1033.03C. The Contractor shall resubmit a new mix design if the material is deemed non-compliant in accordance with Subsection 1002.04, Paragraph 1.
- (2) The blended gradation tolerance ranges from the approved mix design are established in Table 1033.03E.
 - (i) The Contractor shall assume the responsibility to cease operations when the specifications are not met. Production shall not be started again without the approval of the Engineer.

Table 1033.03E Blended Aggregate Production Tolerances

Sieve Size	Tolerances
No. 4 or greater	$\pm 5\%$
No. 10 to No. 30	$\pm 4\%$
No. 50	$\pm 3\%$
Minus No. 200	$\pm 1\%$

- (3) Coarse aggregate from a dry pit shall be uniformly saturated with water before it is used. The wetting shall begin 24 hours before concrete mixing to allow complete saturation.

**DOWEL BARS
(J-15-0812)**

Paragraph 1.c. of Subsection 1022.01 in the Standard Specifications is void and superseded by the following:

1. c. Both Type A and Type B coated dowel bars shall be coated with a bond breaker shown on the NDR Approved Products List, dipped in asphalt or paraffin, or greased in accordance with the specified requirements as shown in the Standard Plans.

**EPOXY COATED REINFORCING STEEL
(J-15-0509)**

Paragraph 5. of Subsection 1021.03 in the Standard Specifications is void and superseded by the following:

5. In order to protect the coated reinforcement from damage, the Contractor shall use padded or nonmetallic slings and padded straps. Bundled bars shall be handled in a manner which will prevent excessive sagging of bars which will damage the coating. If circumstances require storing coated steel reinforcing bars outdoors for more than two months, protective storage measures shall be implemented to protect the material from sunlight, salt spray and weather exposure. Coated steel reinforcing bars, whether individual bars or bundles of bars, or both, shall be covered with opaque polyethylene sheeting or other suitable opaque protective material. For stacked bundles, the protective covering shall be draped around the perimeter of the stack. The covering shall be secured adequately, and allow for air circulation around the bars to minimize condensation under the covering. Coated steel reinforcing bars, whether individual bars or bundles of bars, or both, shall be stored off the ground on protective cribbing. The bundled bars shall not be dropped or dragged. If, in the opinion of the Engineer, the coated bars have been extensively damaged, the material will be rejected. The Contractor may propose, for the approval of the Engineer, alternate precautionary measures.

**INCENTIVE PAYMENT FOR THE USE OF
RECYCLED ASPHALTIC PAVEMENT (RAP) FOR ASPHALTIC MIXTURES
(J-22-1215)**

General

This specification establishes a standard method for paying an incentive to use Recycled Asphaltic Pavement (RAP) in asphalt mixture types: SPH, SPS, SPR, SRM, SLX and LC. The intent of this specification is to provide an incentive for incorporating as much RAP into the asphalt mixtures as allowed by the respective mixture's specification.

Method of Measurement

1. The RAP Incentive Payment shall be based on the actual total of asphalt production for the entire project. A RAP Incentive Payment shall be calculated for each eligible asphaltic concrete type.

2. The following formula will be used to calculate the “RAP Incentive Factor”.

$$\text{RAP Incentive Factor} = [(A-B) \div 100] \times C \times D$$

Where:

- A = State’s Established Percent Binder – based on gradation band.
- B = Actual Percentage of Binder – added to asphaltic mixture.
- C = Unit Bid price of Binder
- D = RAP Pay Factor

3. The State’s established percent binder values (‘A’ values) are as follows:

Asphaltic Concrete Types	‘A’ Value
SPH having 0.500-inch grading band	5.2% Binder
SPS, SPL, SPR and SPR (Fine)	5.2% Binder
SLX	5.5% Binder
SPH having 0.375-inch grading band	5.8% Binder
LC	6.2% Binder
SRM	4.8% Binder

Incentive payments will be made for only the mix types list in this table.

4. The actual percentage of binder added to the particular asphaltic mixture (‘B’ value) shall be calculated as follows:

$$B = (\text{Actual Pay Tons of Binder} \div \text{Actual Pay Tons of Asphaltic Concrete}) \times 100$$

5. The Unit Bid Price of Binder (‘C’ value) is the established contract price for the performance graded binder type used to produce the mix for which the incentive is being calculated.

6. The RAP Pay Factor (‘D’ value) shall be as follows:

RAP Source	‘D’ Value
Contractor supplied RAP	0.50
State supplied RAP coming from an OFF -project source	0.35
* RAP coming from an ON -project source	0.15

* RAP coming from an **ON**-project source shall be completely utilized before allowing RAP from any other source to be used in the asphalt production. An ON-project source shall be considered any asphaltic material removed on the project.

7. Contractor supplied RAP and RAP supplied from either off-project or on-project sources shall be stored, handled and used separately. Incentive payments for RAP from these three source types shall be paid separately. The Contractor may propose a RAP consumption plan that will use multiple RAP sources concurrently and will follow the utilization hierarchy (as detailed above) upon the completion of the project.

8. The Contractor has sole responsibility for determining the quality, quantity, and uniformity of the RAP material. The maintenance of any stockpiles and processing of the RAP material shall also be the sole responsibility of the Contractor.

Basis of Payment

- | | | |
|----|--|------------------------------|
| 1. | Pay Item
RAP Incentive Payment _____ | Pay Unit
Each (ea) |
|----|--|------------------------------|
2. The overall RAP Incentive Payments shall be full compensation for all RAP materials and all hauling, handling and processing necessary to complete the work described in this section.
 3. The overall RAP Incentive Payments – for each eligible mix type and/or RAP source – shall be the RAP Incentive Factor multiplied by the total accepted tons of asphaltic concrete in which the RAP was incorporated.
 4. RAP Incentive Payment is paid for as an “established” contract unit price which is shown in the bid proposal “Schedule of Items”.
 5. The actual quantity for RAP Incentive Payment will be calculated based on the Method of Measurement stated above in this provision.

**RECYCLED ASPHALT SHINGLES FOR USE IN ASPHALTIC CONCRETE
(J-25-1215)**

Description:

Recycled Asphalt Shingles (RAS) may be used in Asphaltic Concrete. The maximum allowable (by weight) will be 10% on shoulders and 5% on mainline.

Materials:

All RAS shall consist of organic felt shingles or fiberglass shingles, obtained from a shingle manufacturing facility or tear offs. Scrap shingles shall not contain any objectionable materials (less than 1.5% by weight), including but not limited to: road tar, metal, glass, wood, plastic, brick, rubber, fabric, or any other material having similar characteristics. The RAS shall not contain harmful quantities of asbestos in accordance with guidelines provided by the Environmental Protection Agency and shall conform to all state and local regulations.

All RAS material shall be sized so that 100% (by weight) of the material passes through a 1/2-sieve, and at least 95 percent shall pass through a 3/8-inch sieve.

Before mix design approval, the following shall be submitted, along with materials and paper work for the mix design.

- I. Certification by the processor of the shingle scrap, as to the shingle scraps content and source. Certification forms are available from DOR.
- II. A 5-lb. sample of the shingle scrap material for review.

Construction Requirements:

RAS shall be stockpiled separate, from other salvaged material. Blending of scrap material in a stockpile with other salvage material is prohibited.

Scrap shingles shall be introduced into the hot mix asphalt, at the asphalt mixing plant, at the same point where Recycled Asphalt Pavement (RAP) is introduced.

Asphaltic Concrete containing RAS, regardless of RAP content, shall have a minimum of 55% virgin PG Binder for tear off shingles, and a minimum of 40% virgin PG Binder when using manufacturer waste shingles.

Basis of Payment:

The RAS material will be eligible for the RAP Incentive at a rate of 50% as specified elsewhere in the specifications.

RECYCLED ASPHALT SHINGLES (RAS) CERTIFICATION SHEET

Project

Processor of Shingle Scrap:

Name

Address

.....

Contact

Phone

We the undersigned, certify that the shingle scrap to be used on this project, was supplied directly from the processor listed below. We also certify that the material supplied consisted of only organic and/or fiberglass shingles and contains no harmful quantity of asbestos or other hazardous material in accordance with Environmental Protection Agency and all state and local regulations.

.....
Name of Contractor Shingle Scrap was Supplied to

.....
Address

.....
Authorized Representative of Processor of Shingle Material

.....
Date

PROPOSAL GUARANTY (A-40-0307)

As an evidence of good faith in submitting a bid for this work, the bidder shall indicate the type of bid bond applied to this project in accordance with the Proposal Guaranty Bid Bond Section of these Special Provisions.

* * * * *

320INFAPR17

INDEX

AGGREGATES	151
ASPHALT DENSITY GAUGE	112
ASPHALTIC CONCRETE	53
ASPHALTIC CONCRETE LONGITUDINAL JOINT DENSITY TESTING	114
ASPHALTIC CONCRETE PLACEMENT	62
ASPHALTIC CONCRETE TYPE SLX	116
BITUMINOUS LIQUID COMPOUNDS FOR CURING CONCRETE	144
BITUMINOUS PAVEMENT PATCHING	58
BORROW, WASTE, STOCKPILE, AND PLANT SITE APPROVAL	25
BRIDGE DECK REPAIR AND BRIDGE APPROACH REPAIR	67
BUY AMERICA	24
CALCIUM CHLORIDE	141
COLD WEATHER ASPHALTIC CONCRETE PLACEMENT	53
CONCRETE BRIDGE DECK/APPROACH REPAIR WITH CLASS 47BD 4000 CONCRETE	67
CONCRETE BRIDGE FLOORS (10-DAY WET CURE)	63
CONCRETE CONSTRUCTION	62
CONCRETE PROTECTION BARRIERS	51
CONSTRUCTION DETAILS	35
CONSTRUCTION METHODS	37
CONSTRUCTION STORMWATER MANAGEMENT CONTROL	35
CONTRACT TIME ALLOWANCE	22
DEFORMED METAL CENTER JOINT AND METAL KEYWAY	151
DOWEL BARS	156
DROP-OFF/COLD-MILLED TAPERED EDGE	59
ELECTRONIC SHOP DRAWINGS	30
ENVIRONMENTAL COMMITMENT	14
ENVIRONMENTAL COMMITMENT DOCUMENT	38
ENVIRONMENTAL COMMITMENT ENFORCEMENT	41
EPOXY COATED REINFORCING STEEL	157
EPOXY COMPOUNDS AND ADHESIVES	149
FLOODPLAIN PERMIT	16
GENERAL CONDITIONS	6
HYDRATED LIME FOR ASPHALT MIXTURES	117
HYDRATED LIME SLURRY FOR ASPHALT MIXTURES	120
INCENTIVE PAYMENT FOR THE USE OF RECYCLED ASPHALTIC PAVEMENT (RAP) FOR ASPHALTIC MIXTURES	157
INERTIAL BARRIER SYSTEM	51
JOINT AND CRACK SEALING FILLER	145

LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC20
 LIABILITY INSURANCE.....31
 LIMITATION OF OPERATIONS36
 LIQUID MEMBRANE-FORMING COMPOUNDS FOR CURING CONCRETE 144

MILLING FOR ASPHALTIC CONCRETE INLAY61

OPTIONAL NOTCHED WEDGE JOINT60

PARTIAL PAYMENT23
 PERFORMANCE GRADED BINDER.....77
 PLANS AND PROPOSALS31
 PORTLAND AND INTERGROUND/BLENDED CEMENT 137
 PORTLAND CEMENT CONCRETE 128
 PREFORMED WATERPROOFING MEMBRANE TYPE 172
 PROPOSAL GUARANTY.....161
 PROPOSAL GUARANTY BID BOND 19

RECYCLED ASPHALT SHINGLES FOR USE IN ASPHALTIC CONCRETE 159
 RECYCLED ASPHALT SHINGLES (RAS) CERTIFICATION SHEET 161
 RELOCATE INERTIAL BARRIER SYSTEM53
 REQUIRED SUBCONTRACTOR/SUPPLIER QUOTATIONS LIST 19

SECTION 1007 -- CHEMICAL ADMIXTURES..... 142
 SECTION 1028 - SUPERPAVE ASPHALTIC CONCRETE88
 SECTION 1029 - PERFORMANCE GRADED BINDER78
 SILICA FUME..... 144

SPECIAL PROSECUTION AND PROGRESS
 (Federal Immigration Verification System)21
 (Migratory Birds) 17
 (Subletting or Assigning of Contract).....26

STATUS OF RIGHT-OF-WAY 13
 STATUS OF UTILITIES..... 13
 STORM WATER DISCHARGES 18
 STORM WATER POLLUTION PREVENTION PLAN (SWPPP).....39

TACK COAT.....56
 TEMPORARY PAVEMENT MARKING48
 TEMPORARY TRAFFIC CONTROL DEVICES
 (Type II Barricades, Reflectorized Drums, 42" (1070 mm) Reflective Cones, and Vertical
 Panels).....46
 TEMPORARY WATER POLLUTION CONTROL 35
 TRAINING SPECIAL PROVISIONS 6
 AMENDMENT TO CONSTRUCTION TRAINING REPORT REQUIREMENTS 13
 TYPE B HIGH INTENSITY WARNING LIGHTS46

VALUE ENGINEERING PROPOSALS (VEP)20

WARM MIX ASPHALT 111
 WATER FOR CONCRETE 140
 WORK ZONE TRAFFIC CONTROL SIGNS 48
 WORKER VISIBILITY 20

